

PRC Environmental Management, Inc.  
233 North Michigan Avenue  
Suite 1621  
Chicago, IL 60601  
312-856-8700  
Fax 312-938-0118

**PRC**

*Listed under 'E'*

**PRELIMINARY ASSESSMENT/  
VISUAL SITE INSPECTION**

**THE EUREKA COMPANY  
BLOOMINGTON, ILLINOIS  
ILD 001 163 823**

**FINAL REPORT**

**Prepared for**

**U.S. ENVIRONMENTAL PROTECTION AGENCY  
Office of Waste Programs Enforcement  
Washington, DC 20460**

Work Assignment No.	:	C05087
EPA Region	:	5
Site No.	:	ILD 001 163 823
Date Prepared	:	February 24, 1992
Contract No.	:	68-W9-0006
PRC No.	:	009-C05087IL38
Prepared by	:	PRC Environmental Management, Inc. (Timothy J. Oliver)
Contractor Project Manager	:	Shin Ahn
Telephone No.	:	(312) 856-8700
EPA Work Assignment Manager	:	Kevin Pierard
Telephone No.	:	(312) 886-4448

EPA Region 5 Records Ctr.



323905

## TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
EXECUTIVE SUMMARY .....	ES-1
1.0 INTRODUCTION .....	1
2.0 FACILITY DESCRIPTION .....	3
2.1 FACILITY LOCATION .....	3
2.2 FACILITY OPERATIONS .....	3
2.3 WASTE GENERATING PROCESSES .....	7
2.3.1 Wastewater Treatment Wastes .....	7
2.3.2 Spent Filters from Plating Operations (F006) .....	12
2.3.3 Paint Wastes (F003, D001) .....	13
2.3.4 Solvent Wastes (F001, F002) .....	14
2.3.5 Parts Washer Sludge .....	15
2.3.6 Waste Oils .....	16
2.3.7 Wastes Generated by Eureka's Normal Facility .....	16
2.3.8 Oil Separator Wastes .....	16
2.4 RELEASE HISTORY .....	17
2.5 REGULATORY HISTORY .....	17
2.6 ENVIRONMENTAL SETTING .....	20
2.6.1 Climate .....	20
2.6.2 Flood Plain and Surface Water .....	20
2.6.3 Geology and Soils .....	20
2.6.4 Ground Water .....	21
2.7 RECEPTORS .....	21
3.0 SOLID WASTE MANAGEMENT UNITS .....	22
4.0 AREAS OF CONCERN .....	52
5.0 CONCLUSIONS AND RECOMMENDATIONS .....	53
REFERENCES .....	64

### Attachments

- A EPA PRELIMINARY ASSESSMENT FORM 2070-12
- B VISUAL SITE INSPECTION SUMMARY AND PHOTOGRAPHS
- C VISUAL SITE INSPECTION FIELD NOTES
- D PROCESS DESCRIPTIONS
- E MATERIAL SAFETY DATA SHEETS AND WASTE ANALYSES
- F TANK REMOVAL CERTIFICATION

## LIST OF TABLES

<u>Table</u>		<u>Page</u>
1	SOLID WASTE MANAGEMENT UNITS (SWMU) .....	8
2	SOLID WASTES .....	11
3	CURRENT IEPA PERMITS FOR FACILITY AIR EMISSIONS .....	19
4	SWMU SUMMARY .....	54

## LIST OF FIGURES

<u>Figure</u>		<u>Page</u>
1	FACILITY LOCATION .....	4
2	PLANT 1 LAYOUT .....	5
3	PLANT 2 LAYOUT .....	6

EXECUTIVE SUMMARY

ENFORCEMENT  
CONFIDENTIAL

PRC Environmental Management, Inc. (PRC), performed a preliminary assessment and visual site inspection (PA/VSI) to identify and assess the existence and likelihood of releases from solid waste management units (SWMU) and other areas of concern (AOC) at the Eureka Company (Eureka) facility in Bloomington, Illinois. This report summarizes the results of the PA/VSI and evaluates the potential for releases of hazardous wastes or hazardous constituents from SWMUs and AOCs identified. In addition, a completed U.S. Environmental Protection Agency (EPA) Preliminary Assessment Form (EPA Form 2070-12) is included in Attachment A to assist in prioritization of RCRA facilities for corrective action.

Eureka is a manufacturer of vacuum cleaners. Operations at the 24.2-acre Eureka facility began in 1958. The facility generates waste plating sludge (F006) containing chromium, nickel, and zinc; paint wastes (D001 and D002); spent Stoddard solvent (F001); and a variety of nonhazardous waste oils. The facility has an interim status container storage area permitted to store 38,500 gallons. Eureka is in the process of closing this container storage area.

The PA/VSI identified the following 48 SWMUs at the facility. No AOCs were identified.

Solid Waste Management Units

Plant 1

1. Parts Washer with Oil Separator and Drum Satellite Accumulation Area (DSAA)
2. Alkaline Parts Washer and DSAA
3. Old 1,1,1-Trichloroethane (1,1,1-TCA) Vapor Degreaser SAA
4. DSAA at Sodium Nitrate Deburrer
5. Scrap Coolant DSAA
6. Oil Recovery Centrifuge Satellite Accumulation Area (SAA)
7. Waste Oil and Stoddard Solvent Waste Accumulation Area
8. Steel Grinding Room Dust Collector
9. New Hazardous Waste Container storage area
10. Zinc Plating Area Sumps
11. Zinc Filter DSAA
12. Nickel/Chrome Plating Areas 1 and 2 SAA
13. Nickel/Chrome Plating Area 3 SAA
14. Tramp Oil in Alkali DSAA (Ni/Cr Lines 1 and 2)
15. Tramp Oil in Alkali DSAA (Ni/Cr Line 3)
16. Wastewater Treatment Plant
17. Nickel Solution Evaporation Unit
18. Sludge Drier and Dry Sludge Drum
19. Sludge Roll-off Box
20. Scrap Metal Trailer
21. Waste Oil Collection Area (Laser Cutting Machines)
22. Waste Oil DSAA (Building 6)



23. Nickel Strip Area
24. Plastic Mold Injection SAA
25. Building 5 Isopropyl Alcohol (IPA Parts Washer) SAA
26. Parts Washer Wastewater Treatment Plant
27. Paint Mixing Room DSAA
28. Phosphoric Acid Parts Washer SAA (Building 1)
29. Old Paint Solvent Storage Cabinet SAA
30. Paint Spray Room DSAA
31. Paint Chip Collection Drum
32. Stoddard Solvent Washer SAA
33. Forklift Waste Oil and Parts Cleaner SAA
34. Phosphoric Acid Parts Washer (Building 5D) SAA
35. Tool Room Stoddard Solvent and Waste Oil Collection Area
36. Chemistry Laboratory DSAA
37. Paint and Solvents Storage Area

Released under the 2016  
FOIA Improvement Act /  
Enforcement sunseting  
provision

#### Plant 2

38. Paint Strip Tanks Waste Oil SAA
39. Phosphoric Acid Derusting Area
40. Plant 2 Wastewater Treatment Plant
41. Oil Separator System
42. Oil Separator Drum Staging Area
43. Old Paint Mixing Room DSAA
44. Old Paint Spray Room Waste Cabinet
45. Plastic Injection Molding Area Waste Oil and Solvent DSAA
46. Plastic Injection Molding Area and Dried Paint Collection DSAA
47. Nonhazardous Waste Roll-off Box
48. RCRA Container Storage Area

The facility currently poses a low potential for release to ground water. All the SWMUs identified during the PA/VSI have sound secondary containment. No floor drains exist throughout the facility. Releases that may have occurred prior to paving the container storage area (SWMU 48) will be addressed during the closure of this area. Based on a review of well logs in the area, several wells were found within 1/6 mile of the facility. Based on conversations with city water officials, this area is now supplied with city water and these wells are no longer believed to be in service. A similar situation applies throughout the 3-mile radius of the facility.

All SWMUs currently have secondary containment that would prevent release to surface water. The nearest surface water bodies are some small ponds south of the facility and Sugar Creek, which is 1.5 miles north of the facility. Drinking water for the cities of Bloomington and Normal is drawn from surface water 10 miles from the facility.

The potential for an air release is low. The facility has air permits for several point sources. No violations of these permits were found during the VSI. The container storage area

(SWMU 48) is located outside. The facility is located in a residential area. No sensitive environments were identified during the PA/VSI.

The potential for a soil release is low. No soil contamination is known to exist at the facility. No soil sampling has been done at the facility to date. The facility is fenced and has 24-hour security.

No further action is recommended for the Eureka facility.

## 1.0 INTRODUCTION

PRC Environmental Management, Inc. (PRC), received Work Assignment No. C05087 from the U.S. Environmental Protection Agency (EPA) under Contract No. 68-W9-0006 (TES 9) to conduct preliminary assessments (PA) and visual site inspections (VSI) of hazardous waste treatment and storage facilities in Region 5.

As part of the EPA Region 5 Environmental Priorities Initiative, the RCRA and CERCLA programs are working together to identify and address RCRA facilities that have a high priority for corrective action using applicable RCRA and CERCLA authorities. The PA/VSI is the first step in the process of prioritizing facilities for corrective action. Through the PA/VSI process, enough information is obtained to characterize a facility's actual or potential releases to the environment from solid waste management units (SWMU) and areas of concern (AOC).

*A SWMU is defined as any discernible unit at a RCRA facility in which solid wastes have been placed and from which hazardous constituents might migrate, regardless of whether the unit was intended to manage solid or hazardous waste.*

The SWMU definition includes the following:

- RCRA-regulated units, such as container storage areas, tanks, surface impoundments, waste piles, land treatment units, landfills, incinerators, and underground injection wells
- Closed and abandoned units
- Recycling units, wastewater treatment units, and other units that EPA has generally exempted from standards applicable to hazardous waste management units
- Areas contaminated by routine and systematic releases of wastes or hazardous constituents. Such areas might include a wood preservative drippage area, a loading-unloading area, or an area where solvent used to wash large parts has continually dripped onto soils.

An AOC is defined as any area where a release to the environment of hazardous waste or constituents has occurred or is suspected to have occurred on a nonroutine and nonsystematic basis. This includes any area where such a release in the future is judged to be a strong possibility.

The purpose of the PA is as follows:

- Identify SWMUs and AOCs at the facility.
- Obtain information on the operational history of the facility.
- Obtain information on releases from any units at the facility.
- Identify data gaps and other informational needs to be filled during the VSI.

The PA generally includes review of all relevant documents and files located at state offices and at the EPA Region 5 office in Chicago.

The purpose of the VSI is as follows:

- Identify SWMUs and AOCs not discovered during the PA.
- Identify releases not discovered during the PA.
- Provide a specific description of the environmental setting.
- Provide information on release pathways and the potential for releases to each medium.
- Confirm information obtained during the PA regarding operations, SWMUs, AOCs, and releases.

The VSI includes interviewing appropriate facility staff, inspecting the entire facility to identify all SWMUs and AOCs, photographing all SWMUs, identifying evidence of releases, initially identifying potential sampling locations, and obtaining all information necessary to complete the PA/VSI report.

This report documents the results of a PA/VSI of the Eureka Company (Eureka) facility in Bloomington, Illinois. The PA was completed on July 14, 1991. PRC gathered and reviewed information from Illinois Environmental Protection Agency (IEPA) and from EPA Region 5 RCRA files. The VSI was conducted on July 17 and 18, 1991. It included interviews with Eureka representatives Don Jenkin and Dean Shoemaker and a walk-through inspection of the facility. Forty-eight SWMUs and no AOCs were identified at the facility.

PRC completed EPA Form 2070-12 using information gathered during the PA/VSI. This form is included in Attachment A. The VSI is summarized and 52 inspection photographs are included in Attachment B. Field notes from the VSI are included in Attachment C.

## **2.0 FACILITY DESCRIPTION**

This section describes the facility's location, past and present operations (including waste management practices), waste generating processes, release history, regulatory history, environmental setting, and receptors.

### **2.1 FACILITY LOCATION**


The Eureka facility is located in Bloomington, McLean County, in central Illinois (40° 28' 12" N, 88° 58' 37" W) (see Figure 1). The facility is bordered on the west by Indianapolis Street, on the north by East Bell Street, on the northeast by Maizefield Avenue, on the southeast by O'Conner Street, and on the south by Croxton Avenue. Hannah Street (U.S. Highway 150) runs north-south through the facility. The east portion of the facility is referred to as Plant 1. It includes Buildings 1, 1A, 1B, 2, 3, 4, 5, 5A, 5D, 5E, 6, 6B, 6C, 7, 11, and 12 (see Figure 2). Except for Building 11, these buildings make up one continuous structure. The west portion of the facility is referred to as Plant 2. It includes Buildings 1T, 1AT, 2T, 2AT, 3T, 3AT, 4T, 5T, 6T, 7T, and 8T (see Figure 3). Portions of Buildings 3, 5, 5A, 5T, 6, 6B, and 6C have second floors.

The facility covers a total of 24.2 acres. The area surrounding the facility is predominantly residential with some industry.

### **2.2 FACILITY OPERATIONS**

The Eureka facility manufactures vacuum cleaners. Various operations, processes, and activities are involved in making the vacuum cleaners. These are summarized below.


1. Electroplating lines plate nickel and chromium onto vacuum cleaner parts. Passive plating with zinc solutions is also used.
2. The parts are cleaned in parts washers; other materials are also used to wash parts. The parts washer also applies a coating that improves the painting process.
3. Paint is applied to parts in a dip tank or in paint booths.
4. When it is necessary to remove the outer layers of painted or plated parts, a stripping operation is employed that uses potassium hydroxide.
5. Metal parts are cut and drilled in the machine shop, generating waste metal and scrap oil.



# EUREKA SITE LOCATION


QUADRANGLE LOCATION

SCALE 1:24000



THE EUREKA COMPANY  
BLOOMINGTON, ILLINOIS

**FIGURE 1**  
**FACILITY LOCATION**



EUREKA-S.DWG - 08/28/91 - RAO

SOURCE: Eureka, 1989.



THE EUREKA COMPANY  
BLOOMINGTON, ILLINOIS

**FIGURE 2**  
**PLANT 1 - FACILITY LAYOUT**

**PRC** ENVIRONMENTAL MANAGEMENT, INC.

EUREKA-NDWG - 05/28/81 - RAO

SOURCE: Eureka, 1989.



THE EUREKA COMPANY  
BLOOMINGTON, ILLINOIS

FIGURE 3

PLANT 2 - FACILITY LAYOUT

**PRC** ENVIRONMENTAL MANAGEMENT, INC.



6. Plastic molding machines are used to make plastic parts.
7. Vacuum cleaners are assembled, packaged, and shipped.

Operations at the facility began in June 1958. The facility presently employs about 1,000 people. Wastes are handled in many different areas of the facility. These areas are described individually in Section 3.0. Table 1 lists SWMUs identified at the facility. These units are shown in Figure 2. The facility formerly had four underground storage tanks (UST). These are described below.

The gasoline UST held 560 gallons for refueling Eureka vehicles. The tank was in place from 1980 to 1989. No leaks or soil contamination were found when the tank was removed. Certification for the tank removal is included in Attachment F.

The 1,000-gallon, steel, product solvent UST was in place from 1978 to 1989. The solvent was similar in composition to that currently used in painting operations. No leaks or soil contamination were found when the tank was removed. Certification for the tank removal is included in Attachment F.

Two Plant 1 product USTs were formerly located just north of Building 11. The 500-gallon steel tanks held toluene and paint operation solvent mix. The tanks were in place from 1977 to 1988. No leaks or soil contamination were found when the tanks were removed. Certification for the tank removal is included in Attachment F.

## **2.3 WASTE GENERATING PROCESSES**

Table 2 lists the solid wastes generated at the facility. A complete discussion of each waste is contained in a 1989 IEPA inspection report (IEPA, 1989d) that is the source of most of the information presented in this section. Supplementary information was gathered during the VSI.

### **2.3.1 Wastewater Pretreatment Wastes**

Waste streams from several different operations and sources flow to a central pretreatment system (SWMUs 16, 18, and 19). Here they are treated and discharged to the Bloomington

**TABLE 1**  
**SOLID WASTE MANAGEMENT UNITS (SWMU)**

<b>SWMU Number</b>	<b>SWMU Name</b>	<b>RCRA Hazardous Waste Management Unit*</b>	<b>Status</b>
1	Parts Washer with Oil Separator and Drum Satellite Accumulation Area (DSAA)	No	Active
2	Alkaline Parts Washer and DSAA	No	Active
3	Old 1,1,1-Trichloroethane (1,1,1-TCA) Vapor Degreaser	No	Inactive
4	DSAA	No	Active
5	DSAA	No	Active
6	Oil Recovery Centrifuge	No	Active
7	Waste Oil and Stoddard Solvent Waste Accumulation Area	No	Active
8	Steel Grinding Room Dust Collector	No	Active
9	New Hazardous Waste Container Storage Area	No	Inactive
10	Zinc Plating Area	No	Active
11	Zinc Filter DSAA	No	Active
12	Nickel/Chrome Plating Areas 1 and 2	No	Active
13	Nickel/Chrome Plating Area 3	No	Active
14	Tramp Oil in Alkali DSAA (Ni/Cr Lines 1 and 2)	No	Active
15	Tramp Oil in Alkali DSAA (Ni/Cr Line 3)	No	Active
16	Wastewater Treatment Plant	No	Active
17	Nickel Solution Evaporation Unit	No	Active
18	Sludge Drier and Dry Sludge Drum	No	Active
19	Sludge Roll-off Box	No	Active
20	Scrap Metal Trailer	No	Active

21	Waste Oil Collection Area (Laser Cutting Machines)	No	Inactive
22	Waste Oil DSAA (Building 6)	No	Active
23	Nickel Strip Area	No	Active
24	Plastic Mold Injection Containment System	No	Active
25	Building 5 Isopropyl Alcohol (IPA) Parts Washer	No	Active
26	Parts Washer Wastewater Treatment Plant	No	Active
27	Paint Mixing Room DSAA	No	Active
28	Phosphoric Acid Parts Washer	No	Active
29	Old Paint Solvent Storage Cabinet	No	Inactive
30	Paint Spray Room DSAA	No	Active
31	Paint Chip Collection Drum	No	Active
32	Stoddard Solvent Washers	No	Active
33	Forklift Waste Oil Collection Area and Parts Cleaner	No	Active
34	Parts Washer and Oil Skimmer (Building 5D)	No	Active
35	Tool Room Stoddard Solvent and Waste Oil Collection Area	No	Active
36	Chemistry Laboratory SAA	No	Active
37	Paint and Solvents Storage Area	No	Active

#### **Plant 2**

38	Paint Strip Tanks	No	Active
39	Phosphoric Acid Derusting Area	No	Active
40	Plant 2 Wastewater Treatment Plant	No	Active
41	Oil Separator System	No	Active
42	Oil Separator Drum Staging Area	No	Active

43	Old Paint Mixing Room DSAA	No	Inactive
44	Old Paint Spray Room Waste Cabinet	No	Inactive
45	Plastic Injection Molding Area Waste Oil and Solvent DSAA	No	Active
46	Plastic Injection Molding Area Parts Washer and Dried Paint Collection Drum	No	Active
47	Nonhazardous Waste Roll-off Box	No	Active
48	RCRA Container Storage Area	Yes	Active

---

**Note:**

- \*** A RCRA hazardous waste management unit is one that currently requires or formerly required a RCRA Part A or Part B permit application.
-

**TABLE 2**  
**SOLID WASTES**

<u>Waste/EPA Waste Code</u>	<u>Source</u>	<u>Primary Management Unit*</u>
Wastewater and wastewater treatment sludge/F006	Plating water treatment operations	16, 18, and 19
Spent Ni/Cr/Zn plating filters/F006	Plating operations	10, 11, 12, and 13
Solvent-Reduced paint/F003, D001	Painting operations	27, 29, 30, 31, 43, 44, and 48
Spent Stoddard solvent/F001, F002	Maintenance and metal forming operations	7, 32, 33, 34, and 48
Water-reduced paint/NA**	Painting operations	46, 48
Paint strip sludge/NA	Painting operations	38, 40, and 47
Paint pigments and alkali/D002	Painting operations	48
Parts washer sludge/NA	Wastewater treatment operations	26 and 40
Tramp oil/NA	Plating operations	14, 15, 41, and 48
Waste oil/NA	Facility maintenance	1, 2, 4, 5, 6, 7, 22, 24, 28, 33, 34, 35, 38, 41, 42, 45, and 48
Spent paint filters/NA	Painting operations	47
Grinder sludge/NA	Metal forming operations	48
Oil separator sludge/NA	Waste oil treatment operations	48
Dry paint overspray/NA	Painting operations	47
Metal Dust/NA	Metal Working	8
Scrap Metal/NA	Throughout facility	20
IPA Paint sludges/NA	IPA Parts washer	25

**Note:**

\* Primary management unit refers to a SWMU that currently manages or formerly managed the waste.

\*\* Nonapplicable (NA) designates a nonhazardous waste stream.

Normal Water Reclamation District (BNWRD). Treatment in tanks includes chrome reduction, flocculation, clarifying, neutralization, and sludge thickening, and involves sludge filter presses and a sludge drier. The sludge resulting from wastewater treatment is hazardous waste and classified as F006 waste. A flow diagram of the wastewater pretreatment process is included in Attachment D. The following sections discuss the areas at the facility that discharge wastewater to the wastewater pretreatment system.

Eureka has three electroplating lines that apply nickel and chromium plating to vacuum cleaner parts (SWMUs 12 and 13). These lines generate wastes that are discharged via aboveground piping to the pretreatment system. The wastes include rinse water, acid and alkaline cleaning bath solutions, and plating solutions. Sediment generated in the bottoms of the baths is also sent to the pretreatment system.

Wastewater is also generated from a zinc barrel electroplating line (SWMUs 10 and 11). The wastewater, which includes rinse water, acid and alkaline cleaning bath solutions, and plating solutions, is sent to the pretreatment system. Sediment generated in the baths is also sent to the pretreatment system. The zinc line has a chrome dip tank for corrosion prevention. A part can go to one chrome dip tank and get blue finish; another chrome dip tank previously used for gold finish is now used for water rinsing only. Neither of the chrome dip tanks has been electrically charged. Baths associated with the chrome-dipping operation discharge to the on-site pretreatment system.

The nickel and chrome plating occasionally has to be removed from a part. Rinse waters and acid and alkaline solutions from the plating-strip operation are discharged to the pretreatment system. When sediment in the stripping tank is cleaned out, the stripping solution (hydrochloric acid) is pumped to a tank and the sediment is flushed to the pretreatment system. The stripping solution is then returned to the tank, and the operation is continued.

Wastewater from the RotoFinish operation also discharges to the pretreatment system. Metal parts are deburred by the RotoFinish machines. The machines are doughnut-shaped devices with an outer compartment filled with pieces of abrasive material. Parts are placed in the compartment with the abrasive pieces, and then the machine vibrates. An alkaline cleaning solution is added to the compartment during the machine operation.

### **2.3.2 Spent Filters from Plating Operations (F006)**

Paper filters coated with diatomaceous earth and activated carbon are used to screen particulates and organics out of nickel and chrome plating solutions. The filtering device is a

metal cylinder that holds about 22 paper filters. When the paper filters become too dirty to effectively remove the organics, they are placed in a drum (SWMUs 12 and 13) located next to the filtering devices. A small amount of lime is added to the spent filters being accumulated to neutralize the waste. Bags that serve as screens around the nickel chips in the electroplating baths are also deposited in the drum when they are no longer effective. When the drum is full, it is emptied into the roll-off box (SWMU 19) used to accumulate F006 waste from the pretreatment system.

The zinc plating line also has a filtering system (SWMUs 10 and 11). The tube filters used contain three bags. When the bags need to be replaced, they are allowed to dry over a pit connected to the pretreatment system (SWMUs 16, 18, and 19) and then collected in a drum. When the drum is full it is deposited in the roll-off box.

### **2.3.3 Paint Wastes (F003, D001)**

Eureka can apply a high-solids, solvent-based paint to vacuum cleaner parts electrostatically in automatic paint booths or with hand-held spray guns. A solvent composed of methyl isobutyl ketone (MIBK) is used to flush the paint hoses and spray guns on a daily basis. Toluene was used as the cleaning solvent in the past. Spent solvent and paint are collected in small containers that are emptied into 55-gallon drums in metal cabinets near the spray booths (SWMU 27, 30, 31, 43, and 44). Full drums are taken to the container storage area.

Some vacuum cleaner parts are conveyed through a dip tank containing a water-based paint. When Eureka cleans the tank, wastes are pumped into drums which are stored in the container storage area (SWMU 48). Eureka is currently handling the water-reduced paint as hazardous waste, although analysis has revealed no hazardous characteristics. This waste is not mixed with any hazardous wastes. A waste analysis for this waste is included in Attachment E.

Eureka has a paint-stripping operation in which paint is removed from production items, paint hooks, and paint racks, and then accumulated in SWMU 38. A potassium hydroxide solution is used to remove the paint. This operation is conducted in Building 7 (formerly in Building 5). Reusable alkaline material is taken out of the decant tank and is placed in either the hook or rack paint-stripping tank. Material that settles to the bottom of the decant tank is drawn out and disposed of as hazardous waste (D002) in drums. This material is not mixed with any other waste. These drums are stored in the container storage area (SWMU 48) before treatment and disposal off-site. The material is called paint pigments in alkali. A waste analysis for this waste is included in Attachment E.

The rinse water from the stripping baths overflows to a supply tank that feeds the vacuum filter. The vacuum filter removes suspended solids. Sludge generated from the vacuum filter is called paint strip sludge. A waste analysis for this waste is included in Attachment E. Wastewater discharged from the vacuum filter goes on to be further treated at the parts washer wastewater treatment plant (SWMU 26) located in the west room of Building 4T. Paint strip sludge is accumulated in a "Gaylord Box" (a plastic-lined cardboard box) near the strip pad that is placed in the container storage area. The Gaylord Box is placed into a roll-off box (SWMU 47) and is sent to McLean County Landfill for disposal. This waste is neutralized as part of the treatment system and does not exhibit any hazardous characteristics.

Fiberglass paint filters are routinely removed from the dry booths as the filters become saturated with overspray. Chemical analyses of the spent filters have indicated that they are nonhazardous. A waste analysis for this waste is included in Attachment E. The spent filters are placed in a Gaylord Box that is placed into a roll-off box (SWMU 47). The are disposed of at the McLean County Landfill.

Dried paint on paint hooks and racks is "knocked off" before a part is stripped and collected in a drum (SWMU 31). The dried paint is collected along with paint overspray from the paint booths and is disposed of with the paint strip sludge.

#### **2.3.4 Solvent Wastes (F001, F002)**

Eureka once employed 1,1,1-trichloroethane (1,1,1-TCA) in a variety of processes. All use of this solvent has been discontinued. Previously, a small vapor degreaser with 1,1,1-TCA was used in the metal shop (Building 7) to clean oil, dirt, and grease off metal parts, thus generating and accumulating spent 1,1,1-TCA. The vapor degreaser held about 80 gallons of solvent. Waste solvent removed from the degreaser was stored in a drum on the east side of Building 7 (SWMU 3).

A small parts washer was also located in the eastern portion of Building 7. The parts washer held about 10 gallons of 1,1,1-TCA solvent. Waste solvent from the parts washer was collected in a drum kept next to the east central wall of Building 7 (SWMU 3).

The solvent, 1,1,1-TCA, was used to dissolve silicon rubber gaskets off parts (SWMU 40). The solvent was collected in a drum in the Plant 2 Wastewater Treatment Area.

The facility also received spent 1,1,1-TCA from Eureka's Normal facility. The Normal facility uses 1,1,1-TCA to clean resin off field coils and armatures and to clean trickle lines to



prevent clogging. This waste was manifested and sent to the Bloomington facility for storage in SWMU 48.

Spent Stoddard solvent is used in several areas of the facility. Several small safety containers of Stoddard solvent used to clean parts are accumulated in Building 7 (SWMU 7). The spent solvent is accumulated in a drum kept next to the east central wall of Building 7 (SWMU 7). Stoddard solvent is also used in a 25-gallon tank in the tool room (SWMUs 32 and 34) to remove grease and oil from metal parts. There are also other areas in the maintenance and machine shops where Stoddard solvent is used.

A small container of Stoddard solvent is located in the Mule Barn where forklifts are serviced in Building 3 (SWMU 33). About 5 gallons of spent Stoddard solvent is generated at this location every 6 months (SWMU 33). A drum of spent Stoddard solvent is located in a cabinet south of Building 3. This is the designated satellite accumulation point for spent solvent for Building 3 (SWMU 33).

Spent Stoddard solvent is also generated at the Normal facility from parts cleaning in its maintenance department. This spent solvent has been shipped to the Bloomington facility in the past. It was stored at the Bloomington facility until it could be transported to a recycler. This activity was discontinued in 1990.

### **2.3.5            Parts Washer Sludge**

Prior to painting, some metal parts go through a parts washing process at the facility. Phosphoric acid is used to apply a surface coating to a part, allowing paint to adhere better. There are currently two parts washers that use phosphoric acid (SWMUs 28 and 34) and solution treatment centers (SWMUs 26 and 40) at the facility. Rinse waters and waste acid solution are sent to the treatment centers for neutralization and filtering before they are discharged to the BNWRD sewer system. Sludge collects on the paper cartridge filters during the treatment process which are then disposed of as nonhazardous waste.

The sludge generated in the treatment center in the northern portion of Building 1B is considered nonhazardous. Analysis has indicated that it does not exhibit hazardous waste characteristics.

### **2.3.6 Waste Oils**

At the beginning of each nickel/chrome plating line is an alkaline bath used to remove oil and grease from parts prior to plating. The bath solution is regenerated by piping it to an adjacent centrifuge that separates oil and grease from the solution. The solution circulates back to its original tank. Oil and grease generated from the treatment is called tramp oil. A waste analysis for this waste is included in Attachment E. Tramp oil is collected in drums (SWMUs 14 and 15) and stored. Full drums are taken to the oil separator located in the west room of Building 4T (SWMU 40). Tramp oil is combined with scrap cimcool (a water-soluble coolant) and ferric chloride in the oil separator. Sulfuric acid then is added, and the contents are mixed. The oil layer is removed for recycling, the water layer is discharged to the BNWRD sewer system, and the sludge is drained into drums for off site disposal.

Straight oil (non-water-soluble) is used for various lubricating jobs at the facility. Some cutting and drawing machines apparently use lubricating oils, as do vehicle crankcases, machine gearboxes and hydraulic systems. Waste oil is generated when lubricating oils are replaced. Different waste oils are mixed and stored in 55-gallon drums in the container storage area (SWMU 48). Waste oil has also been received from Eureka's Normal facility in the past.

### **2.3.7 Wastes Generated by Eureka's Normal Facility**

In the past, the Bloomington facility has accepted waste from Eureka's Normal facility. Because the Bloomington facility is closing its RCRA container storage area, this practice will be discontinued. Water-soluble resin is used at the Normal facility to make parts for vacuum cleaners. Both hardened scrap resin and resin in water have been manifested to the Bloomington facility in the past. The resin and water waste is generated from cleaning resin application equipment with water. The Bloomington facility had a treatment unit to evaporate water from the resin and water waste. The scrap resin was disposed of at McLean County Landfill.

Eureka's Normal facility also generates a food-grade adhesive waste. The adhesive is used to seal shipping boxes. In the past, empty drums that had held the adhesive were brought to the Bloomington facility where they were scraped out. The residue was accumulated in a waste drum that was eventually shipped off site (SWMU 48).

### **2.3.8 Oil Separator Wastes**

Grinding machines used to work on metal parts generate a waste consisting of metal fines and a small amount of adhering cooling oil. Eureka has a centrifuge where the metal scraps are

spun to remove excess oil. The scrap oil is then accumulated in 55-gallon drums (SWMU 6) for treatment in the oil separator. Non-water-soluble scrap oil and tramp oil are also treated in the oil separator (SWMU 41). An oil-skimming belt removes the oil from the treatment tank. The remaining sludge is treated with lime, and absorbent material is added. Spent filters from the oil separator are accumulated in drums in the area before being stored in the container storage area (SWMU 48) before off-site treatment and disposal.

## **2.4 DOCUMENTED RELEASE HISTORY**

On August 2, 1985, 25 gallons of trichrome additive was released from a drum inside the facility (IEPA, 1985a). The spill flowed under a door, off the facility, onto a playground, and into a tile drain. The tile drain was connected to a storm sewer that discharges into Sugar Creek about 2 miles from the Eureka facility. Blue precipitate from the spill was observed 1,000 to 1,500 feet downstream of the storm sewer outlet. About 22,000 gallons of contaminated water was removed from 500 feet of the creek and taken back to the Eureka facility to be treated in its water treatment system to remove the contamination. The facility also flushed the storm water system to remove any additional contaminants. Straw used to contain the precipitate was disposed of off site. The area where the spill occurred has now been trenched, and trichrome additive is no longer used at the facility. No other spills have been documented.

## **2.5 REGULATORY HISTORY**

On September 5, 1978, Eureka submitted to IEPA an application for a permit to develop a solid waste management area (Eureka, 1980b). The application was for a transfer and storage area for drummed wastes. On August 13, 1980, the facility submitted a Notification of Hazardous Waste Activity as a generator; treatment, storage, or disposal (TSD) facility, and transporter of a wide variety of F, U, P, and D listed hazardous wastes (Eureka, 1980a). Many of these wastes were misclassified by the facility and accordingly do not appear on subsequent notifications. On November 18, 1980, the facility filed a RCRA Part A permit application for storage of 38,500 gallons of D001, D002, D003, D006, D007, F001, and F006 listed wastes in its (SWMU 45) container storage area (Eureka, 1980c). The permit application also listed 158,400 gallons per day of tank treatment (T01) of D006, D007, and F006 wastes (SWMU 16). IEPA granted a developmental permit (1980-41-DE) and an operational permit (1980-41-OP) to Eureka to develop and operate a special waste storage area on December 3, 1980 (IEPA, 1980a and 1980b). On March 12, 1985, the facility submitted a revised Part A permit application that added F002 listed waste and deleted D006 waste (Eureka, 1985b).

Violations of various IEPA and RCRA requirements found during inspections in 1985 resulted in issuance of Compliance Inquiry Letters on September 23, 1985 (IEPA, 1985c), and September 2, 1986 (IEPA, 1986d). Continuing violations led to a pre-enforcement conference on November 14, 1986; the violations were apparently resolved. On October 21, 1987, IEPA again sent Eureka a Compliance Inquiry Letter for apparent violations identified during an August 20 and 21, 1987, inspection (IEPA, 1987b). The apparent violations included nondetermination of waste streams as hazardous waste [35 Illinois Administrative Code (IAC) 722.111] and an inadequate waste analysis plan [35 IAC 725.113(b)]. A Notice of Violation regarding these violations was sent to Eureka on December 29, 1987 (IEPA, 1987c). The violations were apparently resolved by a January 18, 1988, response letter from Eureka (Eureka, 1988). A March 29, 1989, IEPA inspection discovered additional apparent violations involving unlabeled waste drums, an open roll-off container used to collect hazardous waste sludge, and accumulation of hazardous wastes in excess of 55 gallons in satellite accumulation areas (IEPA, 1989a). These violations were apparently resolved.

Eureka submitted a closure plan dated April 29, 1991, that was approved on June 25, 1991 (Eureka, 1991b). Closure activities must be completed by January 1, 1992, and must include decontamination and sampling of the container storage pad and surrounding area (SWMU 48). Eureka will begin using a new hazardous waste drum storage area (SWMU 9) for hazardous waste storage and will ship all wastes before the 90-day limit is reached.

IEPA granted a water pollution control permit (1984-EP-3004) to Eureka in 1984 to operate a water pollution control wastewater pretreatment system. This permit allowed discharges totaling 387,000 gallons per day (gpd) to the BNWRD system from three different outlets, which is regulated under permit BNWRD 91-02. The outlets are located at Maple Street, McClun Street, and the Shell Plant. Permit BNWRD 91-02 allows a total discharge of 255,000 gpd design average flow (DAF) and 365,000 gpd design maximum flow (DMF). Discharges are regularly monitored for various heavy metals, cyanide, pH, and biological parameters.

IEPA has issued permits for several facility waste streams, which are summarized in Table 2. Table 3 lists IEPA air emission permits held by the facility.

Eureka also has a National Pollutant Discharge Elimination System (NPDES) permit (IL0002771) that regulates three non-contact cooling water (003) and storm water (005 and 006) outfalls on Goose Creek. Discharges are monitored for flow, pH, temperature, biodegradable oxygen demand, and total suspended solids.

**TABLE 3**  
**CURRENT IEPA PERMITS FOR FACILITY AIR EMISSIONS**

<b><u>PERMIT NO.</u></b>	<b><u>EXPIRATION DATE</u></b>	<b><u>ITEM PERMITTED</u></b>
74030104	03/27/95	Nickel, chrome strip line
74030119	01/11/95	Automatic plater No. 1
74030121	09/21/93	Annealing room--salt furnace and bake ovens
74030123	10/22/91	Wash, paint, bake line 131
74030125	05/15/95	Vapor degreaser
74030126	08/01/93	Five tool room grinders
74030130	10/22/91	Wash, paint, bake line 132
74030131	05/16/94	Three gas-fired boilers
74060129	06/30/92	Automatic plater No. 2
74060130	12/06/93	Two alkali strip tanks
74060131	07/25/93	Dust room, field engineering
75030071	07/25/93	Paint dip and parts washer
76080019	06/30/92	Automatic plater No. 3
77050045	01/09/96	Wax dip booth, dept. 21
81080043	01/31/92	Acid chloride zinc line
91020094	03/12/96	Derust tank and buffing jack
81080045	05/19/96	Two alkali strip tanks
81080046	02/05/92	Chrome destruct and treatment tanks
86010023	01/27/96	Sludge dryer, reducer

## **2.6 ENVIRONMENTAL SETTING**

This section describes the climate, floodplain and surface water, geology and soils, and ground water in the vicinity of the Eureka facility.

### **2.6.1 Climate**

The climate of McLean County is generally continental with hot summers and cold winters. The average temperature is 72.6°F in July and 35.8°F in February. The average annual precipitation is 35 inches, and the average annual evaporation rate is 32 inches. Winds are generally from the west at 8 to 10 miles per hour. The 1-year, 24-hour maximum rainfall value is 2.6 inches.

### **2.6.2 Floodplain and Surface Water**

The facility is not located in a flood plain (FEMA, 1984). The only surface water within 2 miles includes some small ponds south of the facility and Sugar Creek about 1.5 miles north of the facility; Goose Creek, the point of discharge for the facility's NPDES outfalls, is about 2 miles south of the facility. These bodies of water are used for recreation. Bloomington and Normal receive their water supplies from Lake Bloomington (Money and Hickory Creeks) and Lake Evergreen (Six Mile Creek), which are located about 10 miles northeast and northwest of the facility, respectively.

### **2.6.3 Geology and Soils**

McLean County topography and surface geology are results of the Illinois glacier and early Wisconsin-age glaciation. The average depth of glacial till over McLean County is 200 feet. Soils in the area are typically upland prairie soils composed of brown silt-loam (Hopkins, 1915). These soils are well drained. Well records for the area indicate topsoil over yellow clay to a depth of about 120 feet; this is underlain by alternating layers of sand and clay to 250 to 275 feet (Illinois State Water Survey, 1991).

The bedrock underlying the glacial till is Pennsylvanian shale containing thin beds of limestone, sandstone, and coal. (The shale may be water yielding, depending on the type of composition of the beds.)

#### **2.6.4 Ground Water**

A review of well records indicate that ground water in the area is found at a depth of 130 to 140 feet in sand and gravel lenses. These wells have been used for domestic and industrial purposes in the past. These wells are reportedly no longer used (Bloomington Water Department, 1991). The Bloomington water supply is drawn from surface water. Ground water flow direction is unknown (Illinois State Water Survey, 1991).

#### **2.7 RECEPTORS**

The facility is entirely fenced and is under 24-hour surveillance by security personnel. Records indicate several industrial and domestic water wells were discovered within 1/2 mile of the facility. Based on conversations with city water officials, this area is now supplied with city water and these wells are no longer believed to be in service. A similar situation applies throughout the 3-mile radius of the facility. All the wells were finished in sand and gravel aquifers at 130 to 140 feet with 120 feet of confining clay above. No surface water pathways exist near the facility except through the city sewer. The facility is located in a residential area. The population of Bloomington is approximately 50,000. Drinking water for the cities of Bloomington and Normal is drawn from surface water 10 miles from the facility. No sensitive environments were identified within three miles of the facility.

### 3.0 SOLID WASTE MANAGEMENT UNITS

This section describes the 48 SWMUs identified during the PA/VSI. The following information is presented for each SWMU: description of the unit, dates of operation, wastes managed, release controls, history of release, and PRC observations.

#### Plant 1

##### **SWMU 1**

##### **Parts Washer with Oil Separator and DSAA**

**Unit Description:** This unit is located in the northwest corner of Building 7. A biodegradable solvent is used to remove oil from metal parts. An oil separator removes oil from the above solution, which is then collected in a 55-gallon drum (see Photograph No. 1). The rest of the solution is reused.

**Date of Startup:** This unit was put in operation in May 1990.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** This unit manages nonhazardous waste oil removed from metal parts. The solvent consists of approximately 5 percent RP-775 solution in tap water. The Material Safety Data Sheet (MSDS) for RP-775 is included in Attachment E.

**Release Controls:** This unit is located on concrete within the building.

**History of Release:** There have been no documented releases from this SWMU.

**Observations:** This unit was in operation at the time of the VSI. There was no visual evidence of release. The unit appeared to be in good condition. The facility stated that the drum is filled about every 3 months.

##### **SWMU 2**

##### **Alkaline Parts Washer and DSAA**

**Unit Description:** This unit is located at the north end of Building 7. The small parts washer uses the same solvent as SWMU 1 to remove oil from metal



parts. A 2- to 3-gallon pail is used to collect waste oil removed from the parts (see Photograph No. 2).

**Date of Startup:** This unit was put in operation in May 1990.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** This unit manages nonhazardous waste oil removed from metal parts.

**Release Controls:** This unit is located on concrete within the building.

**History of Release:** There have been no documented releases from this unit.

**Observations:** This unit was in operation at the time of the VSI. There was no visual evidence of release. The unit appeared to be in good condition.

### **SWMU 3**

#### **Old 1,1,1-TCA Vapor Degreaser**

**Unit Description:** This unit was located in the northwest part of Building 7 just south of the present location of SWMU 1. The unit was formerly used to remove oil from metal parts (see Photograph No. 3). Waste solvent was accumulated in a 55-gallon drum and moved to SWMU 48 for storage and off-site disposal when full.

**Date of Startup:** This unit was put in operation in 1981.

**Date of Closure:** This unit was closed in 1990.

**Wastes Managed:** The unit manages nonhazardous waste oil removed from metal parts.

**Release Controls:** This unit was located on concrete within the building.

**History of Release:** There were no documented releases from this unit.

<b>Observations:</b>	<b>This unit has been removed and was not viewed during the VSI. Presently, a sodium nitrate deburrer is located near the area of the unit. Crystals from the deburrer were observed on the floor around the area where the unit was located.</b>
<b>SWMU 4</b>	<b>DSAA at Sodium Nitrate Deburrer</b>
 <b>Unit Description:</b>	 <b>This unit is located in the northwest portion of Building 7 near the former location of SWMU 3. The deburrer is used to debur metal parts with sodium nitrate. When the deburrer is cleaned, the solution is removed, placed in drums, and moved to the wastewater treatment system.</b>
 <b>Date of Startup:</b>	 <b>This unit was put in operation in 1968.</b>
 <b>Date of Closure:</b>	 <b>This unit is currently operational.</b>
 <b>Wastes Managed:</b>	 <b>This unit manages a solution of 5 to 10 percent sodium nitrate. The waste solution is disposed of in the wastewater treatment system.</b>
 <b>Release Controls:</b>	 <b>This unit is located on concrete within the building.</b>
 <b>History of Release:</b>	 <b>Crystals apparently from this unit were noted on the floor during the VSI. No other releases have been documented.</b>
 <b>Observations:</b>	 <b>This unit was in operation at the time of the VSI. A crystal substance was observed on the floor around the deburrer.</b>
<b>SWMU 5</b>	<b>Scrap Coolant DSAA</b>
 <b>Unit Description:</b>	 <b>This unit is a 55-gallon drum used to collect scrap coolant from processes conducted in the northern portion of Building 7. The waste is sent to the oil recovery system in Plant 2 (SWMU 41) (see Photograph No. 4).</b>
 <b>Date of Startup:</b>	 <b>This unit was put in operation in 1981.</b>

**Date of Startup:** This unit was put in operation in 1981.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** This unit stores spent Stoddard solvent (D001) and nonhazardous waste oil.

**Release Controls:** The drums are located on pallets over a concrete floor inside the building.

**History of Release:** There have been no documented releases from this unit, although occasional small spills do occur.

**Observations:** There were three covered drums present in this unit during the VSI. The drums were apparently being filled using a funnel. Some oil-dry was spread on the floor to capture a spill.

#### **SWMU 8**

#### **Steel Grinding Room Dust Collector**

**Unit Description:** This unit is used to collect metal dust from various metal-working operations. The exhaust is vented to the outside air (see Photograph No. 7).

**Date of Startup:** This unit was put in operation in 1981.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** This unit manages metal dust.

**Release Controls:** This unit has a fabric filter to remove metal dust from vacuum exhaust.

**History of Release:** There have been no documented releases from this unit.

**Observations:** This unit was not being used at the time of the VSI, but it appeared to be in good condition.

**SWMU 9****New Hazardous Waste Container Storage Area**

**Unit Description:** Eureka has purchased six cabinets to replace the hazardous waste container storage area (SWMU 48) and placed them outside the east wall of Building 7. Each cabinet can hold 10 drums and is self-contained (see Photograph No. 8).

**Date of Startup:** Eureka will start to use this unit in late 1991 for less than 90 day storage.

**Date of Closure:** This unit has not yet been used.

**Wastes Managed:** This unit will manage hazardous waste from throughout the facility.

**Release Controls:** Each cabinet is ventilated and can contain a 220-gallon spill. The cabinets are all located on asphalt.

**History of Release:** There have been no releases from this unit. It has not yet been used.

**Observations:** The cabinets were new. Eureka was waiting for fire extinguishers before using the cabinets.

**SWMU 10****Zinc Plating Area Sumps**

**Unit Description:** The zinc barrel plating line is located in the east portion of Building 10. Sumps located below the tanks receive spill and overflow material, which is occasionally pumped to the wastewater treatment plant (SWMU 16). A cylindrical filter is located behind the plating tanks that removes sludge from the plating solutions (see Photographs No. 9 and 10). A description of this process is included in Attachment D.

**Date of Startup:** This unit was put in operation in 1981.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** This unit manages zinc and chromium waste plating solutions.

**Release Controls:** The sump receives any spills or overflows from the area.

**History of Release:** There have been no documented releases from this area.

**Observations:** This unit was in operation at the time of the VSI and appeared to be in good condition. Ventilation is to the roof, without treatment.

**SWMU 11**

**Zinc Filter DSAA**

**Unit Description:** Spent filters from the zinc plating operation are collected in a 55-gallon drum in the southeast portion of Building 6B. The waste is added to the sludge roll-off box (SWMU 19). A drum is filled about once every 4 months (see Photograph No. 11).

**Date of Startup:** This unit was put in operation in 1981.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** This unit manages sludge from zinc plating solution. The waste is collected and disposed of with other electroplating wastewater sludges as hazardous waste (F006).

**Release Controls:** This unit is located on a concrete floor within the building.

**History of Release:** There have been no documented releases from this unit.

**Observations:** The drum was covered and appeared to be in good condition during the VSI.

**SWMU 12**

**Nickel/Chrome Plating Areas 1 and 2 SAA**

**Unit Description:** This unit is made up of two nickel/chrome plating lines located in Building 6B. Overflow from the tanks is caught and pumped to the wastewater treatment plant. Spent filters on the nickel and chromium plating tanks are removed and collected in a 55-gallon

drum next to the plating line. A description of the process is included in Attachment D (see Photograph No. 12).

**Date of Startup:** Plating line 1 has been used since 1961. Plating line 2 has been used since 1973.

**Date of Closure:** The unit is currently operational.

**Wastes Managed:** This unit manages plating solution wastes and filter sludges (D007). A separate, multi-plate filter is used on the chrome plating bath and on the nickel plating bath on each plater. Each plate has a reusable polypropylene filter; a cellulose filter aid is added to improve filtering ability, and carbon is added to remove organic contaminants. When pressure in the filters builds to a set point, the plates are removed and the filtrate is scraped into a 55-gallon collection drum.

**Release Controls:** The entire unit is located on concrete within the building. The unit is ventilated to the outside air. Spills from the plating tanks are collected and sent to the wastewater treatment plant (SWMU 16). The three sumps have capacities of 740 gallons (chrome), 314 gallons (nickel), and 1,200 gallons (acid and alkali).

**History of Release:** There have been no documented releases from the areas included within this SWMU.

**Observations:** This unit was in good condition during the VSI. Plating line 1 was the only one in operation. The drums were covered, and there was no visual evidence of release.

#### **SWMU 13**

#### **Nickel/Chrome Plating Area 3 SAA**

**Unit Description:** See the SWMU 12 unit description. Plating line 3 is slightly larger than plating lines 1 and 2 (see Photograph No. 16).

**Date of Startup:** This unit was put in operation in 1976.

**Date of Closure:** This unit is currently operational.

<b>Wastes Managed:</b>	See the SWMU 12 wastes managed.
<b>Release Controls:</b>	This unit is located on concrete within the building. The three sumps have capacities of 800 gallons (chrome), 2,900 gallons (nickel), and 4,300 gallons (acid and alkali).
<b>History of Release:</b>	There have been no documented releases from this unit.
<b>Observations:</b>	This area appeared to be in good condition during the VSI. Drippings on the floor from metal parts were being collected with oil-dry. Facility representatives stated that the oil-dry was disposed of with oil separator sludge.
 <b>SWMU 14</b>	
<b>Unit Description:</b>	Tramp Oil in Alkali DSAA (Ni/Cr Lines 1 and 2)  A potassium hydroxide wash tank removes oil from metal parts before they are plated in Ni/Cr lines 1 and 2. The oil is removed from the alkaline solution by a centrifuge, and the waste, "tramp oil in alkali," is collected in a 55-gallon drum in this unit (see Photograph No. 13).
<b>Date of Startup:</b>	This unit was put in operation in 1972.
<b>Date of Closure:</b>	This unit is currently operational.
<b>Wastes Managed:</b>	This unit manages tramp oil in alkali (waste oil removed from metal parts).
<b>Release Controls:</b>	This unit is located on concrete within the building.
<b>History of Release:</b>	There have been no documented releases from this unit.
<b>Observations:</b>	The drum was covered during the VSI. There was no evidence of release.

**SWMU 15****Tramp Oil in Alkali DSAA (Ni/Cr Line 3)**

**Unit Description:** See the SWMU 14 unit description (see Photograph No. 15).

**Date of Startup:** This unit was put in operation in 1976.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** See the SWMU 14 wastes managed.

**Release Controls:** This unit is located in a diked area on concrete within the building.

**History of Release:** There have been no documented releases from this unit.

**Observations:** The collection drum was covered during the VSI. However, the drum was resting on top of the concrete ledge forming the containment dike.

**SWMU 16****Wastewater Treatment Plant**

**Unit Description:** This unit handles liquid waste from plating operations and alkaline waste from rotofinish deburring operations. The unit is located in Building 6B. Its operation is discussed in Section 2.3. A process flow diagram is included in Attachment D. Treated water is discharged to the BNWRD sewer system. Sludge is sent to SWMU 18 (see Photograph No. 17).

**Date of Startup:** This unit was put in operation in 1984.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** This unit manages plating solutions containing various heavy metals (D007).

**Release Controls:** This unit is located on concrete within the building. The discharge is monitored. Any release would flow to a nearby sanitary sewer and be treated by the BNWRD treatment plant.



<b>History of Release:</b>	There have been no documented releases from this unit.
<b>Observations:</b>	This unit was in operation during the VSI. No evidence of release was observed.
<b>SWMU 17</b>	<b>Nickel Solution Evaporation Unit</b>
<b>Unit Description:</b>	Two rinse tanks are used to rinse excess nickel from metal parts after the plating process. The tanks are continuously emptied and replenished by a nickel recovery system. Rinse solutions are sent to the evaporation unit, where the nickel and water are separated. The nickel is returned to the plating solution and the water is returned to the rinse tanks (see Photograph No. 18). Material that cannot be recovered by this unit was being collected in a concrete secondary containment structure during the VSI.
<b>Date of Startup:</b>	This unit was put in operation in 1980.
<b>Date of Closure:</b>	This unit is currently operational.
<b>Wastes Managed:</b>	This unit recycles used rinse solution containing nickel. Wastes from the evaporation unit were being collected on the surrounding concrete secondary containment structure during the VSI.
<b>Release Controls:</b>	The unit is located on a concrete floor within the Building 6B, and the area is diked.
<b>History of Release:</b>	There have been no documented releases from this unit.
<b>Observations:</b>	Waste nickel solution was dripping from this unit during the VSI.
<b>SWMU 18</b>	<b>Sludge Drier and Dry Sludge Drum</b>
<b>Unit Description:</b>	This unit is located in Building 6B. It removes liquid from sludge generated in the wastewater treatment tank. The sludge is accumulated in a 55-gallon drum and is then added to the sludge roll-off box. The liquid removed is returned to the wastewater treatment plant (see Photograph No. 19).

**Date of Startup:** This unit was put in operation in 1984.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** This unit manages plating sludge (F006) from the wastewater treatment plant.

**Release Controls:** This unit is located on a concrete floor within the building.

**History of Release:** There have been no documented releases from this unit.

**Observations:** This unit appeared to be in good condition during the VSI.

**SWMU 19                      Sludge Roll-off Box**

**Unit Description:** The roll-off box located in Building 6C is used to collect plating sludge from the wastewater treatment plant (F006), chromium and nickel filters from the plating lines, and the zinc plating wastes (see Photograph No. 20).

**Date of Startup:** This unit was put in operation in 1985.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** The roll-off box is used for temporary accumulation of plating sludges (F006) until they are shipped off site.

**Release Controls:** This unit is located on a concrete floor within the building.

**History of Release:** There have been no documented releases from this unit.

**Observations:** This unit was covered and appeared to be in good condition during the VSI.

**SWMU 20                      Scrap Metal Trailer**

**Unit Description:** This trailer is located in Building 6C near SWMU 19. The trailer is used to collect scrap metal generated throughout the facility in

various operations. The metal is shipped off site to a recycler (see Photograph No. 21).

<b>Date of Startup:</b>	This unit was put in operation in 1988.
<b>Date of Closure:</b>	This unit is currently operational.
<b>Wastes Managed:</b>	This unit manages scrap metal that is often covered with oil.
<b>Release Controls:</b>	This unit is located on concrete within the building.
<b>History of Release:</b>	There have been no documented releases from this unit.
<b>Observations:</b>	During the VSI, oil dripping from the trailer was being absorbed with oil-dry.
<b>SWMU 21</b>	<b>Waste Oil Collection Area (Laser Cutting Machines)</b>
<b>Unit Description:</b>	This unit is a future SAA collection point for waste oil generated by machines used to form metal parts.
<b>Date of Startup:</b>	This unit will start being used in late 1991.
<b>Date of Closure:</b>	This unit is not yet in place.
<b>Wastes Managed:</b>	This unit will manage nonhazardous waste oil from metal parts formation.
<b>Release Controls:</b>	This unit will be located on concrete within Building 5.
<b>History of Release:</b>	No releases have occurred. This unit is only proposed.
<b>Observations:</b>	This unit was not viewed during the VSI. It is only proposed at this time.

**SWMU 22****Waste Oil DSAA (Building 6)**

**Unit Description:** This unit contains a 55-gallon drum used to accumulate scrap oil and hydraulic fluid from punch presses located in Building 6. The waste oil is treated in the oil treatment system in Facility 2 (see Photograph No. 22).

**Date of Startup:** This unit was put in operation in 1980.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** This unit manages waste oil and hydraulic fluid.

**Release Controls:** This unit is located on a concrete floor within the building.

**History of Release:** There have been no documented releases from this unit.

**Observations:** The drum was covered and appeared to be in good condition during the VSI.

**SWMU 23****Nickel Strip Area**

**Unit Description:** Improperly plated metal parts are stripped of their finish in this unit using sodium hydroxide. All wastewater is sent to the wastewater treatment plant (SWMU 16). This wastewater is collected in a sump beneath the strip tanks. Operation of the stripping operation is discussed in Attachment D (see Photograph No. 24).

**Date of Startup:** This unit was put in operation in 1978.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** This unit manages nickel and chromium in solution that have been stripped from metal parts using sodium hydroxide.

**Release Controls:** This unit is located on concrete within Building 6A. Spills and overflow from the stripping tank are collected in sumps and sent to the wastewater treatment plant.

<b>History of Release:</b>	There have been no documented releases from this unit.
<b>Observations:</b>	This unit was in operation during the VSI. No signs of release were observed.
<b>SWMU 24</b>	<b>Plastic Mold Injection SAA</b>
<b>Unit Description:</b>	Eureka uses General Electric Lexan and Cypolac plastics to form vacuum cleaner parts in Building 5. Waste oils from the plastic forming machines are collected in trays beneath the injection machines. A trench surrounds the area to prevent a release.
<b>Date of Startup:</b>	This unit was put in operation in 1988.
<b>Date of Closure:</b>	This unit is currently operational.
<b>Wastes Managed:</b>	This unit manages waste oils from plastic mold injection machines. The trenches are drained as needed.
<b>Release Controls:</b>	The entire area of the unit is trenched. The injection machines are located on concrete and are located within the building.
<b>History of Release:</b>	There have been no documented releases from this unit.
<b>Observations:</b>	This unit was clean and in good condition during the VSI.
<b>SWMU 25</b>	<b>Building 5 IPA Parts Washer SAA</b>
<b>Unit Description:</b>	The unit, an IPA parts washer, is located in Building 5. Sludges generated are collected in a 55-gallon drum next to the parts washing sink. The area is ventilated, and new IPA is added to the sink as old IPA evaporates (see Photograph No. 25).
<b>Date of Startup:</b>	This unit was put in operation in 1988.
<b>Date of Closure:</b>	This unit is currently operational.

**Wastes Managed:** This unit manages nonhazardous paint sludges contaminated with IPA.

**Release Controls:** This unit is located on concrete within the building. The area of the unit is ventilated.

**History of Release:** There have been no documented releases from this unit.

**Observations:** This unit was in good condition during the VSI. No evidence of release was observed. There was a noticeable odor of IPA in the area.

**SWMU 26                      Parts Washer Wastewater Treatment Plant**

**Unit Description:** A wastewater treatment plant located in Building 1B treats spent parts washer solution from the phosphoric acid parts washer in the painting area (SWMU 28) and the alkaline parts washer in Building 7 (SWMU 34). Wastewater enters a collection tank that overflows to a treatment tank. Solution pH is adjusted to a range of 7 to 8 with either a 10 percent caustic soda solution or a 10 percent sulfuric acid solution. After neutralization, the wastewater is sent to a filter supply tank. Wastewater is drawn from this tank through a cartridge filter. It can then be sent back to the filter supply tank to maintain wastewater volume for filters or discharge directly to the BNWRD system. Parts washer cleanouts are treated by the same process. Sludge and filter material is collected at the point of generation in a Gaylord box and is landfilled off site as nonhazardous neutralized sludge. A process flow diagram is included in Attachment D (see Photograph No. 26).

**Date of Startup:** This unit was put in operation in 1975.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** This unit manages spent phosphoric acid parts washer solution and spent alkaline parts washer solution.

**Release Controls:** This unit is located on concrete within the building. Any release would be directed to the BNWRD sewer system.

**History of Release:** There have been no documented releases from this unit.

**Observations:** This unit consists of the wastewater treatment system, the filters for the wastewater, and the Gaylord box. The unit was operating and was in good condition during the VSI.

**SWMU 27                      Paint Mixing Room DSAA**

**Unit Description:** This unit is used for mixing product paints before they are pumped into the spray booths. Wastes generated from cleaning the mixers and drums are collected in a 55-gallon drum (see Photograph No. 27).

**Date of Startup:** This unit was put in operation in 1977.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** This unit manages waste paint and spent solvent (D001 and F003).

**Release Controls:** This unit is curbed with concrete. The unit is located within Building 1.

**History of Release:** There have been no documented releases from this unit.

**Observations:** The drum was covered and appeared to be in good condition during the VSI.

**SWMU 28                      Phosphoric Acid Parts Washer SAA**

**Unit Description:** This parts washer is a three-stage parts washer using phosphoric acid to clean parts before they are painted in the spray booths. This unit is located in Building 1. A similar unit is located in Building 5D (SWMU 34). Waste oil is skimmed from the cleaning solution and collected in a 55-gallon drum located next to the parts washer.

<b>Date of Startup:</b>	This unit was put in operation in 1977.
<b>Date of Closure:</b>	This unit is currently operational.
<b>Wastes Managed:</b>	This unit manages nonhazardous waste oil from parts cleaned in the parts washer.
<b>Release Controls:</b>	The parts washer and collection drum are located on concrete within Building 1.
<b>History of Release:</b>	There have been no documented releases from this unit.
<b>Observations:</b>	This unit was operating and appeared to be in good condition at the time of the VSI.
<b>SWMU 29</b>	<b>Old Paint Solvent Storage Cabinet SAA</b>
<b>Unit Description:</b>	At one time, Eureka had a storage cabinet to contain a drum of waste paint and spent solvent from the spray booths. The cabinet is still located just north of Department 132 in Building 1 (see Photographs No. 28 and 29).
<b>Date of Startup:</b>	This unit was put in operation in 1978.
<b>Date of Closure:</b>	This unit has not been used since June 1991. The cabinet is still present outside the paint shop.
<b>Wastes Managed:</b>	This unit managed waste paint and spent solvent from the spray booths. Analytical results for the waste paint and solvent are included in Attachment E.
<b>Release Controls:</b>	This unit is a self-contained cabinet capable of storing one 55-gallon drum. Any spills would have been captured in the bottom of the cabinet.
<b>History of Release:</b>	There have been no documented releases from this unit.



<b>Observations:</b>	The unit was not in use during the VSI. Paint had been spilled all over the inside of the cabinet, but PRC observed no evidence of a release.
<b>SWMU 30</b>	<b>Paint Spray Room DSAA</b>
<b>Unit Description:</b>	The unit contains the drum used to collect spray booth waste paint and spent solvent. The drum, previously kept in SWMU 29, is now located in the spray booth area (see Photograph No. 30).
<b>Date of Startup:</b>	This unit was put in operation in June, 1991.
<b>Date of Closure:</b>	This unit is currently operational.
<b>Wastes Managed:</b>	This unit manages waste paint and spent solvent from the spray booths (D001, F003).
<b>Release Controls:</b>	This unit is located in a concrete room that is curbed.
<b>History of Release:</b>	There have been no documented releases from this SWMU.
<b>Observations:</b>	The drum was covered and was being filled using a funnel at the time of the VSI.
<b>SWMU 31</b>	<b>Paint Chip Collection Drum</b>
<b>Unit Description:</b>	This unit is located at the northeast corner of the paint shop. It is used to collect dried paint chips that have been knocked off paint racks (see Photograph No. 31).
<b>Date of Startup:</b>	This unit was put in operation in 1978.
<b>Date of Closure:</b>	This unit is currently operational.
<b>Wastes Managed:</b>	This unit manages dried paint chips that are disposed of with neutralized paint sludge.
<b>Release Controls:</b>	The unit is located on a concrete floor within Building 1A.

<b>History of Release:</b>	There have been no documented releases from this unit.
<b>Observations:</b>	The drum was on a pallet and was almost full at the time of the VSI. Paint chips had been spilled on the floor around the drum.
<b>SWMU 32</b>	<b>Stoddard Solvent Washer SAA</b>
<b>Unit Description:</b>	The unit contains three Stoddard solvent washers kept in the tool room (Building 3) to clean metal parts (see Photograph No. 32). Spent solvent is collected in trays beneath the washers.
<b>Date of Startup:</b>	This unit was put in operation in 1979.
<b>Date of Closure:</b>	These units are currently operational.
<b>Wastes Managed:</b>	Trays beneath the washers collect spent Stoddard solvent (D001), which is later transferred to drums. The washers generate about one drum of waste every 3 months.
<b>Release Controls:</b>	The trays are located on concrete.
<b>History of Release:</b>	There have been no documented releases from this unit.
<b>Observations:</b>	The one washer viewed during the VSI was in good condition. There was no evidence of release.
<b>SWMU 33</b>	<b>Forklift Waste Oil and Parts Cleaner SAA</b>
<b>Unit Description:</b>	Waste oil from forklift maintenance and a Stoddard solvent parts cleaner are located in the "mule barn" (Building 3). Waste oil and parts cleaner sludge are collected in 55-gallon drums (see Photographs No. 33 and 34).
<b>Date of Startup:</b>	This unit was put in operation in 1985.
<b>Date of Closure:</b>	This unit is currently operational.

<b>Wastes Managed:</b>	This unit manages Stoddard solvent sludge (D001) and nonhazardous waste oil.
<b>Release Controls:</b>	This unit is curbed, and the floor slopes to a sump that can be pumped out. The area of the unit is made of concrete.
<b>History of Release:</b>	There have been no documented releases from this unit.
<b>Observations:</b>	This unit contained four drums of waste oil at the time of the VSI. Facility representatives stated that the parts cleaner was not used very often.
 <b>SWMU 34                      Phosphoric Acid Parts Washer (Building 5D) SAA</b>	
<b>Unit Description:</b>	This parts washer is similar to the one in SWMU 28 (see Photograph No. 35) and oil is removed from the cleaning solution in the same manner as for SWMU 28..
<b>Date of Startup:</b>	This unit was put in operation in 1974.
<b>Date of Closure:</b>	This unit is currently operational.
<b>Wastes Managed:</b>	This unit manages nonhazardous waste oil from parts cleaned in the parts washer.
<b>Release Controls:</b>	The parts washer is located on concrete.
<b>History of Release:</b>	There have been no documented releases from this unit.
<b>Observations:</b>	The unit appeared to be in good condition during the VSI.
 <b>SWMU 35                      Tool Room Stoddard Solvent and Waste Oil Collection Area</b>	
<b>Unit Description:</b>	This unit is an accumulation area for wastes generated in the tool and maintenance rooms (see Photographs No. 36 and 37).
<b>Date of Startup:</b>	This unit was put in operation in 1978.
<b>Date of Closure:</b>	This unit is currently operational.

**Wastes Managed:** This unit manages spent Stoddard solvent (D001) and nonhazardous waste oil.

**Release Controls:** The spent Stoddard solvent is collected in a drum inside a cabinet similar to the one in SWMU 29. Drums are stored on concrete within the building.

**History of Release:** There have been no documented releases from this unit.

**Observations:** This unit was in good condition. Three drums of waste oil and one drum of spent Stoddard solvent were located in this unit during the VSI.

**SWMU 36                      Chemistry Laboratory DSAA**

**Unit Description:** Eureka has an on-site chemistry laboratory to analyze monitoring data and wastes generated. The unit is located on the second floor of Building 5A. The unit has a collection container for atomic absorption standards and samples, a container for plating tank waste samples, and a container for thinner and paint waste (see Photographs No. 49, 50, and 51).

**Date of Startup:** Atomic absorption materials have been managed in this unit since 1978; the other materials have been managed here since 1988.

**Date of Closure:** All three containers are currently being used to collect laboratory waste.

**Wastes Managed:** All wastes generated at the facility are analyzed in this unit. Table 2 provides a complete list of these wastes.

**Release Controls:** The unit is located on the second floor of Building 5A. The unit has a tile floor to contain any small spills that may occur in the laboratory.

**History of Release:** There have been no documented releases from this SWMU.

**Observations:** The laboratory was clean and orderly at the time of the VSI.

**SWMU 37**

**Paint and Solvents Storage Area**

**Unit Description:** This unit is in Building 11, which is separate from the rest of the Plant 1 structure. The unit is used to store product paint and solvents (see Photograph No. 52). Because the area appeared to be subject to routine and systematic releases, the unit is considered a SWMU.

**Date of Startup:** This unit was put in operation in 1971.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** No wastes are managed in this unit.

**Release Controls:** The unit is curbed and has a concrete floor.

**History of Release:** This unit has no documented history of release to the environment.

**Observations:** At the time of the VSI, the floor of Building 11 was covered with paint that had leaked from drums and with dead pigeons. There was also a pervasive odor of solvent. Based on information provided by the facility, the pigeons were likely the victims of Eureka's pigeon abatement program (which is permitted) and not the paint and solvent in the building.

## **Plant 2**

### **SWMU 38**

#### **Paint Strip Tanks Waste Oil SAA**

**Unit Description:** Paint is stripped from metal parts and paint racks using potassium hydroxide in four tanks. The tanks generate paint pigments in alkali, which is collected from the bottoms of the tanks and moved immediately to the container storage area (SWMU 48). Waste oil is also generated when metal parts are dipped in oil to prevent rusting. The waste oil is collected in a 55-gallon drum located near the strip tanks. A description of the process is included in Attachment D (see Photographs No. 38 and 39).

**Date of Startup:** This unit was put in operation in 1981.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** This unit manages nonhazardous waste oil.

**Release Controls:** This unit is located on concrete within Building 7T. The strip tanks are diked. Any waste reaching the diked area is pumped directly to the Facility 2 wastewater treatment plant.

**History of Release:** There have been no documented releases from this unit.

**Observations:** This unit was in operation during the VSI. Two recycling containers were also located in the area of the unit. The containers are no longer used.

### **SWMU 39**

#### **Phosphoric Acid Derusting Area**

**Unit Description:** In this unit, paint racks used in painting operations are derusted with phosphoric acid (see Photograph No. 40). Vapors are vented from this area through the roof untreated. Paint sludge is removed from this area and stored in a 55-gallon drum.

**Date of Startup:** This unit was put in operation in 1986.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** This unit manages spent phosphoric acid and evaporating product.

**Release Controls:** The unit is ventilated. Plastic balls float on the surface of the phosphoric acid to prevent excess evaporation.

**History of Release:** There have been no documented releases from this unit.

**Observations:** The unit was not being used at the time of the VSI. The unit appeared to be in good condition. No evidence of release was observed.

**SWMU 40**

**Plant 2 Wastewater Treatment Plant**

**Unit Description:** This unit pretreats paint strip wastewater before discharging it to the BNWRD. The wastewater is neutralized and filtered, generating neutralized paint sludge that is collected in a Gaylord box. The area of the unit was previously used as a 1,1,1-TCA strip area (see Photographs No. 41, 42 and 43).

**Date of Startup:** This unit was put in operation in 1975.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** This unit manages nonhazardous paint sludge and wastewater.

**Release Controls:** The unit is located on concrete within Building 4T.

**History of Release:** There have been no documented releases from this unit.

**Observations:** This unit was in good condition during the VSI. No visual evidence of release was observed.

**SWMU 41**

**Oil Separator System**

**Unit Description:** The oil separator system uses a batch treatment process. One 55-gallon drum of scrap cimcool oil, four 55-gallon drums of oil and

water, and 1 gallon of ferric chloride flocculite polymer are mixed and brought to a pH of 1 using sulfuric acid. The batch is mixed again and allowed to separate. The oil is skimmed off, and the remaining water is neutralized to a pH of 7 using lime. One ounce of DuBois flocculite #551 is added, and the sludge is settled out. The remaining liquid is sent to the parts washer treatment system (SWMU 26). The sludge is collected and disposed of as nonhazardous waste. The oil is shipped off site for recycling (see Photograph No. 43).

**Date of Startup:** This unit was put in operation in 1980.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** This unit manages nonhazardous waste oils.

**Release Controls:** The unit is located on concrete within Building 4T.

**History of Release:** There have been no documented releases from this unit.

**Observations:** The unit was operating and appeared to be in good condition during the VSI.

#### **SWMU 42**

#### **Oil Separator Drum Staging Area**

**Unit Description:** This unit is located in a room adjacent to SWMU 41 in the southern part of Building 4T. The unit is used to store drums before their contents are added to the oil separator.

**Date of Startup:** This unit was put in operation in 1980.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** This unit manages nonhazardous waste oils.

**Release Controls:** This unit is located on a concrete floor within the building.

**History of Release:** There have been no documented releases from this unit.



**Observations:** During the VSI, the unit contained six drums of waste oil waiting to be processed. There was no evidence of release from the unit.

**SWMU 43                      Old Paint Mixing Room DSAA**

**Unit Description:** A drum was previously kept in the Plant 2 mixing room in Building 2T to collect waste paints and solvents. This unit is not currently being used, and the drum has been removed.

**Date of Startup:** This unit was put in operation in 1972.

**Date of Closure:** This unit was closed in 1990.

**Wastes Managed:** This unit managed waste paint and spent solvent from the mixing process.

**Release Controls:** The mixing room is curbed and lined with a concrete floor.

**History of Release:** There have been no documented releases from this unit.

**Observations:** The mixing room was empty at the time of the VSI.

**SWMU 44                      Old Paint Spray Room Waste Cabinet**

**Unit Description:** This unit is a cabinet similar to SWMU 29. The cabinet was previously used to store waste paint and spent solvent from the spray booths in Plant 2 (see Photograph No. 44).

**Date of Startup:** This unit was put in operation in 1978.

**Date of Closure:** This unit was closed in 1990.

**Wastes Managed:** This unit managed waste paint and spent solvent from spray booths (D001, F003).

Release Controls:	The room where the unit is located has a concrete floor. The unit is located within Building 2T. No waste is currently being collected in this unit.
History of Release:	There have been no documented releases from this unit.
Observations:	The cabinet was empty at the time of the VSI.
<b>SWMU 45</b>	<b>Plastic Injection Molding Area Waste Oil and Solvent DSAA</b>
Unit Description:	This unit is a container storage area for waste oils and spent Stoddard solvent generated in the molding area and machine shop in Building 5T (see Photograph No. 45).
Date of Startup:	This unit was put in operation in 1977.
Date of Closure:	This unit is currently operational.
Wastes Managed:	This unit manages spent Stoddard solvent (D001) and nonhazardous waste oil.
Release Controls:	The unit is located on a concrete floor within Building 5T. The area of the unit is trenched.
History of Release:	There have been no documented releases from this unit.
Observations:	At the time of the VSI, two 55-gallon drums of scrap oil and one 55-gallon drum of Stoddard solvent were in the unit.
<b>SWMU 46</b>	<b>Plastic Injection Molding Area Parts Washer and Dried Paint Collection DSAA</b>
Unit Description:	This SWMU consists of an IPA parts washer and a 55-gallon collection drum for dried paint generated by the maintenance shop (see Photograph No. 46).
Date of Startup:	This unit was put in operation in 1981.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** This unit manages IPA sludge and nonhazardous waste paint.

**Release Controls:** The unit is located on a concrete floor within Building 5T.

**History of Release:** There have been no documented releases from this unit.

**Observations:** The floor around the parts washer and collection drum was covered with paint chips and small spills.

**SWMU 47**

**Nonhazardous Waste Roll-off Box**

**Unit Description:** The roll-off box is used to collect nonhazardous wastes generated at the facility. These wastes are disposed of in a local landfill (see Photograph No. 47).

**Date of Startup:** This unit was put in operation in 1981.

**Date of Closure:** This unit is currently operational.

**Wastes Managed:** This unit manages neutralized paint sludge, paint pigments in alkali, and other paint-associated nonhazardous wastes.

**Release Controls:** The roll-off box is located on an asphalt parking lot.

**History of Release:** There have been no documented releases from this unit.

**Observations:** During the VSI, the roll-off box appeared to be in good condition. The asphalt around the box was cracked, and a full Gaylord box of waste was waiting to be added to the roll-off box.

**SWMU 48**

**RCRA Container Storage Area**

**Unit Description:** This unit is Eureka's container storage area identified on their Part A. It is used to store hazardous and nonhazardous wastes. Drummed wastes are stored on the concrete floor. The container storage area has walls on three sides and is covered by a canopy.

The unit consists of eight bays. The bay floors are sloped into a diked asphalt area. The four bays that store liquid wastes contain trenches to capture any spilled waste. The unit was storing about 60 drums of waste during the VSI. The facility has an approved closure plan for this area. Closure will include decontamination and sampling (see Photograph No. 48).

<b>Date of Startup:</b>	This unit was put in operation in 1981.
<b>Date of Closure:</b>	This unit is currently operational.
<b>Wastes Managed:</b>	This unit manages hazardous and nonhazardous liquid wastes. These include paint wastes mixed with spent solvents, Stoddard solvent wastes, and waste oils.
<b>Release Controls:</b>	The area is covered with asphalt or concrete and is sloped to the southwest. The entire area is curbed, and hazardous wastes are stored in trenched bays. No release controls were in place before 1985.
<b>History of Release:</b>	There have been no documented releases from this unit. The area was covered with asphalt in 1985. Previously the area was covered with gravel.
<b>Observations:</b>	During the VSI, the unit was in good condition. No evidence of release was observed. Eureka is removing all the waste from this unit so that the container storage area can be closed.

#### **4.0 AREAS OF CONCERN**

**PRC identified no AOCs during the PA/VSI.**

## 5.0 CONCLUSIONS AND RECOMMENDATIONS

The PA/VSI identified 48 SWMUs at the Eureka facility. No AOCs were identified. Background information on the facility's location, operations, waste generating processes, release history, regulatory history, environmental setting, and receptors is presented in Section 2.0. SWMU-specific information, such as the unit's description, dates of operation, wastes managed, release controls, release history, and observed condition, is discussed in Section 3.0. Following are PRC's conclusions and recommendations for each SWMU. Table 4 identifies the SWMUs at the Eureka facility and suggested further actions.

### **SWMUs 1, 2, 4, 5,     Satellite Accumulation Areas**

**6, 7, 11, 14, 15, 21,  
22, 23, 24, 25, 27, 28,  
29, 30, 31, 32, 33, 34,  
35, 36, 38, 39, 41, 42, 43,  
44, 45, and 46**

#### **Conclusions:**

All these SWMUs are satellite accumulation areas for various hazardous and nonhazardous wastes generated throughout both facilities. There have been no documented releases from any of these SWMUs. All are located on concrete floors within buildings. The potential for release from these units is similar. The potential for release to specific environmental pathways is summarized below.

**Ground Water:** The potential for release from any of these SWMUs via the ground-water route is low. Containment within buildings on concrete floors would prevent any spills from reaching an area where hazardous constituents could migrate to ground water.

**Surface Water:** The potential for release from any of these SWMUs via the surface water route is low. Containment within buildings on concrete floors and lack of a nearby surface water body limit the possibility of hazardous constituents being released via this pathway.

**Air:** The potential for release from any of these SWMUs via the air route is low. All the SWMUs are located in buildings where potential releases could be contained. Many of the SWMUs handle wastes that would pose a threat of air emissions only if a fire occurred.

ENFORCEMENT  
CONFIDENTIAL

**TABLE 4**  
**SWMU SUMMARY**

<u>SWMU</u>	<u>Operational Dates</u>	<u>Evidence of Release</u>	<u>Suggested Further Action</u>
<u>Plant 1</u>			
1. Parts Washer with Oil Separator and DSAA	May 1990 to present	None	No further action
2. Alkaline Parts Washer and DSAA	May 1990 to present	None	No further action
3. Old 1,1,1-TCA Vapor Degreaser	1981 to 1990	None	No further action
4. DSAA	1968 to present	Crystalline substance on floor	No further action
5. DSAA	1981 to present	None	No further action
6. Oil Recovery Centrifuge	1981 to present	None	No further action
7. Waste Oil and Stoddard solvent Waste Accumulation Area	1981 to present	None	No further action
8. Steel Grinding Room Dust Collector	1981 to present	None	No further action
9. New Hazardous Waste Container Storage Area	Will begin in late 1991	None	No further action
10. Zinc Plating Area	1981 to present	None	No further action
11. Zinc Filter DSAA	1981 to present	None	No further action
12. Nickel/Chrome Plating Area 1 and 2	1961 to present(1) 1973 to present(2)	None	No further action
13. Nickel/Chrome Plating Area 3	1976 to present	Oil-dry used to catch drippings from plating racks	No further action

ENFORCEMENT  
CONFIDENTIAL

TABLE 4 (Continued)  
SWMU SUMMARY

<u>SWMU</u>	<u>Operational Dates</u>	<u>Evidence of Release</u>	<u>Suggested Further Action</u>
14. Tramp Oil in Alkali DSAA (Ni/Cr Lines 1 and 2)	1972 to present	None	No further action
15. Tramp Oil in Alkali DSAA (Ni/Cr) Line 3	1976 to present	None	Place 55-gallon drum in the diking provided.
16. Wastewater Treatment Plant	1984 to present	None	No further action
17. Nickel Solution Evaporation Unit	1980 to present	Waste solution dripping from the column on to the concrete floor	Fix the leak.
18. Sludge Drier and Dry Sludge Drum	1984 to present	None	No further action
19. Sludge Roll-off Box	1985 to present	None	No further action
20. Scrap Metal Trailer	1988 to present	None	No further action
21. Waste Oil Collection Area (Laser Cutting Machines)	Will begin late 1991	None	No further action
22. Waste Oil DSAA (Building 6)	1980 to present	None	No further action
23. Nickel Strip Area	1978 to present	None	No further action
24. Plastic Mold Injection Containment System	1988 to present	None	No further action
25. Building 5 IPA Parts Washer DSAA	1988 to present	None	No further action



ENFORCEMENT  
CONFIDENTIAL

Sludges and other wastes generated by these units are properly handled and are disposed of off site according to their content. The potential for release to specific environmental pathways is summarized below.

**Ground Water:** These units pose a similarly low threat of release to ground water. All are located on concrete floors where small spills could be contained. The possibility of a large release from any of these units is remote.

**Surface Water:** These units pose a low threat of release to surface water. Discharges from these units are sent to the BNWRD system for further treatment. No surface water is present near the facility.

**Air:** The potential for release via the air route is low. The units are not ventilated and do not treat volatile wastes. All the units are located within facility buildings.

**On-site Soils:** The potential for release via the on-site soils route is low. All the units are located on concrete floors, and the possibility of a large release is remote.

**Recommendations:** No further action is recommended.

**SWMU 19                      Sludge Roll-off Box**

**Conclusions:** The roll-off box is used to store plating waste sludges before they are shipped off site. The potential for release to specific environmental pathways is summarized below.

**Ground Water:** The potential for release from this unit to ground water is low. The dried sludge could easily be contained should a spill from the box occur. The box is located on concrete within a building.

**Surface Water:** The potential for release from this unit to surface water is low. The dried sludge could easily be contained should a spill from the box occur. The box is located on concrete within a building.

**Air:** The potential for release from this unit to air is low because it is covered, it is located within a building, and it does not handle wastes that can migrate to air.

**On-site Soils:** The potential for release from this unit to on-site soils is low. The dried sludge could easily be contained should a spill from the box occur. The box is located on concrete within a building.

**Recommendations:** No further action is recommended.

**SWMU 20                      Scrap Metal Trailer**

**Conclusions:** This unit is used to store scrap metal before the metal is being shipped off site. During the VSI, PRC observed waste oil dripping onto the concrete floor from the trailer. The potential for release to specific environmental pathways is summarized below.

**Ground Water:** The potential for release to ground water is low. The amount of waste oil in the trailer is small and can be easily collected from the concrete floor below the trailer. The scrap metal is nonhazardous and is sent off-site for recycling.

**Surface Water:** The potential for release to surface water is low. The amount of waste oil in the trailer is small and can be easily collected from the concrete floor below the trailer. The scrap metal is nonhazardous and is sent off site for recycling.

**Air:** The potential for release to air is low. This unit is located within a building.

**On-site Soils:** The potential for release to on-site soils is low. The trailer is located on a concrete floor.

**Recommendations:** No further action is recommended.

ENFORCEMENT  
CONFIDENTIAL

**SWMU 37**

**Paint and Solvents Storage Area**

**Conclusions:**

This unit is a product storage area. PRC observed that it was covered with spills during the VSI. The potential for release to specific environmental pathways is summarized below.

**Ground Water:** The potential for release to ground water is low to moderate. All spills were contained within Building 11 during the VSI. A release from the building would have to cross a large asphalt parking lot before it could reach a route to ground water.

**Surface Water:** The potential for release to surface water is low. A release from the building, if not cleaned up first, would be directed to storm sewers. The outlet of the storm sewers is 2 miles north of the facility, and a spill would probably be remedied by the time it reached this outlet.

**Air:** The potential for release to air is high. At the time of the VSI, the drums in the unit had been leaking and there was a noticeable odor of solvent outside Building 11.

**On-site Soils:** The potential for release to on-site soils is low. The facility grounds are covered by asphalt paving. This limits the potential for a release to reach surface soils.

**Recommendations:**

This unit should be cleaned regularly, and the facility should prevent future releases of paints and solvents from the product drums.

**SWMU 47**

**Nonhazardous Waste Roll-off Box**

**Conclusions:**

This box is used to store nonhazardous wastes before they are shipped off site. The potential for release to specific environmental pathways is summarized below.

**Ground Water:** The potential for release to ground water is low. The box is self-contained and is located on asphalt. Any wastes released from the box would be directed to the storm water drains in the parking lot.

**TABLE 4 (Continued)  
SWMU SUMMARY**

<u>SWMU</u>	<u>Operational Dates</u>	<u>Evidence of Release</u>	<u>Suggested Further Action</u>
26. Parts Washer Wastewater Treatment Plant	1975 to present	None	No further action
27. Paint Mixing Room DSAA	1977 to present	None	No further action
28. Phosphoric Acid Parts Washer	1977 to present	None	No further action
29. Old Paint Solvent Storage Cabinet	1978 to present	None	No further action
30. Paint Spray Room DSAA	June 1991 to present	None	No further action
31. Paint Chip Collection Drum	1978 to present	Paint chips on the concrete floor around the drum	No further action
32. Stoddard Solvent Washers	1979 to present	None	No further action
33. Forklift Waste Oil Collection Area and Parts Cleaner	1985 to present	None	No further action
34. Parts Washer and Oil Skimmer (Building 5D)	1974 to present	None	No further action
35. Tool Room Stoddard Solvent and Waste Oil Collection Area	1978 to present	None	No further action
36. Chemistry Laboratory DSAA	1978 to present	None	No further action
37. Paint and Solvents Storage Area	1971 to present	Paint and solvent on floor of Building 11	Clean area and take actions to prevent future leaks.
38. Paint Strip Tanks	1981 to present	None	No further action

**TABLE 4 (Continued)  
SWMU SUMMARY**

<u>SWMU</u>	<u>Operational Dates</u>	<u>Evidence of Release</u>	<u>Suggested Further Action</u>
39. Phosphoric Acid Derusting Area	1986 to present	None	No further action
40. Facility 2 Wastewater Treatment Plant	1975 to present	None	No further action
41. Oil Separator System	1980 to present	None	No further action
42. Oil Separator Drum Staging Area	1980 to present	None	No further action
43. Old Paint Mixing Room DSAA	1972 to 1990	None	No further action
44. Old Paint Spray Room Waste Cabinet	1978 to 1990	None	No further action
45. Plastic Injection Molding Area Waste Oil and Solvent DSAA	1977 to present	None	No further action
46. Plastic Injection Molding Area Parts Washer and Dried Paint Collection Drum	1981 to present	None	No further action
47. Nonhazardous Waste Roll-off Box	1981 to present	None	No further action
48. RCRA Container Storage Area	1981 to present	None	No further action unless closure activities determine that a release to surface soils has occurred

**ENFORCEMENT  
CONFIDENTIAL**

ENFORCEMENT  
CONFIDENTIAL

**On-site Soils:** The potential for release from any of these SWMUs via the on-site soils route is low. No releases have ever occurred. The SWMUs are located on concrete floors within buildings, limiting the possibility of release via this route.

**Recommendations:** No further action is recommended.

**SWMU 3                      Old 1,1,1-TCA Vapor Degreaser**

**Conclusions:** This unit has been removed from the facility. The 1,1,1-TCA is no longer being used at the facility, and no releases from this unit were ever recorded. This unit poses no threat of release via any of the environmental pathways.

**Recommendations:** No further action is recommended.

**SWMU 8                      Steel Grinding Room Dust Collector**

**Conclusions:** This unit does not handle hazardous wastes, and the dust is collected before the exhaust is emitted to the atmosphere. The potential for release to specific environmental pathways is summarized below.

**Ground Water:** The potential for release from this unit via the ground-water route is low. The SWMU does not handle hazardous wastes.

**Surface Water:** The potential for release from this unit via the surface water route is low. The SWMU does not handle hazardous wastes.

**Air:** The potential for release from this unit via the air route is low. Dust is collected by a fabric filter before exhaust is emitted to the atmosphere. This unit does not handle hazardous wastes.

**On-site Soils:** The potential for release from this unit via the on-site soil route is low. This SWMU does not handle hazardous waste.

**Recommendations:** No further action is recommended.

**SWMU 9**

**New Hazardous Waste Container storage area**

**Conclusions:** This unit has not yet been used. It currently poses no threat of release via any of the environmental pathways.

**Recommendations:** No further action is recommended.

Released under the 2016  
FOIA Improvement Act /  
Enforcement sunseting  
provision

**SWMUs 10, 12,  
and 13**

**Plating Areas**

**Conclusions:**

These units have similar collection systems for the wastes they generate. The potential for release to specific environmental pathways is summarized below.

**Ground Water:** The potential for release from these areas via the ground-water route is low. The areas are located on concrete, and the contents of their collection pans can be sumped to the wastewater treatment plant for extra secondary containment.

**Surface Water:** The potential for release from these areas via the surface water route is low. The areas are located within buildings, and the possibility of a large release (more than a few of the plating tanks leaking at one time) is remote. No surface water is present near the facility.

**Air:** The potential for release from these areas via the air route is low. Vapors from the plating tanks are discharged without treatment to the atmosphere, and these discharges are permitted by IEPA. Only small amounts of hazardous metals are believed to be present in the emissions.

**On-site Soils:** The potential for release from these areas via the on-site soils route is low. The areas are located on concrete within buildings.

**Recommendations:** No further action is recommended.

**SWMUs 16, 17, 18,  
26, and 40**

**Waste Treatment Areas**

**Conclusions:**

These SWMUs all treat wastes generated by processes at the facility. Where there are discharges, they are monitored; all discharges are to the BNWRD system, where they would be treated further if a release occurred.

ENFORCEMENT  
CONFIDENTIAL

**Surface Water:** The potential for release to surface water is low. The box is self-contained and is located on asphalt. The unit manages only solid wastes; these would have to travel through 2 miles of storm sewer before they could be discharged to surface water.

**Air:** The potential for release to air is low. The wastes handled by this unit are solid and nonvolatile. The box is self-contained.

**On-site Soils:** The potential for release to on-site soils is low. The facility grounds are covered by asphalt. This limits the potential for a release to reach surface soils.

**Recommendations:** No further action is recommended.

**SWMU 48 RCRA Container Storage Area**

**Conclusions:** This unit is used to store hazardous and nonhazardous liquid wastes. Eureka is in the process of closing this unit. The potential for release to specific environmental pathways is summarized below.

**Ground Water:** The potential for release to ground water is low. No documented releases occurred before the entire area was covered with asphalt; spills can be readily collected.

**Surface Water:** The potential for release to surface water is low. Spills leaving the storage bays would be diverted to the southwestern part of the pad so they could be easily collected.

**Air:** The potential for release to air is low. The unit is located outside, but the drums are kept closed.

**On-site Soils:** The potential for release to on-site soils is low. Any spills leaving the storage bays would be directed to a collection area. The entire unit is covered by concrete or asphalt.

**Recommendations:** Any releases from this unit that may have occurred will be addressed during closure. No further action is recommended at this time.



## REFERENCES

- Bloomington Normal Water Reclamation District (BNWRD), 1991. General Industrial Discharge Permit, BNWRD 91-02, January.
- Eureka Company, 1980a. Application for Permit to Develop a Solid Waste Management Site, June 24.
- Eureka Company (Eureka), 1980b. Notification of Hazardous Waste Activity, EPA Form 8700-12, August 13.
- Eureka, 1980c. Part A Permit Application, November 18.
- Eureka Permit, 1985a. Letter from Don Jenkins to EPA with Revised Part A Permit Application, March 12.
- Eureka, 1985b. Letter from Don Jenkins to EPA Regarding Revised Part A Permit Application, April 15.
- Eureka, 1985c. Letter from Jennie Pike to EPA Regarding August 2 Spill, August 14.
- Eureka, 1986a. Certification Regarding Potential Releases from SWMUs for August 2, 1985, spill, February 11.
- Eureka, 1986b. Letter from Don Jenkins to Richard Johnson, IEPA, Regarding Water Pollution Control Permit (Pretreatment), August 29.
- Eureka, 1988. Letter from Don Jenkins to EPA Regarding Notice of Violation, January 18.
- Eureka, 1989a. Plant 2 Evacuation Route Map, January 8.
- Eureka, 1989b. Plant 1 Evacuation Route Map, May 18.
- Eureka, 1991a. Letter from Don Jenkins to John Justice, IEPA, Regarding Air Variance, January 4.
- Eureka, 1991b. Closure Plan, April 29.
- Federal Emergency Management Agency (FEMA), 1984. Flood Insurance Rate Map for the City of Bloomington, Illinois, April 3.
- Hopkins, Cyril, 1915. Soils Report No. 10, McLean County Soils, October 1.
- Illinois Environmental Protection Agency (IEPA), 1979a. Memorandum from Glen Savage, Division of Land Pollution Control (DLPC), Regarding Pre-Developmental Inspection of Eureka Company Storage Site, September 27.
- IEPA, 1979b. Letter from Sallie Smith, DLPC, to William Garmer, Eureka, Regarding Application for Permit to Develop a Solid Waste Management Site, October 17.
- IEPA, 1980a. Division of Air Pollution Control (DAPC) Operating Permit, February 7.
- IEPA, 1980b. Letter from Thomas Cavanagh to Harold Schaefer, Eureka, Regarding a Permit to Develop a Special Waste Storage Site, December 3.

IEPA, 1980c. Memorandum from Lynn Grills, DLPC, Regarding Inspection of the Eureka Site, December 30.

IEPA, 1981a. Letter from Thomas Cavanagh, DPLC, to Harold Schaefer, Eureka, Regarding Permit to Operate a Special Waste Storage Site, January 15.

IEPA, 1981b. DPLC Observation Report, January 21.

IEPA, 1981c. DPLC Inspection Report, June 19.

IEPA, 1982a. DLPC Observation Report, January 26.

IEPA, 1982b. DLPC Inspection Report, February 16.

IEPA, 1982c. Letter from Thomas Cavanagh, DLPC, to Don Jenkins, Eureka, Regarding Supplemental Permit to Modify the Special Waste Storage Area, May 19.

IEPA, 1982d. DPLC Observation Report, September 9.

IEPA, 1982e. DLPC Inspection Report, October 8.

IEPA, 1984a. Water Pollution Control Permit, February 9.

IEPA, 1984b. DLPC Observation Report, May 31.

IEPA, 1984c. Compliance Inquiry Letter from Glenn Savage, DLPC, to Don Jenkins, Eureka, Regarding May 31 Inspection, August 17.

IEPA, 1984d. RCRA Inspection Report Interim Status Standards for Transport/Storage/Disposal (TSD), December 21.

IEPA, 1985a. Emergency Response Unit Incident Control Sheet, Eureka, August 2.

IEPA, 1985b. Letter from Lawrence Eastep, DLPC, Regarding Modification of Supplemental Permit, August 7.

IEPA, 1985c. Letter from Mark Haney, DLPC, to Don Jenkins, Eureka, Regarding Permit Violations, September 23.

IEPA, 1986a. Letter from Thomas McSwiggin, DWPC, to National Union Electric Corporation regarding Final National Pollutant Discharge Elimination System (NPDES) Permit, March 12.

IEPA, 1986b. Letter from Robert Kuykendall, DLPC, to Don Jenkins, Eureka, Regarding Underground Storage Tank (UST) Regulations, April 4.

IEPA, 1986c. RCRA Inspection Report Interim Status Standards (TSD), June 26.

IEPA, 1986d. Compliance Inquiry Letter from Mark Haney, DLPC, to Don Jenkins, Eureka, Regarding Inspection Violations, September 2.

IEPA, 1986e. Pre-Enforcement Conference Letter from Michael Nechvatal, DLPC, to Don Jenkins, Eureka, Regarding Inspection Violations, October 28.

IEPA, 1986f. Letter from Harry Chappel, DLPC, to Don Jenkins, Eureka, Regarding Apparent Violations, October 28.

IEPA, 1986g. Water Pollution Control Permit, December 22.

IEPA, 1987a. DLPC Inspection Report Including Land Disposal Restriction (LDR) Checklist, August 20.

IEPA, 1987b. Compliance Inquiry Letter from Harry Chappel, DLPC, to Don Jenkins, Eureka, Regarding Violations Identified During August 20 and 21, 1987, Inspection, October 21.

IEPA, 1987c. Pre-Enforcement Conference Letter to Don Jenkins, Eureka, Regarding Apparent Violations, December 17.

IEPA, 1989a. DLPC Inspection Report, March 28.

IEPA, 1989b. Compliance Inquiry Letter from Angela Aye Tin, DLPC, to Don Jenkins, Eureka, May 2.

IEPA, 1989c. Memorandum Regarding Cooling Tower Water Additives, May 30.

IEPA, 1989d. DLPC Memorandum Regarding Enforcement Action for Violations at the Eureka Facility, July 25.

IEPA, 1989e. Letter from Lawrence Eastep, DLPC, to National Union Electric Corporation Regarding Application for Supplemental Permit to Modify Solid Waste Management (SWM) Site, September 20.

IEPA, 1991. Letter from Lawrence Eastep, DLPC, to Don Jenkins, Eureka, Regarding Closure Plan Approval, April 29.

Illinois Pollution Control Board, 1990. Provisional Variance for Storage of Hazardous Wastes for More Than 90 Days, August 9.

Illinois State Water Survey, 1991. Current Well Records for T23N, R2E, Section 10, of McLean County, July 16.

U.S. Environmental Protection Agency (EPA), 1981. Letter from Arnold Leder, Waste and Hazardous Materials Enforcement Branch, to Don Jenkins, Eureka, Regarding June 19, 1981, inspection, December 1.

EPA, 1982. Letter from Karl Klepitsch, Waste Management Branch, to Kenneth Winchester, Eureka, Regarding Interim Status, April 27.

EPA, 1985a. Conversation Record between Ann Brash, EPA, and Don Jenkins, Eureka, Regarding Part A Permit Application Revisions, May 16.

EPA, 1985b. Letter from Edith Ardiente, EPA, to Don Jenkins, Eureka, Regarding Part A Permit Revisions, June 14.

EPA, 1987. Notice of Violation from William E. Muno, EPA, to Don Jenkins, Eureka, December 29.

**ATTACHMENT A**  
**EPA PRELIMINARY ASSESSMENT FORM 2070-12**

**EPA**

**POTENTIAL HAZARDOUS WASTE SITE  
PRELIMINARY ASSESSMENT  
PART 1 - SITE INFORMATION AND ASSESSMENT**

**I. IDENTIFICATION**

01 STATE IL	02 SITE NUMBER ILD 001163823
----------------	---------------------------------

**II. SITE NAME AND LOCATION**01 SITE NAME (Legal, common, or descriptive name of site)  
The Eureka Company02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER  
1201 East Bell Street

03 CITY

Bloomington

04 STATE

IL

05 ZIP CODE

61701

06 COUNTY

McLean

07 COUNTY 08 CONG

CODE

DIST

09 COORDINATES: LATITUDE  
40° 28' 12" LONGITUDE  
88° 58' 37"

10 DIRECTIONS TO SITE (Starting from nearest public road)

From Interstate 55, take State Route 9 East to U.S. Highway 150. Follow U.S. 150 to Bell Street. Turn left on Bell Street.

**III. RESPONSIBLE PARTIES**

01 OWNER (if known)

National Union Electric Corporation

02 STREET (Business, mailing, residential)  
1201 East Bell Street

03 CITY

Bloomington

04 STATE

IL

05 ZIP CODE

61701

06 TELEPHONE NUMBER

(309) 828-2367

07 OPERATOR (if known and different from owner)

Same as above.

08 STREET (Business, mailing, residential)

09 CITY

10 STATE

11 ZIP CODE

12 TELEPHONE NUMBER

( )

13 TYPE OF OWNERSHIP (Check one)

☒ A. PRIVATE☐ B. FEDERAL:

(Agency name)

☐ C. STATE☐ D. COUNTY☐ E. MUNICIPAL☐ F. OTHER

(Specify)

☐ G. UNKNOWN

14 OWNER/OPERATOR NOTIFICATION ON FILE (Check all that apply)

☒ A. RCRA 3001 DATE RECEIVED: 8 / 13 / 80  
MONTH DAY YEAR☐ B. UNCONTROLLED WASTE SITE (CERCLA 103 c) DATE RECEIVED: / /  
MONTH DAY YEAR☐ C. NONE  
MONTH DAY YEAR**IV. CHARACTERIZATION OF POTENTIAL HAZARD**

01 ON SITE INSPECTION

BY (Check all that apply)

☒ YES DATE 07 / 17 / 91  
☐ NO☐ A. EPA☒ B. EPA CONTRACTOR☐ C. STATE☐ D. OTHER CONTRACTOR☐ E. LOCAL HEALTH OFFICIAL☐ F. OTHER:

(Specify)

CONTRACTOR NAME(S): PRC Environmental Management, Inc.

02 SITE STATUS (Check one)

☒ A. ACTIVE☐ B. INACTIVE☐ C. UNKNOWN

1958 | Present

☐ UNKNOWN

BEGINNING YEAR ENDING YEAR

04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT, KNOWN, OR ALLEGED

Methyl ethyl ketone; paint wastes; waste oils; zinc, chromium, and nickel plating sludges.

05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND/OR POPULATION

No potential hazard identified. No releases documented. Wastes handled in secure areas.

**V. PRIORITY ASSESSMENT**

01 PRIORITY FOR INSPECTION (Check one. If high or medium is checked, complete Part 2 - Waste Information and Part 3 - Description of Hazardous Conditions and Incidents.)

☐ A. HIGH☐ B. MEDIUM☒ C. LOW☐ D. NONE

(Inspection required promptly) (Inspection required)

(Inspect on time-available basis) (No further action needed; complete current disposition form)

**VI. INFORMATION AVAILABLE FROM**

01 CONTACT

Kevin Pierard

02 OF (Agency/Organization)  
U.S. EPA Region 5

03 TELEPHONE NUMBER

(312) 886-4448

04 PERSON RESPONSIBLE FOR ASSESSMENT

Timothy S. Oliver

05 AGENCY

06 ORGANIZATION

PRC EMI

07 TELEPHONE NUMBER

(312) 856-8700

08 DATE

07 / 17 / 91  
MONTH DAY YEAR



EPA

POTENTIAL HAZARDOUS WASTE SITE  
PRELIMINARY ASSESSMENT  
PART 2 - WASTE INFORMATION

## I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
IL ILD 001163823

## II. WASTE STATES, QUANTITIES, AND CHARACTERISTICS

## 01 PHYSICAL STATES (Check all that apply)

- ☐ A. SOLID  
☐ B. POWDER, FINES  
☐ C. SLUDGE  
☐ D. OTHER \_\_\_\_\_  
(Specify)
- ☐ E. SLURRY  
☐ F. LIQUID  
☐ G. GAS

## 02 WASTE QUANTITY AT SITE

(Measures of waste quantities  
must be independent)

TON \_\_\_\_\_

CUBIC YARDS 20

NO. OF DRUMS 80

## 03 WASTE CHARACTERISTICS (Check all that apply)

- ☐ A. TOXIC  
☐ B. CORROSIVE  
☐ C. RADIOACTIVE  
☐ D. PERSISTENT  
☐ E. SOLUBLE  
☐ F. INFECTIOUS  
☐ G. FLAMMABLE
- ☐ H. IGNITABLE  
☐ I. HIGHLY VOLATILE  
☐ J. EXPLOSIVE  
☐ K. REACTIVE  
☐ L. INCOMPATIBLE  
☐ M. NOT APPLICABLE

## III. WASTE TYPE

CATEGORY	SUBSTANCE NAME	01 GROSS AMOUNT	02 UNIT OF MEASURE	03 COMMENTS
SLU	SLUDGE	20	cubic yards	Electroplating sludge
OLW	OILY WASTE 40	drums	Waste oils	
SOL	SOLVENTS	20	drums	Paint solvents
PSD	PESTICIDES			
OCC	OTHER ORGANIC CHEMICALS 20	drums	Other	Paint wastes
IOC	INORGANIC CHEMICALS			
ACD	ACIDS			
BAS	BASES			
MES	HEAVY METALS			

## IV. HAZARDOUS SUBSTANCES (See Appendix for most frequently cited CAS Numbers)

01 CATEGORY	02 SUBSTANCE NAME	03 CAS NUMBER	04 STORAGE/DISPOSAL METHOD	05 CONCENTRATION	06 MEASURE OF CONCENTRATION
SLU	Chromium	7440-47-3	20-cubic-yard roll-off box	unknown	
SLU	Nickel	7440-04-0			

## V. FEEDSTOCKS (See Appendix for CAS Numbers)

CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER	CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER
FDS			FDS		
FDS			FDS		
FDS			FDS		
FDS			FDS		

## VI. SOURCES OF INFORMATION (Cite specific references; e.g., state files, sample analysis, reports)

EPA Region 5 Files / IEPA Files

**EPA**

**POTENTIAL HAZARDOUS WASTE SITE  
PRELIMINARY ASSESSMENT  
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS**

**I. IDENTIFICATION**

01 STATE IL	02 SITE NUMBER ILD 001163823
----------------	---------------------------------

**II. HAZARDOUS CONDITIONS AND INCIDENTS**01 ☐ A. GROUNDWATER CONTAMINATION02 ☐ OBSERVED (DATE: \_\_\_\_\_)☐ POTENTIAL☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_

04 NARRATIVE DESCRIPTION

No possible releases or poor containment.

01 ☐ B. SURFACE WATER CONTAMINATION02 ☐ OBSERVED (DATE: 1985)☐ POTENTIAL☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: 50,000

04 NARRATIVE DESCRIPTION

Release of "trichrome additive" flowed into storm sewer to Sugar Creek. The spill was cleaned up, and no other spill has occurred.

01 ☐ C. CONTAMINATION OF AIR02 ☐ OBSERVED (DATE: \_\_\_\_\_)☐ POTENTIAL☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_

04 NARRATIVE DESCRIPTION

Inspectors noted solvent odor in parking lot on 7/17/91. The facility does not have any type of air treatment operations.

01 ☐ D. FIRE/EXPLOSIVE CONDITIONS02 ☐ OBSERVED (DATE: \_\_\_\_\_)☐ POTENTIAL☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_

04 NARRATIVE DESCRIPTION

None.

01 ☐ E. DIRECT CONTACT02 ☐ OBSERVED (DATE: \_\_\_\_\_)☐ POTENTIAL☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_

04 NARRATIVE DESCRIPTION

None. Facility is fenced and patrolled 24 hours a day.

01 ☐ F. CONTAMINATION OF SOIL02 ☐ OBSERVED (DATE: \_\_\_\_\_)☐ POTENTIAL☐ ALLEGED03 AREA POTENTIALLY AFFECTED: \_\_\_\_\_  
(Acres)

04 NARRATIVE DESCRIPTION

None.

01 ☐ G. DRINKING WATER CONTAMINATION02 ☐ OBSERVED (DATE: \_\_\_\_\_)☐ POTENTIAL☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_

04 NARRATIVE DESCRIPTION

None.

01 ☐ H. WORKER EXPOSURE/INJURY02 ☐ OBSERVED (DATE: \_\_\_\_\_)☐ POTENTIAL☐ ALLEGED

03 WORKERS POTENTIALLY AFFECTED: \_\_\_\_\_

04 NARRATIVE DESCRIPTION

None.

01 ☐ I. POPULATION EXPOSURE/INJURY02 ☐ OBSERVED (DATE: \_\_\_\_\_)☐ POTENTIAL☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_

04 NARRATIVE DESCRIPTION

None.

**EPA**

**POTENTIAL HAZARDOUS WASTE SITE  
PRELIMINARY ASSESSMENT  
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS**

**I. IDENTIFICATION**

01 STATE IL	02 SITE NUMBER ILD 001163823
----------------	---------------------------------

**II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)**

01 <input type="checkbox"/> J. DAMAGE TO FLORA	02 <input type="checkbox"/> OBSERVED (DATE: _____)	<input type="checkbox"/> POTENTIAL	<input type="checkbox"/> ALLEGED
04 NARRATIVE DESCRIPTION			

None.

01 <input type="checkbox"/> K. DAMAGE TO FAUNA	02 <input type="checkbox"/> OBSERVED (DATE: _____)	<input type="checkbox"/> POTENTIAL	<input type="checkbox"/> ALLEGED
04 NARRATIVE DESCRIPTION (Include name(s) of species)			

None.

01 <input type="checkbox"/> L. CONTAMINATION OF FOOD CHAIN	02 <input type="checkbox"/> OBSERVED (DATE: _____)	<input type="checkbox"/> POTENTIAL	<input type="checkbox"/> ALLEGED
04 NARRATIVE DESCRIPTION			

None.

01 <input type="checkbox"/> M. UNSTABLE CONTAINMENT OF WASTES	02 <input type="checkbox"/> OBSERVED (DATE: _____)	<input type="checkbox"/> POTENTIAL	<input type="checkbox"/> ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____		04 NARRATIVE DESCRIPTION	

None.

01 <input type="checkbox"/> N. DAMAGE TO OFF-SITE PROPERTY	02 <input type="checkbox"/> OBSERVED (DATE: <u>1985</u> )	<input type="checkbox"/> POTENTIAL	<input type="checkbox"/> ALLEGED
04 NARRATIVE DESCRIPTION			

See surface water contamination (Item B above).

01 <input type="checkbox"/> O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPS	02 <input type="checkbox"/> OBSERVED (DATE: <u>1985</u> )	<input type="checkbox"/> POTENTIAL	<input type="checkbox"/> ALLEGED
04 NARRATIVE DESCRIPTION			

See surface water contamination (Item B above).

01 <input type="checkbox"/> P. ILLEGAL/UNAUTHORIZED DUMPING	02 <input type="checkbox"/> OBSERVED (DATE: _____)	<input type="checkbox"/> POTENTIAL	<input type="checkbox"/> ALLEGED
04 NARRATIVE DESCRIPTION			

None.

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

Inadequate storage of product paint and solvents has resulted in systematic releases to floor of Building 11.

**III. TOTAL POPULATION POTENTIALLY AFFECTED:** 50,000**IV. COMMENTS**

Currently, only release of solvents into the atmosphere in this residential neighborhood is of concern.

**V. SOURCES OF INFORMATION (Cite specific references; e.g., state files, sample analysis, reports)**

EPA Region 5 Files / IEPA Files



**ATTACHMENT B**  
**VISUAL SITE INSPECTION SUMMARY AND PHOTOGRAPHS**

## **VISUAL SITE INSPECTION SUMMARY**

**The Eureka Company  
1201 E. Bell Street  
Bloomington, Illinois 61701  
ILD 001 163 823**

**Date:** July 17 and 18, 1991


**Facility Representatives:** Don E. Jenkins, Environmental Protection Engineer  
Dean A. Shoemaker, Environmental Engineer

**Inspection Team:** Timothy J. Oliver, PRC Environmental Management, Inc. (PRC)  
Kenneth M. Valder, PRC

**Photographer:** Kenneth M. Valder, PRC

**Weather Conditions:** Sunny, 85°F, calm winds.

**Summary of Activities:** The inspection team met with facility representatives at 8:00 a.m. on July 17. The purpose of the inspection was discussed, and Mr. Jenkins outlined the operations taking place in each area of the facility. At 8:50 a.m., the group started the walk-through inspection of Facility 1. A break was taken at 10:50 a.m., and more of the facility operations were discussed. At 11:15 a.m., the group started the inspection of Facility 2. The inspection concluded, and the inspection team left the facility at 12:35 p.m. The inspection team compiled a list of further information that was required and returned to the facility at 8:30 a.m. on July 18. The list was discussed with the facility representatives, and the inspection team left the facility at 9:00 a.m.




Photograph No. 1

Location: SWMU 1 -- Northwest corner of Building 7

Orientation: Northwest

Date: 7/17/91

Description: Parts washer with oil separator and DSAA. The drum is located in the bottom left of the photograph.




Photograph No. 2

Location: SWMU 2 -- Building 7

Orientation: Northeast

Date: 7/17/91

Description: Alkaline parts washer and DSAA. The collection pail is located in the lower right of the photograph.




Photograph No. 3

Orientation: Southwest

Location: SWMU 3 -- Building 7


Date: 7/17/91

Description: Old 1,1,1-TCA vapor degreaser area. The floor is covered with a crystalline substance, apparently from the sodium nitrate deburrer.



Photograph No. 4  
 Orientation: North  
 Description: Scrap coolant satellite waste accumulation drum.

Location: SWMU 5 -- Building 7  
 Date: 7/17/91



Photograph No. 5  
 Orientation: North  
 Description: Oil recovery centrifuge. The oil is collected in the pails to the right of the centrifuge.

Location: SWMU 6 -- Building 7  
 Date: 7/17/91






Photograph No. 6

Orientation: East

Description: Waste oil and Stoddard solvent waste accumulation area. Notice the oil-dry on the floor in the lower left of the photograph.

Location: SWMU 7 -- Building 7

Date: 7/17/91




Photograph No. 7

Orientation: Southeast

Description: Steel grinding room dust collector.


Location: SWMU 8

Date: 7/17/91




Photograph No. 8  
 Orientation: East-northeast  
 Description: New hazardous waste drum storage area.

Location: SWMU 9  
 Date: 7/17/91



Photograph No. 9  
 Orientation: Northeast  
 Description: Zinc plating area.

Location: SWMU 10 -- Building 6B  
 Date: 7/17/91



Photograph No. 10


Orientation: South

Description: Former gold-chromium finish plating tanks, now used for water rinsing.

Location: SWMU 10 -- Building 6B


Date: 7/17/91





Photograph No. 11  
Orientation: Southeast  
Description: Zinc filter DSAA.

Location: SWMU 11  
Date: 7/17/91




Photograph No. 12

Location: SWMU 12 -- Building 6B

Orientation: Southeast

Date: 7/17/91

Description: Nickel sludge collection drum for Ni/Cr plating lines 1 and 2.



Photograph No. 13  
Orientation: East  
Description: Tramp oil in alkali DSAA.

Location: SWMU 14 -- Building 6B  
Date: 7/17/91



Photograph No. 14


Orientation: Northwest

Description: Area where trichrome additive spill occurred in 1982. The area was not trenched at the time. Product chemicals are stored here.

Location: Building 6B


Date: 7/17/91






Photograph No. 15  
Orientation: North  
Description: Tramp oil in alkali DSAA for Ni/Cr plating line 3.

Location: SWMU 15  
Date: 7/17/91




Photograph No. 16  
 Orientation: South  
 Description: Nickel sludge collection drum for plating line 3.

Location: SWMU 13 -- Building 6B  
 Date: 7/17/91




Photograph No. 17  
 Orientation: West  
 Description: Wastewater treatment plant. Tanks are located to the left and right. The sludge filters can be seen in the lower right portion of the photograph.

Location: SWMU 16 -- Building 6B  
 Date: 7/17/91



Photograph No. 18  
 Orientation: Southeast  
 Description: Nickel evaporation columns.

Location: SWMU 17  
 Date: 7/17/91



Photograph No. 19  
 Orientation: Southeast  
 Description: Sludge drier and dry sludge drum.


Location: SWMU 18 -- Building 6B  
 Date: 7/17/91





Photograph No. 20  
 Orientation: West  
 Description: Plating sludge roll-off box.


Location: SWMU 19 -- Building 6C  
 Date: 7/17/91



Photograph No. 21  
 Orientation: Southeast  
 Description: Scrap metal trailer. Note oil-dry spread on the floor to collect waste oil from trailer.


Location: SWMU 20 -- Building 6C  
 Date: 7/17/91






Photograph No. 22  
 Orientation: South  
 Description: Waste oil DSAA for punch presses in the area.

Location: SWMU 22 -- Building 6  
 Date: 7/17/91




Photograph No. 23  
 Orientation: Southeast  
 Description: Roto-Finish machine.

Location: Building 6  
 Date: 7/17/91



Photograph No. 24  
Orientation: South  
Description: Nickel strip area.


Location: SWMU 23 -- Building 6A  
Date: 7/17/91



Photograph No. 25  
Orientation: East  
Description: IPA parts washer and sludge collection drum.


Location: SWMU 25 -- Building 5  
Date: 7/17/91






Photograph No. 26  
 Orientation: North  
 Description: Parts washer wastewater treatment plant.

Location: SWMU 26 -- Building 1B  
 Date: 7/17/91



Photograph No. 27  
 Orientation: North  
 Description: Paint mixing room DSAA.

Location: SWMU 27 -- Building 1  
 Date: 7/17/91




Photograph No. 28

Orientation: Southwest

Description: Phosphoric acid parts washer oil separator collection drum.

Location: SWMU 28 -- Building 1

Date: 7/17/91



Photograph No. 29

Orientation: Northeast

Description: Old paint solvent storage cabinet.


Location: SWMU 29 -- Building 1

Date: 7/17/91



Photograph No. 30  
 Orientation: East  
 Description: Paint spray room DSAA.


Location: SWMU 30 -- Building 1 Paint Shop  
 Date: 7/17/91



Photograph No. 31  
 Orientation: South  
 Description: Paint chip collection drum. Note waste on floor around drum.

Location: SWMU 31 -- Building 1  
 Date: 7/17/91






Photograph No. 32

Location: SWMU 32 -- Building 3

Orientation: Northeast

Date: 7/17/91

Description: One of three Stoddard solvent washers. Wastes are collected underneath the tanks.



Photograph No. 33

Location: SWMU 33 -- Building 3

Orientation: South

Date: 7/17/91

Description: Waste oil collection drums.



Photograph No. 34  
Orientation: East  
Description: Stoddard solvent parts cleaner.

Location: SWMU 33 -- Building 3  
Date: 7/17/91






Photograph No. 35

Orientation: South

Description: Parts washer and oil skimmer. The collection drum can be seen in the center of the photograph.

Location: SWMU 34 -- Building 5D

Date: 7/17/91



Photograph No. 36  
Location: SWMU 35 -- Building 5E  
Orientation: North  
Date: 7/17/91  
Description: Stoddard solvent storage cabinet.



Photograph No. 37  
 Orientation: West  
 Description: Waste oil storage drums.


Location: SWMU 35 -- Building 5E  
 Date: 7/17/91



Photograph No. 38  
 Orientation: North  
 Description: Waste oil collection drum for paint strip area.


Location: SWMU 38 -- Building 7T  
 Date: 7/17/91





Photograph No. 39  
 Orientation: Northeast  
 Description: Paint strip tanks.

Location: SWMU 38 -- Building 7T  
 Date: 7/17/91



Photograph No. 40  
 Orientation: South  
 Description: Phosphoric acid derusting tank.

Location: SWMU 39 -- Building 7T  
 Date: 7/17/91




Photograph No. 41

Orientation: North

Description: Gaylord box for collection of neutralized paint sludge.

Location: SWMU 40 -- Building 4T

Date: 7/17/91



Photograph No. 42


Orientation: Northwest

Description: Part of the treatment system for the Plant 2 wastewater treatment plant.

Location: SWMU 40 -- Building 4T

Date: 7/17/91





Photograph No. 43

Location: SWMUs 40 and 41 -- Building 4T

Orientation: North-northwest

Date: 7/17/91

Description: Wastewater treatment plant is on the left; oil separator system is on the right.




Photograph No. 44

Location: SWMU 44 -- Building 2T

Orientation: North

Date: 7/17/91

Description: Old paint spray room waste cabinet for Plant 2 spray booths.




Photograph No. 45

Orientation: North-northwest

Description: Waste oil and solvent DSAA in the plastic injection molding area.

Location: SWMU 45 -- Building 5T

Date: 7/17/91



Photograph No. 46

Orientation: West

Description: Parts washer and dried paint collection drum in the plastic injection molding area.


Location: SWMU 46 -- Building 5T

Date: 7/17/91



Photograph No. 47  
 Orientation: Southeast  
 Description: Nonhazardous waste roll-off box.


Location: SWMU 47  
 Date: 7/17/91



Photograph No. 48  
 Orientation: Northeast  
 Description: RCRA container storage area.

Location: SWMU 48  
 Date: 7/17/91






Photograph No. 49

Orientation: Southeast

Description: Atomic absorption materials container in chemistry laboratory.


Location: SWMU 36 -- Building 5A

Date: 7/17/91




Photograph No. 50  
Orientation: East  
Description: Plating tank waste container in chemistry laboratory.

Location: SWMU 36 -- Building 5A  
Date: 7/17/91



Photograph No. 51  
 Orientation: East  
 Description: Paint waste container in chemistry laboratory.

Location: SWMU 36 -- Building 5A  
 Date: 7/17/91



Photograph No. 52  
 Orientation: Northeast  
 Description: Paint and dead pigeons on floor of the product paint and solvents storage area.

Location: SWMU 37 -- Building 11  
 Date: 7/17/91

**ATTACHMENT C**  
**VISUAL SITE INSPECTION FIELD NOTES**

(14)

Everett, Bloomington

0850 DJ DS 7/17/91  
FDKV

1. Oil separator / Parts washer

drum collection SAA

concrete no dike

biodeg. oil only

→ was vapor degreaser

11 TCA 3/90

2.

alkaline wash to

remove oil SAA

2.5 gal paint

concrete no dike

3/90

3.

old vapor degreaser

area

4.  $\text{NaNO}_3$  debrine

on floor stuff

5. scrap coolant + SAA

goes to oil recovery

6. centrifuge to recover

oil

7. scrap oil + sludge

solvent SAA

on concrete no dike

8. new oil SE corner

9. scrap grinding

dust collector

used to collect metal dust

vacuum system w/ filter

10. chemical storage area

for product - floor drains

are blocked off

15



11. Plating chemical storage area
12. new brazwaste storage area. 6 x 10 drums each self contained or asphalt - 220 gal capacity for spill - vent. ducted outside
13. ~~new~~ plating line with waste Zn plating alk river wash 3 Zn tanks 2 rinse
14. Zn filters replaced 1-wk floor is grated-surfaced to wwpf water rinse goes to wwpf also (was the gold plating line) - ventilation to roof
15. Zn filter D5AA on concrete nodules
16. Ni/Cr plating lines = 3 Ni - Cr<sup>3+</sup> - Cr<sup>6+</sup> dip
- 2 tanks
- ~~KOH~~ - over flows to vent.  $\Rightarrow$  waste oil

18	6. NaOH	c. rinses x2 d acid - HCl	19				
	c. rinses x2	f. NaOH		Note: was Zn			
	g. rinses x2	h. acid - H		Most floor trench			
	i. <del>NaOH</del>	j. plate N.		was spill area			
	k. 2 rinses	→ to evaporators	19.	another oil sep centrifuge			
	recovers N: cycles			Trump oil and alkali:			
	d: water			on concrete not diked			
	l. Cr <sup>3+</sup>	m. rinse					
	n. Cr acid dip			Note: oil dry on floor			
	Cr wastes go to Cr <sup>6+</sup>			to catch plating sludging			
	reducing others sep			disposed of w/ oil sep			
				sludge			
17	N: filter on tank						
	Cr filter on tank		20.	N: filter centrifuge			
	stored in SAA			collection drum for			
18.	Trump oil and alkali:			#3 filter SAA			
	from centrifuge			on concrete diked			
	→ concrete not diked						

20

21. WWP

#

Cu rinse waters

- get detailed description

have batch tanks

for spills

22.

Ni evaporator

canning diked

23.

sludge dryer

from filter press

then to it

24.

DSA for dryer

then to rolloff

on concrete no

dike

25.

rolloff container

for sledge

concrete no dike.

covered

6/24/91

21

26.

mach. we area

will have DSA

not presently - goes

to other building

waste die laser cutters

27

scrap oil collection

drum SAA from

punch presses

hydraulic fluid

collection pits under

large units.

28

rotomach deburring

area. alternative in

bunk water to

planting WWP X2

trench collection WWP



22									23
29	Waste oil from truck parts added to other waste oil streams - 1 analysis	32.	IPA solids waste in 5HA in corner of plastics area	parts washer					
30	N. strip area → WOP to P-plant diked on concrete	Note: Compressor room generates w-oil							
31	plastic injection molding area Lexan, Cycolac Recycled Waste oil in trays underneath - area drenched	33.	WOP, plant for parts washers and painting operations Discharge to sewer						
		34.	filter cartridges neutralized - galbord box mixed w/ neutralized paint sludge 5HA x machine shop						

24	25
35. Mixing room for paint room collected in DSAA diked room on concrete	— waste yard is of solvent
36. 1/4 PZ (2) parts washer cleaner (1) (3) Rinse	39. Print shop DSAA waste paint/solvents from paint booth electrically filters replaced daily $\Rightarrow$ roll off PZ
37. Oil skimmer gets oil $\rightarrow$ oil separator in PZ DSAA	40. Print chips off paint racks w/ next, print sludge DSAA concrete - no dike
38. Solvent container box N of print shop used to be used on concrete w/o d, ke solvent blend	TILL nonhaz

26							27
41.	3	Standard solvent washes pans under neath - collect waste in drum.			only paint + sludge generates when cleaned cardboard + paint - sludge		
42.		Boil off oil wash water collected off tool room to oil separator DSA		45.	Standard collection drum for tool room in cabinet on concrete no dikes - trench on bldg		
43.		Standard solvent waste also		46.	slap oil accumulation area from tool room 3 drums DSA + machine repair		
44.		parts washer shoe as extra, one for water based oil collection from skinning DSA container no dike			+ oil dry		
				47.	gasoline UST at Hannan entrance to R2 no drums		

28	4 strip tanks KOH	51.	product storage solvent tank OST was	29
48.	2 recycling tanks are no longer used waste: paint pigments		removed. same mix as in paint shop	
	in alkali NOASA	52.	paint strip w/OT area = neutralized paint sludge get description stored in gal box on concrete - no d, ke was formerly used as H2CA strip area no spills - waste was silicone waste!	
49.	diked waste a-l Cro- dipping parts after stripping DSA			
	71 on concrete not diked			
50.	H <sub>2</sub> SO <sub>4</sub> derusting station trenched w/air permit			

36

53

paint washer water  
treatment (neutral.)  
with filters that  
go into next paint  
sludge waste stream

54

oil sep.  
waste oil + sludge  
separate oil/water  
treatment

55

scrap oil / coolant  
for oil separator  
115' staging area

31

27 paint mixing  
area - unused now

could have been

storage area for  
waste

57

old solvent storage  
area for paint shop  
cabinet or container

3 empty building storage

only was once

a solvent area used

paint shop storage

32

58

2 scrapo.

1 standard solvent

OSA for

welding area +

machine shop

area is trenched

59

FPA

and printer

cleaning

54A

dried paint and

clothes drum

60

rollup for the

non hazardous waste

3 drums close upon

asphalt

33

Note: storm water / noncontact

cooling water goes to NPDES

Goose Creek

61 Container Storage Area

gravel was asphalted when?

122' canopy

liquid bags are trenched

1 2 3 4 5 6 7 8

wend diked sloped to

south on crete/asp.

fairly clean


tank truck pumps out of

drums ~ 60 drums

34

35

site operates 24 hours	correcting EEPA requests	
8 hr is most	for chain of custody	
guards patrol whole plant.		
will discontinue waste	63 old ODS's	
acceptance from Normal plant.	500 gal toluene	
	500 gal solvent mix	
	pulled no problems	
	N. next to raw paint	
	storage area	
62 Chemistry Lab		
plating wastes		
from AA go to	64 Paint storage Area	
plating treatment system	lots of paint spills	
all analysis for	but diked cleaned	
wastes done here	in 6 months - dead birds	
solvent reduced paint	solvent storage on other	
plating wastes	side.	
solvent can to paint shop wastes		



**ATTACHMENT D**  
**PROCESS DESCRIPTIONS**



ACID ZINC CHLORIDE BARREL LINE

REV: 07/20/91

CLEANING: AS NEEDED  
= AIR AGITATION IN ALL TANKS

T-1 ELECTROCLEAN

MAKE UP: 100# UDYPREP 270 (SODIUM HYDROXIDE - 45-55%)  
(EDTA - 1%)  
VOLUME: 260 GALS. - TANK SIZE - 44"W X 45"L X 30"D  
WITH A 6"W X 45"L X 30"D OVERFLOW FOR OIL COLLECTION  
TEMPERATURE: 130F; STEAM HEATED AND GUAGE REGULATED (TRERICE)  
RECTIFIER: AIR-COOLED; 9 VOLTS, 700 AMP  
CONTAMINANTS: OILS AND OXIDES  
DESTINATION: SOLIDS, LIQUIDS, AND WASHOUT IS PUMPED TO TA-7  
OR TA-2 FOR TREATMENT.

T-2 COLD WATER RINSE (CWR)

VOLUME: 200 GALS. - TANK SIZE - 36"W X 45"L X 30"D  
OPERATION: CITY WATER FEED AT 3 GPM; CONTROLLED WITH CONDUCTIVITY  
METER.  
CONTAMINANTS: OILS, ALKALI DRAG-OUT  
DESTINATION: OVERFLOW TO TREATMENT TANK TA-2  
DRAIN TO TREATMENT TANK TA-7 OR TA-2

T-3 ACID PICKLE

MAKE-UP: 350# UDYPREP 345 (SODIUM BISULFATE - 95%)  
20 GAL. HYDROCHLORIC ACID  
VOLUME: 200 GALS - TANK SIZE - 36"W X 45"L X 30"D  
DESTINATION: DRAINED TO TREATMENT TA-7 OR TA-2

T-4 COLD WATER RINSE (CWR)

VOLUME: 200 GAL - TANK SIZE - 36"W X 45"L X 30"D  
OPERATION: CITY WATER FEED AT 3 GPM; CONTROLLED WITH CONDUCTIVITY  
METER.  
CONTAMINANTS: ACID DRAG-OUT  
DESTINATION: OVERFLOW TO TREATMENT TANK TA-2  
DRAIN TO TREATMENT TANK TA-7 OR TA-2

T-5 ACID ZINC CHLORIDE PLATING SOLUTION

VOLUME: 500 GALS - TANK SIZE 108"W X 45"L X 30"D  
TEMPERATURE: 70-80F - COOLING WATER CONTROLLED  
RECTIFIER: UDYLTE SASSC, 9VOLT, 3000AMP  
OPERATION: CHILLER (ALPHA MODEL WCA-5) USED TO MAINTAIN OPTIMUM  
PLATING TEMPERATURE.  
CONTINUOUS FILTRATION USING BAG FILTER  
FILTER UNIT: SUMMIT SCIENTIFIC 8-3-MC5

CHEMICAL CONSTITUENTS:

HYDROCHLORIC ACID  
ZINC CHLORIDE (LIQUID)  
POTASSIUM CHLORIDE  
HYDROGEN PEROXIDE (35%)  
SPECTRALYTE 330 (ZINC CHLORIDE - 20%)  
(FORMALDEHYDE - .01%)  
SPECTRALYTE KX-95  
BORIC ACID

ZINC BARREL LINE


```
graph LR; T1[T-1 ELECTRO-CLEANER] --> T2[T-2 CWR]; T2 --> T3[T-3 ACID PICKLE]; T3 --> T4[T-4 CWR]; T4 --> T5[T-5 ACID ZINC CHLORIDE PLATING]; T5 --> T6[T-6 CWR]; T6 --> T7[T-7 CWR]; T7 --> T8[T-8 HEXAVALENT CHROMATE DIP]; T8 --> SD[SPIN DRYER]; SD --> FP[FINISHED PRODUCT];
```

The diagram illustrates the zinc barrel line process, showing the sequence of tanks and associated inputs/outputs. The tanks are labeled T-1 through T-8, and the final product is labeled FINISHED PRODUCT. The process involves electro-cleaning, pickling, and plating, followed by a spin dryer.

Inputs/Outputs for each tank:

- T-1: ELECTRO-CLEANER. Inputs: STEAM, WATER. Output: TA-2 OR TA-7.
- T-2: CWR. Input: WATER. Output: TA-2 OR TA-7.
- T-3: ACID PICKLE. Input: WATER. Output: TA-2 OR TA-7.
- T-4: CWR. Input: WATER. Output: TA-2 OR TA-7.
- T-5: ACID ZINC CHLORIDE PLATING. Inputs: EXHAUST, COOLING, BATH, FILTRATION. Output: TA-7 (CLEAN-OUT REUSE WATER).
- T-6: CWR. Input: WATER. Output: TA-2 OR TA-7.
- T-7: CWR. Input: WATER. Output: TA-2 OR TA-7.
- T-8: HEXAVALENT CHROMATE DIP. Input: WATER. Output: TA-1 OR TA-7.

The final output is FINISHED PRODUCT.





THE NICKEL-CHROME PLATING LINES (I.E. PLATERS 1, 2, AND 3) AT THE EUREKA COMPANY ARE IDENTICAL IN PROCEDURE. SLIGHT VARIATIONS HAVE BEEN MADE IN THE CLEANING CYCLE MAKE-UP DUE TO THE FINAL UTILIZATION OF THE PARTS PROCESSED. THE PLATED PARTS' SUBSTRATE IS STEEL. THE TANK'S MAKE-UPS ARE DETAILED IN THE FLOW SHEETS FOR EACH PLATER.

BEFORE THE ELECTROPLATING PROCESS. PARTS ARE FIRST CHEMICALLY PREPARED. BASED ON THE NATURE OF THE SOILS. THE FOLLOWING CYCLE IS USED FOR MAXIMUM CLEANING AND METAL SURFACE PREPARATION.

#### TANK 1 - SOAK CLEAN

A HOT, AIR AGITATED ALKALINE CLEANER WHICH REMOVES ORGANIC SOILS AND DIRT BOUND TO THE SURFACE BY THE OILS AND GREASES.

#### TANK 2 - REVERSE ELECTROCLEAN

A HOT, AIR AGITATED ALKALINE CLEANER WHERE THE PART IS MADE CATHODIC (CURRENT APPLIED) WHICH GENERATES A GAS TO LOOSEN SCALE AND SOILS. THE POSITIVELY CHARGES PART WILL REPEL METAL IONS OR SMUT FROM REFORMING ON THE PART.

#### TANKS 3-4 - RINSING

COUNTERCURRENT WATER FLOW TO REMOVE THE ALKALINE FILM.

#### TANK 5 - HOT ACID PICKLING

A HOT, ACIDIC SOLUTION THAT REMOVES THE HEAVIER SCALE AND RUST NOT AFFECTED BY ALKALINE CLEANING.

#### TANKS 6-7 - RINSING

COUNTERCURRENT WATER FLOW TO REMOVE THE ACIDIC FILM.

#### TANK 8 - REVERSE ELECTROCLEAN

PARTS ARE CLEANED AGAIN TO REMOVE ANY PICKLING SCALE

#### TANKS 9-10 - RINSING

COUNTERCURRENT WATER FLOW TO REMOVE THE ALKALINE FILM.

#### TANK 11 - COLD ACID DIP

REMOVES ALKALINE FILM LEFT FROM RINSING AND ACTIVATES METAL SURFACE TO PREPARE FOR NICKEL PLATING.

#### TANK 12 - RINSING

REMOVES EXCESS ACID SO THAT pH OF THE NICKEL TANK IS NOT ADVERSELY AFFECTED.

#### TANK 13 - NICKEL PLATING

PARTS ARE PLATED IN A HIGH NICKEL CHLORIDE BATH. THE NUMBER OF



The Eureka Company  
July 22, 1991

**NICKEL-CHROME PLATER #1**  
UDYLITE CYCLEMASTER 42, SERIAL-A-2640

CLEANING: SEMI-ANNUAL OR AS NEEDED.  
AIR AGITATION ON ALL TANKS.

**T-1 SOAK CLEANER**

MAKE-UP: 400# C-255 (SODIUM HYDROXIDE- 25%)  
VOLUME: 590 GALS - TANK SIZE 88"L X 30"W X 54"D  
TEMPERATURE: 190°F; STEAM HEATED AND GAUGE REGULATED (15PSI MAX)  
CONTAMINANTS: OILS, OXIDES  
DESTINATION: ALKALI OIL REMOVED IN CENTRIFUGE. DRUMMED AND PROPERLY  
DISPOSED OF AS TRAMP OIL AND ALKALI.  
SOLIDS, LIQUIDS, AND WASHOUT PUMPED TO TA-10 OR TA-9  
TREATMENT TANK FOR NEUTRALIZATION AND DEWATERING.

**T-2 REVERSE ELECTROCLEAN #1**

MAKE-UP: 600# E-230 (SODIUM HYDROXIDE- <65%)  
25# UDYFIN 931 ( NO HAZ INGRED.)  
VOLUME: 900 GALS - TANK SIZE 31"L X 30"W X 54"D  
TEMPERATURE: 160°F; STEAM HEATED AND GAUGE REGULATED (15 PSI MAX)  
RECTIFIER: UDYLTE - SASSC 24TTL-5M012-10, 12 VOLTS, 5000 AMP  
SERIAL # 09857  
CONTAMINANTS: OILS, OXIDES, ALKALI DRAGOUT.  
DESTINATION: SOLIDS, LIQUIDS, AND WASHOUT PUMPED TO TREATMENT TANK TA-9  
OR TA-10 FOR NEUTRALIZATION AND DEWATERING.

**T-3, T-4 COLD WATER RINSE (CWR)**

VOLUME: 140 GALS EACH - TANK SIZE - 21"L X 30"W X 54"D  
OPERATION: CITY WATER FEED AT 2.5-3 GPM FLOW CONTROL  
COUNTERCURRENT FLOW FROM T-4 TO T-3.  
WATER SUPPLY CONTROLLED BY CONDUCTIVITY METER.  
CONTAMINANTS: OILS, ALKALI DRAGOUT, AND OXIDES.  
DESTINATION: OVERFLOW TO TREATMENT TANK TA-2.  
DRAIN TO TREATMENT TANK TA-2, OR TA-9, OR TA-10.

**T-5 HOT ACID TANK**

MAKE-UP: 700# UDYPREP 350 (FLUORIDES - 2-5%)  
(SODIUM HYDROGEN SULFATE - 85-95%)  
1 GAL UDYFIN 367 (FORMALDEHYDE - .01%)  
VOLUME: 377 GALS - TANK SIZE - 57"L X 34"W X 54"D  
TEMPERATURE: 140°F- 170°F; STEAM HEATED AND GAUGE REGULATED.  
CONTAMINANTS: ALKALI SCALE, METALS, AND OXIDES.  
DESTINATION: SOLIDS, LIQUIDS, AND WASHOUT PUMPED TO TREATMENT TANK TA-2.  
OR TA-9, OR TA-10 FOR NEUTRALIZATION AND DEWATERING.

### T-13 NICKEL PLATING BATH

VOLUME: 1900 GALS - TANK SIZE - 269.5"L X 30"W X 54"D  
TEMPERATURE: 130°F: STEAM HEATED AND GAUGE REGULATED (15 PSI MAX)  
RECTIFIER: UDYLLITE SASSC, MODEL 2VDV-4M009-410, 9 VOLT, 6000 AMP  
SERIAL # 22015  
OPERATION: 360 SQ FT PRODUCTION PER HOUR  
CONCENTRATED NICKEL RINSE WATER RETURN FROM EVAPORATIVE  
RECOVERY UNITS  
CITY WATER MAKE-UP FOR EVAPORATION.  
CONTINUOUS FILTRATION USING DIATOMACEOUS EARTH AND ACTIVATED  
CARBON - SLIMLINE FILTER SL24-30  
CHEMICAL CONSTITUENTS: SULFURIC ACID  
HYDROCHLORIC ACID  
LIQUID NICKEL CHLORIDE  
ELECTROLYTIC NICKEL CHIPS  
BORIC ACID  
NICKEL BRIGHTENER #63 - FORMALDEHYDE- <.01%  
SACCHARIN - 10-25%  
NICKEL BRIGHTENER #61 - FORMALDEHYDE- <.01%  
NICKEL BRIGHTENER MAGNUM S - SACCHARIN - 5-10%  
NIRON LC STABILIZER - POLYHYDROXY ACID- <50%  
DESTINATION: TO NICKEL STORAGE TANK FOR TREATMENT AND FILTRATION TO  
REMOVE ORGANIC CONTAMINATION (BRIGHTENER BREAKDOWN). NICKEL  
PLATING SOLUTION IS TREATED WITH NICKEL CARBONATE (pH  
ADJUSTMENT), POTASSIUM PERMANGANATE (OXIDIZER), ACTIVATED  
CARBON, AND FILTER AID.

NICKEL BAGS ARE LEACHED WITH SULFURIC ACID IN TANK. AFTER  
RINSING, BAGS ARE THEN PLACED IN 55-GALLON LINED DRUMS.  
THESE ARE LABELED AND ADDED TO THE ROLL-OFF CONTAINING THE  
PLATING SLUDGE - F006. PLATING TANK IS CLEANED AND WASHED  
OUT. FRESH NICKEL BAGS ARE PLACED ON THE BASKETS. THE BAGS  
ARE SOAKED IN A WEAK SULFURIC ACID SOLUTION ( 3 GALLONS PER  
TANK FILLED WITH WATER) IN ORDER TO REMOVE THE SIZING IN  
THE BAGS.

WASHOUT FROM THE PLATING BATH CAN BE SENT TO TA-2 OR TA-7.  
THIS IS AT THE WASTETREATMENT OPERATOR'S DISCRETION.

NICKEL PLATING BATH IS RETURNED TO THE TANK VIA FILTRATION.  
STORAGE TANK IS WASHED OUT AND THE RESIDUALS ARE PUMPED TO  
TREATMENT TANK TA-7.

### T-14, T-15, T-16 COLD WATER RINSES

VOLUME: T-14, T-15: 140 GALS EACH - TANK SIZE - 21"L X 30"W X 54"D  
T-16 - SPRAY RINSE ONLY - DRY TANK.  
OPERATION: T-15 - CITY WATER FEED AT 2.5-3 GPM FLOW CONTROL OR NICKEL  
RECOVERY DISTILLATE AT 2 GPM. COUNTERCURRENT FLOW  
FROM T-15 TO T-14.  
T-16 - SPRAY FEED AT 2.5 GPM FOR 12.5 SEC (DOWN CYCLE TIME)

The Eureka Company  
July 22, 1991

TEMPERATURE: ROOM.

DESTINATION: DRAIN TO TREATMENT TANK TA-1 OR TA-7

**T-20 COLD WATER RINSE**

VOLUME: 140 GALS - TANK SIZE - 21"L X 30"W X 54"D.

OPERATION: CITY WATER FEED AT 2.5-3 GPM FLOW CONTROL

CONTAMINANTS: CHROME PLATING DRAGOUT.

DESTINATION: OVERFLOW TO TREATMENT TANK TA-1.

DRAIN TO TREATMENT TANK TA-1, OR TA-7.

**T-21 COLD WATER RINSE**

VOLUME: 140 GALS. TANK SIZE - 21"L X 30"W X 54"D.

OPERATION: CITY WATER FEED AT 2.5-3 GPM FLOW CONTROL.

DESTINATION: DRAIN TO TREATMENT TANK TA-1 OR TA-7.

OVERFLOW TO TREATMENT TANK TA-1.





The Eureka Company  
July 22, 1991

**NICKEL-CHROME PLATER #2**  
UDYLITE CYCLEMASTER 42. SERIAL #4997  
ELECTRICAL PSO #4998  
LOADER PSO #4999  
CONVEYOR PSO #5000

CLEANING: SEMI-ANNUAL OR AS NEEDED.  
AIR AGITATION ON ALL TANKS.

**T-1 SOAK CLEANER**

MAKE-UP: 1000# C-255 (SODIUM HYDROXIDE- 25%)  
VOLUME: 1250 GALS - TANK SIZE 133"L X 33"W X 60"D  
TEMPERATURE: 190°F; STEAM HEATED AND GAUGE REGULATED (15PSI MAX)  
CONTAMINANTS: OILS, OXIDES  
DESTINATION: ALKALI OIL REMOVED IN CENTRIFUGE. DRUMMED AND PROPERLY  
DISPOSED OF AS TRAMP OIL AND ALKALI.  
SOLIDS, LIQUIDS, AND WASHOUT PUMPED TO TA-10 OR TA-9  
TREATMENT TANK FOR NEUTRALIZATION AND DEWATERING.

**T-2 REVERSE ELECTROCLEAN #1**

MAKE-UP: 475# E-504 (SODIUM HYDROXIDE- <45%)  
25# UDYFIN 931 ( NO HAZ INGRED.)  
VOLUME: 755 GALS - TANK SIZE 91"L X 33"W X 60"D  
TEMPERATURE: 160°F; STEAM HEATED AND GAUGE REGULATED (15 PSI MAX)  
RECTIFIER: UDYLITE MODEL 2VDV-6M009-310. 9 VOLT. 6000 AMP  
SERIAL # 19973  
CONTAMINANTS: OILS, OXIDES. ALKALI DRAGOUT.  
DESTINATION: SOLIDS, LIQUIDS, AND WASHOUT PUMPED TO TREATMENT TANK TA-9  
OR TA-10 FOR NEUTRALIZATION AND DEWATERING.

**T-3, T-4 COLD WATER RINSE (CWR)**

VOLUME: 170 GALS EACH - TANK SIZE - 21"L X 33"W X 60"D  
OPERATION: CITY WATER FEED AT 2.5-3 GPM FLOW CONTROL  
COUNTERCURRENT FLOW FROM T-4 TO T-3.  
WATER SUPPLY CONTROLLED BY CONDUCTIVITY METER.  
CONTAMINANTS: OILS, ALKALI DRAGOUT, AND OXIDES.  
DESTINATION: OVERFLOW TO TREATMENT TANK TA-2.  
DRAIN TO TREATMENT TANK TA-2, OR TA-9, OR TA-10.

**T-5 HOT ACID TANK**

MAKE-UP: 700# ACID SALTS #2 (SODIUM FLUORIDES - <10%)  
(SODIUM BISULFATE <25%)  
2 QTS UDYFIN 367 (FORMALDEHYDE - .01%)  
VOLUME: 475 GALS - TANK SIZE - 57"L X 33"W X 60"D  
TEMPERATURE: 140°- 170°F: STEAM HEATED AND GAUGE REGULATED.  
CONTAMINANTS: ALKALI SCALE, METALS, AND OXIDES.  
DESTINATION: SOLIDS, LIQUIDS, AND WASHOUT PUMPED TO TREATMENT TANK TA-2,  
OR TA-9, OR TA-10 FOR NEUTRALIZATION AND DEWATERING.

The Eureka Company  
July 22, 1991

VOLUME: 170 GALS - TANK SIZE - 21"L X 33"W X 60"D  
OPERATION: CITY WATER FEED AT 2.5-3 GPM FLOW CONTROL  
CONTAMINANTS: CHROME PLATING DRAGOUT.  
DESTINATION: OVERFLOW TO TREATMENT TANK TA-1.  
DRAIN TO TREATMENT TANK TA-1. OR TA-7.

**T-21 COLD WATER RINSE**

VOLUME: 170 GALS. TANK SIZE - 21"L X 33"W X 60"D.  
OPERATION: CITY WATER FEED AT 2.5-3 GPM FLOW CONTROL  
DESTINATION: DRAIN TO TREATMENT TANK TA-1 OR TA-7.  
OVERFLOW TO TREATMENT TANK TA-1



The Eureka Company  
July 22, 1991

**NICKEL-CHROME PLATER #3**  
UDYLITE CYCLEMASTER III. SERIAL #760701  
MACHINE PSO #1254  
ELECTRICAL PSO #1255  
LOADER PSO #1256  
CONVEYOR PSO #1257

CLEANING: QUARTERLY OR AS NEEDED.  
AIR AGITATION ON ALL TANKS.

**T-1 SOAK CLEANER**

MAKE-UP: 1500# C-255 (SODIUM HYDROXIDE- 25%)  
VOLUME: 2170 GALS - TANK SIZE 166"L X 41"W X 66"D  
TEMPERATURE: 190°F; STEAM HEATED AND GAUGE REGULATED (15PSI MAX)  
CONTAMINANTS: OILS, OXIDES  
DESTINATION: ALKALI OIL REMOVED IN CENTRIFUGE. DRUMMED AND PROPERLY  
DISPOSED OF AS TRAMP OIL AND ALKALI.  
SOLIDS, LIQUIDS, AND WASHOUT PUMPED TO TA-10 OR TA-9  
TREATMENT TANK FOR NEUTRALIZATION AND DEWATERING.

**T-2 REVERSE ELECTROCLEAN #1**

MAKE-UP: 875# E-504 (SODIUM HYDROXIDE- 45%)  
40# UDYFIN 931 ( NO HAZ INGRED.)  
VOLUME: 1310 GALS - TANK SIZE 117"L X 41"W X 66"D  
TEMPERATURE: 160°F; STEAM HEATED AND GAUGE REGULATED (15 PSI MAX)  
RECTIFIER: UDYLITE MODEL 2VDV-4M009-300. 9 VOLT. 4000 AMP  
SERIAL # 18153  
CONTAMINANTS: OILS, OXIDES, ALKALI DRAGOUT.  
DESTINATION: SOLIDS, LIQUIDS, AND WASHOUT PUMPED TO TREATMENT TANK TA-9  
OR TA-10 FOR NEUTRALIZATION AND DEWATERING.

**T-3, T-4 COLD WATER RINSE (CWR)**

VOLUME: 300 GALS EACH - TANK SIZE - 25"L X 41"W X 66"D  
OPERATION: CITY WATER FEED AT 2.5-3 GPM FLOW CONTROL  
COUNTERCURRENT FLOW FROM T-4 TO T-3.  
WATER SUPPLY CONTROLLED BY CONDUCTIVITY METER.  
CONTAMINANTS: OILS, ALKALI DRAGOUT, AND OXIDES.  
DESTINATION: OVERFLOW TO TREATMENT TANK TA-2.  
DRAIN TO TREATMENT TANK TA-2, OR TA-9, OR TA-10.

**T-5 HOT ACID TANK**

MAKE-UP: 750# ACID SALTS #2 (SODIUM FLUORIDES - 10%)  
(SODIUM BISULFATE 25%)  
750# UDYPREP 345 (SODIUM HYDROGEN SULFATE 90-95%)  
(FLUORIDES - 5-8%)  
1 GAL UDYFIN 367 (FORMALDEHYDE - .01%)

The Eureka Company  
July 22, 1991

WATER SUPPLY CONTROLLED BY CONDUCTIVITY METER.  
CONTAMINANTS: OILS, ALKALI DRAGOUT, AND OXIDES.  
DESTINATION: OVERFLOW TO TREATMENT TANK TA-2.  
DRAIN TO TREATMENT TANK TA-2, OR TA-9, OR TA-10.

#### T-13 NICKEL PLATING BATH

VOLUME: 4300 GALS - TANK SIZE - 389"L X 41"W X 66"D.  
TEMPERATURE: 130°F: STEAM HEATED AND GAUGE REGULATED (15 PSI MAX)  
RECTIFIER: UDYLLITE SASSC, MODEL 2VDV-8M009-300, 9 VOLT, 8000 AMP.  
SERIAL # 18155  
OPERATION: 1100 SQ FT PRODUCTION PER HOUR  
CITY WATER MAKE-UP FOR EVAPORATION AND CONCENTRATED NICKEL  
RINSE WATER RETURN FROM EVAPORATIVE RECOVERY UNITS.  
CONTINUOUS FILTRATION USING DIATOMACEOUS EARTH AND ACTIVATED  
CARBON - SLIMLINE FILTER SL24-30  
CHEMICAL CONSTITUENTS: SULFURIC ACID  
HYDROCHLORIC ACID  
LIQUID NICKEL CHLORIDE  
ELECTROLYTIC NICKEL CHIPS  
BORIC ACID  
NICKEL BRIGHTENER #63 - FORMALDEHYDE- <.01%  
SACCHARIN - 10-25%  
NICKEL BRIGHTENER #61 - FORMALDEHYDE- <.01%  
NICKEL BRIGHTENER MAGNUM S - SACCHARIN- 5-10%  
NIRON LC STABILIZER - POLYHYDROXY ACID- <90%  
DESTINATION: TO NICKEL STORAGE TANK FOR TREATMENT AND FILTRATION TO  
REMOVE ORGANIC CONTAMINATION (BRIGHTENER BREAKDOWN). NICKEL  
PLATING SOLUTION IS TREATED WITH NICKEL CARBONATE (pH  
ADJUSTMENT), POTASSIUM PERMANGANATE (OXIDIZER), ACTIVATED  
CARBON, AND FILTER AID.

NICKEL BAGS ARE LEACHED WITH SULFURIC ACID IN TANK. AFTER  
RINSING THESE BAGS ARE THEN PLACED IN 55 GALLON LINED  
DRUMS. THESE ARE LABELED AND ADDED TO THE ROLL-OFF  
CONTAINING THE PLATING SLUDGE -FOO6. TANK IS WASHED AND  
CLEANED OUT. FRESH NICKEL BAGS ARE PLACED ON THE BASKETS.  
THE BAGS ARE SOAKED IN A WEAK SULFURIC ACID SOLUTION ( 3  
GALLONS PER TANK FILLED WITH WATER) IN ORDER TO REMOVE THE  
SIZING IN THE BAGS.

WASHOUT FROM THE PLATING BATH CAN BE SENT TO TA-2 OR TA-7.  
THIS IS AT THE WASTETREATMENT OPERATOR'S DISCRETION.

NICKEL PLATING BATH IS RETURNED TO THE TANK VIA FILTRATION.  
STORAGE TANK IS WASHED OUT AND THE RESIDUALS ARE PUMPED TO  
TREATMENT TANK TA-7.

T-14, T-15, T-16 COLD WATER RINSES



The Eureka Company  
July 22, 1991

## Nickel Strip

Cleaning: As needed

Dresser Roots Blower 36AF providing air agitation in all tanks.

### T-1 CHROME STRIP

MAKE UP: 60# UDYPREP (SODIUM HYDROXIDE 45-55%)  
(EDTA 1%)

10# UDYFIN 931

VOLUME: 200 GAL - TANK SIZE 36"L X 36"W X 36"D WITH AN OVERFLOW  
TROUGH 3"L X 36"W X 5"D

TEMPERATURE: 140-160F: STEAM HEATED AND REGULATED (TRERICE)  
COIL IS TRANTER PLATECOIL 60AD

ANODES: STEEL - 3" X 3/8" X 30"

RECTIFIER: DUAL-O-MATIC, AIR COOLED, 6 VOLT, 1500 AMP

EXHAUST: PVC EXHAUST HOOD AND DUCT CONNECTED TO BUFFALO TYPE B  
VANEAXIAL FAN. SIZE 18

OPERATION: TO STRIP CHROME FROM PLATING REJECTS

DESTINATION: SOLIDS, LIQUIDS, AND WASH-OUT PUMPED TO TREATMENT  
TANK TA-7

### T-2 COLD WATER RINSE (CWR)

VOLUME: 80 GAL - TANK SIZE 24"L X 24"W X 30"D

OPERATION: CITY WATER FEET AT 2.5-3 GPM FLOW CONTROL

CONTAMINANTS: ALKALI DRAG OUT

DESTINATION: OVERFLOW TO TREATMENT TA-2  
DRAIN TO TREATMENT TA-7

### T-3 ACID ACTIVATION

MAKE UP: 100# ACID SALTS #2 (SODIUM FLUORIDE <10%)  
(SODIUM BISULFATE >90%)

VOLUME: 80 GAL - TANK SIZE 24"L X 34"W X 30"D

TEMPERATURE: ROOM

ANODES: 1" X 4" X 24" CARBON, WITH 4" TITANIUM HOOK

RECTIFIER: RAPID ELECTRIC, AIR COOLED, 6 VOLT, 250 AMP

EXHAUST: PVC HOOD AND DUCT COMMON TO EXHAUST ON T-1

OPERATION: TO ACTIVATE NICKEL SURFACE FOR STRIPPING

DESTINATION: SOLIDS, LIQUIDS AND WASH OUT PUMPED TO TREATMENT  
TANK TA-7

### T-4 COLD WATER RINSE (CWR)

VOLUME: 80 GAL - TANK SIZE 24"L X 24"W X 30"D

OPERATION: CITY WATER FEED AT 3 GPM FLOW CONTROL

ALSO FUNCTIONS AS COOLING STATION FOR NICKEL STRIPPING  
SOLUTION. SOLUTION IS PUMPED VIA AIR PUMP THROUGH  
TRANTER PLATECOIL (18"W X 29"L - 16 GAUGE STAINLESS  
STEEL TYPE 70AD). NON-CONTACT COOLING.

CONTAMINANTS: ACIDIC DRAG-OUT

DESTINATION: OVERFLOW TO TREATMENT TANK TA-2  
DRAIN TO TREATMENT TANK TA-7


### T-5 NICKEL STRIP





## PARTS WASHER 131

RINSE WATERS AT A THREE STAGE IRON PHOSPHATE PARTS WASHER AND ALKALINE PARTS WASHER ARE DISCHARGED TO THE TREATMENT CENTER. WATERS ENTER A COLLECTION TANK WHICH OVERFLOWS INTO A TREATMENT TANK. THE pH IS ADJUSTED TO A RANGE OF 7 TO 8 WITH EITHER A 10% CAUSTIC SODA SOLUTION OR A 10% SULFURIC ACID SOLUTION. AFTER NEUTRALIZATION THE WATER IS SENT TO A FILTER SUPPLY TANK. WATER IS DRAWN FROM THIS TANK THROUGH A CARTRIDGE FILTER AND CAN BE SENT BACK TO THE FILTER SUPPLY TANK TO MAINTAIN WATER VOLUME FOR FILTERS OR DISCHARGE DIRECTLY TO SANITARY SEWER. PARTS WASHER CLEAN OUTS ARE TREATED IN THE SAME PROCEDURE. SLUDGE AND FILTER MATERIAL IS LANDFILLED OFF-SITE AS A NON-HAZARDOUS. NEUTRALIZED SLUDGE.



**ATTACHMENT E**  
**MATERIAL SAFETY DATA SHEETS**  
**AND WASTE ANALYSES**

# MATERIAL SAFETY DATA SHEET

## I - PRODUCT IDENTIFICATION

COMPANY NAME: Calgon Vestal Laboratories		
ADDRESS: 5035 Manchester Avenue St. Louis, MO 63110		Tel No: (314)535-1810
		Nights: (314)862-2000
		CHEMTREC: (800)424-9300
PRODUCT NAME: RP-775		Product No.: 1809
Synonyms: Alkaline Corrosion Inhibitor/Cleaner		

## II - HAZARDOUS INGREDIENTS OF MIXTURES

MATERIAL:	(CAS#)	(ORAL LD50)	% By Wt.	TLV	PEL
#2-Butoxyethanol	(111-76-2)	(470mg/kg)	<10	25ppm	25ppm HSTC
Sodium Nitrite	(7632-00-0)	(85mg/kg)	<5	STEL: 75ppm	(skin) HS
Potassium Hydroxide	(1310-58-3)	(365mg/kg)	<5	N/AV	N/AV HS
Sodium Tetraborate, Decahydrate	(1303-96-4)		<5	2mg/m3	2mg/m3
# Ingredient subject to reporting under Section 313 of Title III (SARA) and 40 CFR 372.				(ceiling)	(ceiling)
				5mg/m3	10mg/m3

## III- PHYSICAL DATA

Vapor Pressure, mm Hg: Undetermined	Vapor Density (Air=1)60-90F: Undeter
Evaporation Rate(ether=1): N/A	% Volatile by wt <5
Solubility in H2O: Complete	pH @ Solution N/A
Freezing Point F: N/A	pH as Distributed: 13.4
Boiling Point F: > 212	Appearance: Clear pale light straw liq
Specific Gravity H2O=1 @25C: 1.115	Odor: Mild chemical odor

## IV - FIRE AND EXPLOSION

Flash Point F: N/A	Flammable Limits: N/A
Extinguishing Media: Product is not flammable or combustible. Use media appropriate for the primary source of fire.	
Special Fire Fighting Procedures: Use caution when fighting any fire involving chemicals. A self-contained breathing apparatus is essential.	
Unusual Fire and Explosion Hazards: None known	

## V - REACTIVITY DATA

Stability - Conditions to avoid: None known
Incompatibility: Strong acids
Hazardous Decomposition Products: Carbon monoxide, carbon dioxide and oxides of nitrogen may be released in a fire.
Conditions Contributing to Hazardous Polymerization: Product will not polymerize.



MATERIAL SAFETY DATA SHEET  
For Materials Provided

OSHA

Section I - Product Identification

4/4/86

Provider: AMERICAN CHEMCO INDUSTRIES, INC.  
675 East Irving Park Road, Suite 305  
Roselle, Illinois 60172

Information Phone: (312)894-4433  
Emergency Phone: (312)577-5045

Product Class:  
Trade Name : EP-89 Hot Strip  
Product Code :  
C.A.S. No. : NA-1719

Hazard Rating: none→extreme  
0→4  
Corrosive Material  
Health:  
Fire :  
Reactivity:

Section II - Hazardous Ingredients

Ingredients:	CAS#	Weight %	Exposure Limits	Vapor Pr. mm Hg
Potassium Hydroxide	1310-58-3	< 30	2.0 mg/m <sup>3</sup> for 15 min. (PEL) OSH 2.0 mg/m <sup>3</sup> for AIR BORNE (TLV) Acute LD <sub>50</sub> =365 mg/kg (ORAL RAT)	
Dipropylene Glycol		< 20	TLV-Not Established Acute LD <sub>50</sub> 14.8 g/kg (ORAL RAT) Acute LD <sub>50</sub> > 2 kg/mg (DERMAL) Acute LD <sub>50</sub> > 200 mg/l in 1 hr (inhalation)	

Section III - Physical Data

Boiling Range: > 200°F	Vapor Density: (air=1) >1
Evap. Rate : (Butyl Acetate=1) ÷ 0.36	Liquid Density: (mmHg) ÷ 8
Volatiles by volume: ÷ 4.0	Wgt. Per Gallon: (Water=1) ÷ 1.26
Solubility in water: Complete	pH: 10% Solution > 12
Appearance: Colorless, Odorless Liquid	

Section IV - Fire and Explosion Hazard Data

Flammability Class: None Flash Point: None LEL;  
--EXTINGUISHING MEDIA: Usual media

--SPECIAL FIREFIGHTING PROCEDURES: Wear full protective equipment and clothing.

--UNUSUAL FIRE AND EXPLOSION HAZARDS: This product will react with aluminum, zinc, tin and their alloys to produce flammable hydrogen gas.

Section V - Health Hazard Data

--PERMISSIBLE EXPOSURE LEVELS:

--EFFECTS OF OVEREXPOSURE: Eyes: Can cause chemical burns, severe. May produce irreversible damage and blindness. Skin: Can cause severe chemical burns. Ingestion: Can cause gastrointestinal damage. Inhalation: Inhaling mist from this product may produce nasal and respiratory damage.

—EYE PROTECTION: Do Not Wear contact lenses. Wear OSHA approved chemical splash goggles (with face shield as needed).

—ADDITIONAL PROTECTIVE OR HEALTH EQUIPMENT

---

#### Section IX - Special Precautions

---

—PRECAUTIONS TO BE TAKEN IN HANDLING AND STORAGE: Strong liquid alkaline product, containing caustic alkali. Causes severe burns to skin and eyes. Do not allow contact with skin, eyes, clothing. Do not take internally. Do not inhale mist, dust, or spray. Do not contact acids. When handling, wear safety goggles or face shield and rubber gloves as well as protective clothing and respirator if necessary.

Store in cool dry place, in original container with lid tightly closed. DO NOT CUT,  
OTHER INFORMATION: MUTILATE, WELD, OR REUSE THIS CONTAINER FOR ANY PURPOSE.  
FOR INDUSTRIAL USE ONLY. KEEP AWAY FROM CHILDREN.





MATERIAL SAFETY DATA SHEET  
For Materials Provided

OSHA

5/9/86

Section I - Product Identification

Provider: AMERICAN CHEMCO INDUSTRIES, INC.  
675 East Irving Park Road, Suite 305  
Roselle, Illinois 60172

Information Phone: (312)894-4433

Emergency Phone: (312)577-5045

Product Class: *listed as Chemco 15*  
Trade Name : #15 Rust Preventative  
Product Code :  
C.A.S. No. : 64742-47-8

Hazard Rating: none->extreme  
0-->4  
Health: Fire :  
Reactivity:  
Combustible Liquid, Irritant

Section II - Hazardous Ingredients

Ingredients:	CAS#	Weight %	Exposure Limits	Vapor Pr. mm Hg
Mineral Spirits	64742-47-8	90%	100 ppm (ACGIH) 500 ppm (OSHA)	
Butyl Carbitol	112-34-5	5%	N/E	

Section III - Physical Data

Boiling Range: 365° - 394° F.  
Evap. Rate : (BAC=1) Slower  
Volatiles by volume: 90%  
Spec. Gravity: .78  
Appearance: Low viscosity Amber Liquid, Mild Solvent Odor

Vapor Density: (air=1) Heavier  
Liquid Density:  
Wgt. Per Gallon:

Section IV - Fire and Explosion Hazard Data

Flammability Class: Volatile Flash Point: 110°F(COC) LEL;  
--EXTINGUISHING MEDIA: Carbon Dioxide, Dry Chemical, Water Fog (mist)

--SPECIAL FIREFIGHTING PROCEDURES: Use water to cool exposed containers.

--UNUSUAL FIRE AND EXPLOSION HAZARDS:

Section V - Health Hazard Data

--PERMISSIBLE EXPOSURE LEVELS:

--EFFECTS OF OVEREXPOSURE: Eyes: Causes eye Irritation. Skin: Defatting and irritation after prolonged contact. Inhalation: Nausea, Breathing difficulties in area with concentrations above TLV.

—EYE PROTECTION: Goggles

—ADDITIONAL PROTECTIVE OR HEALTH EQUIPMENT Eye Wash, Safety Shower

---

#### Section IX - Special Precautions

---

—PRECAUTIONS TO BE TAKEN IN HANDLING AND STORAGE: Store in cool, dry area away from ignition sources.

OTHER INFORMATION:



Don Jenkins

063 \*\*\*

6/2/88

M A T E R I A L   S A F E T Y   D A T A   S H E E T

PAGE 1

REV: 04/21/88

CHEMTECH INDUSTRIES, INC.  
1655 DES PERES ROAD  
P.O. BOX 31000  
ST. LOUIS, MO 63131  
PHONE: (314) 966-9900

PROD F199  
MASTER

HEALTH = 2      REACTIVITY = 0  
FIRE     = 3      EQUIPMENT = \_

HAZARD RATINGS : 0 = LEAST      1 = SLIGHT  
                         2 = MODERATE    3 = HIGH  
                         4 = EXTREME

SECTION I ===== PRODUCT DESCRIPTION =====

PRODUCT NAME:        F 199  
SYNONYMS:             SOLVENT  
CHEMICAL FAMILY:     NOT APPLICABLE

SECTION II ===== PRODUCT COMPOSITION =====

INGREDIENT	CAS #	TLV
ALIPHATIC PETROLEUM NAPHTHA	64742-89-8	300 PPM
ISOPROPANOL	67-63-0	400 PPM
2-BUTOXY ETHANOL = Butyl Cellosolve	111-76-2	25 PPM
METHYL ISOBUTYL KETONE. HSTC RO 5000 TO -	108-10-1	50 PPM

SECTION III ===== PHYSICAL PROPERTIES =====

BOILING RANGE:                    82-170C / 180-338F  
SPECIFIC GRAVITY (WATER=1):        0.791  
VAPOR PRESSURE AT 20C (MM OF HG): 21.8  
VAPOR DENSITY (AIR=1):            3.2  
SOLUBILITY IN WATER:               APPRECIABLE  
EVAPORATION RATE (N-BOAC=1):      1.9  
% VOLATILES:                        100  
APPEARANCE AND ODOR:    CLEAR, COLORLESS LIQUID WITH A TYPICAL THINNER ODOR

SECTION IV ===== FIRE AND EXPLOSION DATA =====

LOWER FLAMMABILITY LIMITS (% IN AIR):    1.5  
FLASH POINT (AND METHOD): (TCC)            57 F

WASTE DISPOSAL PROCEDURES:

INCINERATE PER LOCAL, STATE AND FEDERAL POLLUTION REGULATIONS

SECTION VIII ===== SPECIAL PROTECTION INFORMATION =====

RESPIRATORY PROTECTION: A NIOSH-APPROVED RESPIRATOR FOR ORGANIC MATERIALS

LOCAL EXHAUST: RECOMMENDED

PROTECTIVE GLOVES: SOLVENT RESISTANT SUCH AS VINYL OR NEOPRENE

EYE PROTECTION: CHEMICAL SAFETY GOGGLES

OTHER PROTECTIVE EQUIPMENT: EYE-WASH, SAFETY SHOWER, PROTECTIVE CLOTHING

SECTION IX ===== ADDITIONAL PRECAUTIONS =====

PRECAUTIONS TO BE TAKEN IN HANDLING AND STORAGE:

DANGER! HARMFUL IF SWALLOWED! FLAMMABLE!

KEEP AWAY FROM HEAT AND OPEN FLAME. USE ONLY WITH ADEQUATE VENTILATION

AVOID PROLONGED BREATHING OF VAPOR OR SPRAY MIST. AVOID PROLONGED OR  
REPEATED CONTACT WITH SKIN. KEEP CONTAINER CLOSED WHEN NOT IN USE.

FOR INDUSTRIAL USE ONLY!

OTHER PRECAUTIONS:

DO NOT STORE ABOVE 49C (120F). STORE LARGE AMOUNTS IN STRUCTURES MADE FOR  
FLAMMABLE LIQUIDS. EMPTY CONTAINER HAZARDOUS. CONTINUE ALL LABEL  
PRECAUTIONS. DO NOT FLAME CUT, BRAZE OR WELD.

THE INFORMATION HEREIN IS PRESENTED IN GOOD FAITH AND  
BELIEVED TO BE CORRECT AS OF THE DATE HEREOF. HOWEVER, CHEMTECH  
MAKES NO REPRESENTATION AS TO THE COMPLETENESS AND ACCURACY  
THEREOF. USERS MUST MAKE THEIR OWN DETERMINATION AS TO THE  
SUITABILITY OF THE PRODUCT FOR THEIR PURPOSES PRIOR TO USE.

NO REPRESENTATIONS OR WARRANTIES, EITHER EXPRESS OR IMPLIED,  
OF MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE OR OF ANY  
OTHER NATURE WITH RESPECT TO THE PRODUCT OR TO THE INFORMATION  
HEREIN IS MADE HEREUNDER. CHEMTECH SHALL IN NO EVENT BE  
RESPONSIBLE FOR ANY DAMAGES OF WHATSOEVER NATURE DIRECTLY OR  
INDIRECTLY RESULTING FROM THE PUBLICATION OR USE OF, OR RELIANCE  
UPON INFORMATION CONTAINED HEREIN.





safety-kleen®

ACCEPT

FLUID RECOVERY

NO ATTACHMENT

\* \* FLUID RECOVERY \* \*

CUSTOMER INFORMATION: 5136-01-9049

EUREKA  
1201 E BELL  
BLOOMINGTON

IL 61701

ATTN: DON JENKINS

BRANCH: 513601 ROGER BROTHERTON

NATURE OF BUSINESS: MFG OF VACUUMS

FEDERAL EPA ID: IL0001163823 STATE EPA: IL ID: 1130900009 ID:

MANIFEST ADDRESS IS FACILITY MANIFEST TO

SIC #: 3633

MATERIAL: PAINT WASTE

PROCESS: PAINTING

VOLUME: 2200 GALS PER QUARTER

VOLUME ON HAND: 2750

STORAGE CAPACITY: 0 IN DRUMS

SHIPPING FREQUENCY: QTRLY IN DRUMS

COLOR: BLUISH/GRAY

LAYERS: TWO

PHYSICAL STATE: LIQUID

VISCOSITY: LOW

MATERIAL COMPOSITION(VOL%):

CODE	MIN	MAX	TYPICAL
PAINT WASTE	0.0		100.0
XYLENE	0.0		

RESTRICTED SUBSTANCES: NONE

D.O.T. HAZARDOUS MATERIAL: CUSTOMER REQUEST ASSISTANCE

EPA HAZARDOUS WASTE: CUSTOMER REQUEST ASSISTANCE

P.O. NO:

BRANCH: 513601

DATE: 05/30/91

TYPE OF SAMPLE: COMPOSITE

NUMBER OF DRUMS SAMPLED: 4

TAKEN BY: SALESREP

CONTACT: DON JENKINS

TITLE: ENGINEER

PHONE: 309-823-5461

SURVEY COMMENTS: ANALYZE AT ELK GROVE

L#12086-6

CORPORATE REVIEWS: DISPOSITION REVIEWER DATE

TECHNICAL: ACCEPT JHP 06/18/91

REGULATORY: ACCEPT AAD 06/18/91

OPERATING: ACCEPT JWH 06/18/91

PRICING CODE: F1

APPROVED FACILITIES:

(658) SAFETY-KLEEN CORP	(654) SAFETY-KLEEN CORP
STATE HWY 146	633 EAST 138TH ST
NEW CASTLE KY 40050	DOLTON IL 60419

FED EPA#: KY0053348108

ILD980613913

STATE EPA#:

0310690006

TELEPHONE: 502/845-2453

708/849-4850

STATE CODE:

000161

EPA WASTE CODES  
FO03 0001

APPROVD 0000537 DRUM

DOT-EPA WASTE FLAMMABLE LIQUID, N.O.S.

DESC: (METHYL ISOBUTYL KETONE) UN1993

(FO03)(ERG #27)

COMMENTS: OK FOR FUEL. FRS PART 82101.

THIS SERVES AS NOTICE PER, 40CFR264.12(B), THAT THE FACILITY(IES) NOTED ABOVE  
HAS THE APPROPRIATE PERMITS AND IS WILLING TO RECEIVE THE MATERIAL DESCRIBED.

SAFETY-KLEEN CORP.  
PREQUALIFICATION EVALUATION  
MATERIAL ANALYSISPAGE 3 OF 3  
COMPLETE: 06/20/91  
CONTROL#: 0099216-8  
SAMPLE# : 202591FLUID RECOVERY  
EUREKAACCEPT  
NO ATTACHMENT

\*\* FLUID RECOVERY \*\*

LABORATORY REVIEW: A  
LEVEL: SEG CODE: RELEASED: 06/20/91  
LAB REVIEWERS: AJ AJ ANALYZED: 06/17/91TRACKING INFORMATION: DATE FACILITY  
SURVEY RECEIVED : 06/03/91 SK TECHNICAL CEN.  
SAMPLE RECEIVED : 06/03/91  
RESAMPLE SHIPPED :  
RESAMPLE RECEIVED:

THE ANALYSES CONTAINED HEREIN ARE PERFORMED SOLELY FOR THE PURPOSE OF QUALIFYING THE ANALYZED MATERIALS FOR ACCEPTANCE BY SAFETY-KLEEN IN ACCORDANCE WITH ITS PERMITS AND PROCESSING CAPABILITY.

NOTICE OF LAND DISPOSAL RESTRICTION OF WASTE IS REQUIRED UNDER 40 CFR PART 268.

EPA WASTE CODES FOR LDR: F003 D001

ANALYSIS DOES NOT INDICATE THAT MATERIAL IS CALIFORNIA LIST HALOGENATED ORGANIC COMPOUND WASTE.





Prise Pigments & alkali & Turp oil & Alkali

```

: W-Auth No#: 39806 Shipper-no: 00375 / INA 0359368
: Generator #: G311 Name: EUREKA COMPANY
: Location: BLOOMINGTON IL 61701 Received Date: 02/11/91
: Pickup Date: 02/11/91 Carrier/Driver: COMMERCIAL SEWER
: Material: WASTE Gallons: Pounds: 32,480
: Analysis by: SW
: % Oil: 4 %Water: 82 %Solid: 14
: Lbs/Gal: Normality:
: Flash PT.: > 240 F PH: 10.0 Viscosity:

```

```

----- WORK/ANALYSIS -- Qty in PPM, * Degree of Detection -----
, Descriptn Quantity Descriptn Quantity Descriptn Quantity
, PCB: ND01PPM Barium: 3.636 Cadmium: 0.0000
, Chromium: 0.5461 Lead: 0.0000 Mercury:
, Selenium: 0.9022 Silver: 0.0000 Arsenic: 0.0000
, *Halides: ND Cyanides: Sulfides:
, PCB Analysis-no: T 16-312-4 Metal Analysis-no: M 31-38
, Additional comments:

```

#####

Paint Pigments and Alkali: TRAMP OIL and Alkali

```

: W-Auth No#: 36713 Shipper-no: 0359367 /097867
: Generator #: G311 Name: EUREKA COMPANY
: Location: BLOOMINGTON IL 61701 Received Date: 07/17/90
: Pickup Date: 07/17/90 Carrier/Driver: COMM. SEWER / 097867
: Material: CAUSTIC Gallons: Pounds: 25,080
: Analysis by: CJW

```

```

Oil Characteristics:
-----
WORK/ANALYSIS -- Qty in PPM. * Degree of Detection -----

```

Descriptn	Quantity	Descriptn	Quantity	Descriptn	Quantity
PCB:	ND@1PPM	Barium:	3.244	Cadmium:	.0000
Chromium:	.4934	Lead:	.1524	Mercury:	
Selenium:	.0250	Silver:	.0000	Arsenic:	.0000
*Halides:	ND	Cyanides:	ND@1PPM	Sulfides:	

PCB Analysis-no: T 15-20-3 Metal Analysis-no: M 24-457

[illegible]

# Daily Analytical Laboratories

7807 N. Pioneer Lane • Peoria, Illinois 61614 Tel. 309-692-5252



Eugene J. Daily, President

Otis E. Michels  
John P. Higgins  
Walter H. Johansen  
Lyn A. Denton  
Woodrow C. Chenault, Jr.  
Thomas B. Jordan  
Philip W. Jacobs

## ANALYTICAL & ENVIRONMENTAL ENGINEERING LABORATORY

TO: The Eureka Company DATE RECEIVED 5-6-80  
1201 E. Bell Street CLIENT P.O. #   
Bloomington, IL 61701 D/A PROJECT # 5183.00  
 ATTENTION: Mr. Ken Winchester DATE OF REPORT 5-23-80

D/A SAMPLE NO.		0127-17		0127-18	
SAMPLE DESCRIPTION		Paint Pigments in Alkali Top		Paint Pigments in Alkali Bottom	
SAMPLE DATE					
Acids, Volatile Organic	mg/l				
Acidity, (as CaCO <sub>3</sub> )	mg/l				
Alkal., Phthalein	mg/l				
Alkal., Total, (as CaCO <sub>3</sub> )	mg/l	130,000		130,000	
Bicarbonates	mg/l				
BOD-5, Total	mg/l				
BOD-5, Soluble	mg/l				
BOD-20, Total	mg/l				
BOD-20, Carbonaceous	mg/l				
BOD-20, Nitrogenous	mg/l				
Bromide	mg/l				
Carbonates	mg/l				
Chloramine, Mono-	mg/l				
Chloramine, Di-	mg/l				
Chloride	mg/l				
Chlorine-Demand	mg/l				
-Comb. Residual	mg/l				
-Free Residual	mg/l				
-Total Residual	mg/l				
Color	Unit				
C.O.D.	mg/l				
Cyanide, Free	mg/l				
Cyanide, Total	mg/l	0.17		0.08	
Dissolved Oxygen	mg/l				
Fluoride	mg/l				
Hardness (as CaCO <sub>3</sub> )	mg/l				
Nitrogen, Ammonia (as N)	mg/l				
Nitrogen, Kjeldahl (as N)	mg/l				
Nitrogen, Organic (as N)	mg/l				

ANALYTICAL & ENVIRONMENTAL ENGINEERING LABORATORY

O/A SAMPLE NO.		0127-17		0127-18	
SAMPLE DESCRIPTION		Paint Pigments in Alkali Top		Paint Pigments in Alkali Bottom	
SAMPLE DATE					
Nitrate	mg/l				
Nitrite	mg/l				
Odor, Intensity Index	OII				
Odor, Threshold @ 60°C	TO				
Oils & Grease (Soxhlet)	mg/l				
Oxygen Demand Index	mg/l				
pH	Units	14		14	
Phenols	mg/l				
Phosphate, Total (as P)	mg/l				
Phosphate, Ortho (as P)	mg/l				
Phosphorous (as P)	mg/l				
Sludge Volume Index	Units				
Specific Conductance	umhos				
Solids, Total (103°C)	mg/l				
Solids, Total (180°)	mg/l				
Solids, Total Fixed	mg/l				
Solids, Total Volatile	mg/l				
Solids, Dissolved	mg/l				
Solids, Settleable	ml/l				
Solids, Tot. Suspended	mg/l				
Solids, Volatile Sus.	mg/l				
Solids, Volatile Sus.	%				
Sulfate	mg/l				
Sulfide	mg/l				
Sulfite	mg/l				
Total Organic Carbon	mg/l				
Turbidity	JTU				
% Solids		65%		68%	
Flashppint		>200°F		>200°F	

BACTERIOLOGICAL ANALYSIS

Coliforms, Total	#/100ml				
Coliforms, Fecal	#/100ml				
Fecal Streptococci	#/100ml				
Pseud.aeruginosa	#/100ml				
Staph.aureus	#/100ml				

mg/l=parts per million

Analysis Certified By:

John R. LaPayne  
John R. LaPayne, Chief Chemist

Analysis and Testing performed in accordance with procedures described in Standard Methods for the Examination of Water and Waste Water 13th Edition, (1971) A.P.H.A.; ASTM Standards Part 23, "Water, Atmospheric Analysis", (1972), A.S.T.M.; and other equivalent procedures.

ANALYTICAL & ENVIRONMENTAL ENGINEERING LABORATORY

O/A SAMPLE NO.	0127-17		0127-18		
SAMPLE DESCRIPTION	Paint Pigments in Alkali Top Dry Wt. Bas.	Soluble Metals 1/100 in 0.1N HOAc	Paint Pigments in Alkali Bottom Dry Wt. Bas.	Soluble Metals 1/100 in 0.1N HOAc	
SAMPLE DATE					
HEAVY METALS ANALYSIS					
Aluminum	mg/l				
Antimony	mg/l				
Arsenic	mg/l 2.5	0.02	2.9	0.016	
Barium	mg/l 1,040	3.3	1,010	3.4	
Beryllium	mg/l				
Bismuth	mg/l				
Boron*	mg/l				
Cadmium	mg/l 32	0.16	48	0.19	
Calcium	mg/l				
Chromium Trivalent *	mg/l				
Chromium Hexavalent*	mg/l				
Chromium Total	mg/l 45	1.1	48	0.55	
Copper	mg/l 160	0.55	120	0.52	
Iron Dissolved	mg/l				
Iron Total	mg/l				
Lanthanum	mg/l				
Lead	mg/l 27	0.07	30	< 0.05	
Magnesium	mg/l				
Manganese	mg/l				
Mercury	ppb 18	0.50	10	0.32	
Nickel	mg/l 27	0.26	24	0.24	
Potassium	mg/l				
Selenium	mg/l 7.4	0.022	13.1	0.022	
Silicon	mg/l				
Silver	mg/l < 0.30	< 0.03	0.30	< 0.03	
Sodium	mg/l				
Strontium	mg/l				
Sulfur	mg/l				
Tin	mg/l				
Titanium	mg/l				
Tungsten	mg/l				
Vanadium	mg/l				
Zinc	mg/l 130	1.0	98	0.09	

mg/l=parts per million

Analysis Certified By:

John R. LaPayne  
John R. LaPayne, Chief Chemist

Analysis and Testing performed in accordance with procedures described in Standard Methods for the Examination of Water and Waste Water 13th Edition, (1971) A.P.H.A.; ASTM Standards Part 23, "Water, Atmospheric Analysis"; (1972), A.S.T.M.; and other equivalent procedures.

All analysis by Atomic Absorption Spectrophotometry unless otherwise specified.

\* Analysis by wet chemistry procedures.





safety-kleen®

A C C E P T

FLUID RECOVERY

NO ATTACHMENT

\* \*

F L U I D   R E C O V E R Y

\* \*

CUSTOMER INFORMATION: 5136-01-9049

EUREKA  
1201 E BELL  
BLOOMINGTON

IL 61701

ATTN: DON JENKINS

BRANCH: 513601 ROGER BROTHERTON

NATURE OF BUSINESS: MFG OF VACUUMS

FEDERAL EPA ID: ILD001163823 STATE EPA: IL ID: 1130900009

ID:

MANIFEST ADDRESS IS FACILITY MANIFEST TO

SIC #: 3633

MATERIAL: PAINT WASTE

PROCESS: PAINTING

VOLUME: 2200 GALS PER QUARTER

VOLUME ON HAND: 2750

STORAGE CAPACITY: 0 IN DRUMS

SHIPPING FREQUENCY: QTRLY IN DRUMS

COLOR: BLUISH/GRAY

LAYERS: TWO

PHYSICAL STATE: LIQUID

VISCOSITY: LOW

MATERIAL COMPOSITION(VOL%):

CODE	MIN	MAX	TYPICAL
PAINT WASTE	0.0		100.0
XYLENE	0.0		

RESTRICTED SUBSTANCES: NONE

D.O.T. HAZARDOUS MATERIAL: CUSTOMER REQUEST ASSISTANCE

EPA HAZARDOUS WASTE: CUSTOMER REQUEST ASSISTANCE

P.O. NO:

BRANCH: 513601

DATE: 05/30/91

TYPE OF SAMPLE: COMPOSITE

NUMBER OF DRUMS SAMPLED: 4

TAKEN BY: SALESREP

CONTACT: DON JENKINS

TITLE: ENGINEER

PHONE: 309-823-5461

SURVEY COMMENTS: ANALYZE AT ELK GROVE

L#12086-6

CORPORATE REVIEWS: DISPOSITION REVIEWER DATE

TECHNICAL: ACCEPT JHP 06/18/91

REGULATORY: ACCEPT AAD 06/18/91

OPERATING: ACCEPT JWH 06/18/91

PRICING CODE: F1

APPROVED FACILITIES:

(658) SAFETY-KLEEN CORP (654) SAFETY-KLEEN CORP

STATE HWY 146

633 EAST 138TH ST

NEW CASTLE KY 40050

DOLTON IL 60419

FED EPA#: KYD053348108

ILD980613913

STATE EPA#:

0310690006

TELEPHONE: 502/845-2453

708/849-4850

STATE CODE:

000161

EPA WASTE CODES  
F003 D001

APPROVD 0000537 DRUM

DOT-EPA WASTE FLAMMABLE LIQUID, N.O.S.

DESC. (METHYL ISOBUTYL KETONE) UN1993

(F003)(ERG #27)

COMMENTS: OK FOR FUEL. FRS PART 82101.

THIS SERVES AS NOTICE PER, 40CFR264.12(B), THAT THE FACILITY(IES) NOTED ABOVE  
HAS THE APPROPRIATE PERMITS AND IS WILLING TO RECEIVE THE MATERIAL DESCRIBED.



ACCEPT  
NO ATTACHMENTFLUID RECOVERY  
EUREKA

\*\* FLUID RECOVERY \*\*

## GENERAL ANALYSIS OF TOTAL SAMPLE

COLOR : GRAY/BLUE  
 WATER CONTENT : 1.9 WT%  
 NON-VOLATILE RESIDUE : 31.6 WT% DESCRIPTION: SOLID  
 FLAMMABILITY : FLASHED AT 140 F BY SETAFLASH  
 FLAMMABILITY : FLASHED AT 100 F BY SETAFLASH  
 PH : EXTRACT BY METER 5.9  
 RADIOACTIVITY : NONE DETECTED

## FUEL EVALUATION OF TOTAL SAMPLE

HEAT CONTENT : 13800 BTU/LB  
 TOTAL CHLORINE CL : 0.2 WT%  
 TOTAL FLUORINE F : < 0.1 WT%  
 ASH UPON COMBUSTION : 1.3 WT%  
 TOTAL BROMINE BR : < 0.1 WT%  
 TOTAL SULFUR S : < 0.1 WT%

## GENERAL COMPOSITION:

SPECIFIC  
GRAVITYVISCOSITY  
(CENTIPOISE)

## GENERAL COMPOSITION BY:

APPEARANCE TOTAL  
(VOL%) (WT %)

AQUEOUS PHASE (FREE WATER)		0.0	0.0
ORGANIC PHASE (FEEDSTOCK)		100.0	100.0
BOTTOM SLUDGE (SEMISOLIDS)		0.0	0.0
BOTTOM SOLID (SETTLED SOLIDS)		0.0	0.0
TOTAL	.930 < 50 CPS	100.0	100.0

## SPECIFIC COMPOSITION OF TOTAL SAMPLE

## COMPOSITION OF:

	TOTAL SAMPLE (WT%)	TOTAL SAMPLE (WT%)
WATER CONTENT	1.9	1.9
NON-VOLATILE RESIDUE DESCRIPTION: SOLID	31.6	31.6
VOLATILE ORGANICS BY DIFFERENCE	66.5	66.5
TOTAL	100.0	100.0

## VOLATILE ORGANIC COMPOSITION OF ORGANIC PHASE BY GAS CHROMATOGRAPHY

SAMPLE PREPARATION METHODS: NEAT  
 DETECTION METHODS : FID, FID

## COMPOUND NAME

## COMPOSITION OF:

VOLATILE  
ORGANICS  
(WT%)VOLATILE  
ORGANICS  
(WT%)TOTAL  
SAMPLE  
(WT%)

METHYL ISOBUTYL KETONE	MIBK	108-10-1	65.5	65.5	43.6
MEDIUM-BOILING ALIPHATIC HYDROCARBONS (C9-C13)	MHC	8030-30-6	6.8	6.8	4.5
ETHYLENE GLYCOL BUTYL ETHER	EGBE	111-76-2	6.7	6.7	4.5
XYLENES (ORTHO-, META-, AND PARA-)	XYLS	1330-20-7	4.5	4.5	3.0
LOW-BOILING ALIPHATIC HYDROCARBONS (C5-C8)	LHC	64741-89-5	4.2	4.2	2.8
BUTYL ALCOHOL, ISO-	IBA	78-83-1	3.4	3.4	2.3
METHYL ALCOHOL	MEOH	67-56-1	3.2	3.2	2.1
TOTAL OTHERS (<1.0% EACH)	TO	0-05-5	2.2	2.2	1.5
ACETONE	ACE	67-64-1	2.1	2.1	1.4
ETHYLBENZENE	ETB	100-41-4	1.4	1.4	0.9
TOTAL			100.0	100.0	66.5

## SUMMARY OF VOLATILE ORGANIC COMPOSITION BY COMPOUND CHEMICAL CLASS WT%:

ALCOHOLS	6.6	ALIPHATIC HYDROCARBONS	11.0
AROMATIC HYDROCARBONS	5.9	CHLORINATED SOLVENTS	
ESTERS		ETHERS	
GLYCOL ETHERS	6.7	INHIBITORS	
KETONES	67.6	NITROGEN COMPOUNDS	

## SPECIFIC ORGANIC COMPOSITION

POLYCHLORINATED BIPHENYLS (PCBS): NONE DETECTED &lt;

ADDITIONAL ANALYTICAL INFORMATION: IBA 1.9% BY ESTD%

SAFETY-KLEEN CORP.  
PREQUALIFICATION EVALUATION  
MATERIAL ANALYSISPAGE 3 OF 3  
COMPLETE: 06/20/91  
CONTROL#: 0099216-8  
SAMPLE# : 202591FLUID RECOVERY  
EUREKAACCEPT  
NO ATTACHMENT

\*\* FLUID RECOVERY \*\*

LABORATORY REVIEW: A  
LEVEL: SEG CODE: RELEASED: 06/20/91  
LAB REVIEWERS: AJ AJ ANALYZED: 06/17/91TRACKING INFORMATION: DATE FACILITY  
SURVEY RECEIVED : 06/03/91 SK TECHNICAL CEN  
SAMPLE RECEIVED : 06/03/91  
RESAMPLE SHIPPED :  
RESAMPLE RECEIVED:

THE ANALYSES CONTAINED HEREIN ARE PERFORMED SOLELY FOR THE PURPOSE OF QUALIFYING THE ANALYZED MATERIALS FOR ACCEPTANCE BY SAFETY-KLEEN IN ACCORDANCE WITH ITS PERMITS AND PROCESSING CAPABILITY.

NOTICE OF LAND DISPOSAL RESTRICTION OF WASTE IS REQUIRED UNDER 40 CFR PART 268.

EPA WASTE CODES FOR LDR: F003 D001

ANALYSIS DOES NOT INDICATE THAT MATERIAL IS CALIFORNIA LIST HALOGENATED ORGANIC COMPOUND WASTE.



# Daily Analytical Laboratories

7807 N. Pioneer Lane • Peoria, Illinois 61615 Tel. 309-692-5252



Eugene J. Daily, Chairman  
John P. Higgins, President  
Otis E. Michels, Vice President  
James F. Dallmeyer  
Laboratory Director

TO: Eureka Company DATE RECEIVED 1-7-85  
1201 E. Bell Street CLIENT P.O. # \_\_\_\_\_  
Bloomington, IL 61701 D/A PROJECT # 5183.00  
ATTENTION: Mr. Don Jenkins DATE OF REPORT 1-11-85

D/A SAMPLE NO.		5007-05	5007-06	5007-07		
SAMPLE DESCRIPTION		Scrap Stoddard	Scrap Solvent Reduced	Scrap Chlorinated Solvent		
SAMPLE DATE		1-2-85	1-2-85	1-2-85		
Flashpoint	°F	92	73	185		
% Solids	%	7.4	11	2.7		
Cyanide	mg/kg	<0.13	0.54	< 0.09		
pH *	Units	6.3	6.0	5.0		
Sulfide	mg/kg	<10	< 10	< 10		
Phenol	mg/kg	9.6	2.6	9.5		
E.P. TOXICITY						
Arsenic	ug/l	280	59	98		
Barium	ug/l	24,000	< 2,100	< 2,100		
Cadmium	ug/l	700	< 240	270		
Chromium	ug/l	<240	< 240	< 240		
Lead	ug/l	5,700	< 440	< 440		
Mercury	ug/l	120	<12	36		
Selenium	ug/l	<15	< 15	< 15		
Silver	ug/l	< 240	< 240	< 240		

## abbreviated report sheet

\*10% Mixture in DDI Water.

ug/l = parts per billion

1,000 ug/l = 1 mg/l

Analysis Certified By: \_\_\_\_\_

John R. LaPayne, Chief Chemist

Analysis and Testing shall be performed in accord with U.S. EPA's current manual of practice or with other procedures acceptable to U.S. EPA and IEPA.



# PDC Laboratories, Inc.

4349 Southport Rd. • Peoria, IL 61615  
809.678.4893

## ANALYTICAL REPORT FORM

To: The Eureka Company Sales Rep                       
1201 East Bell Street Sample                       
Bloomington, IL 61701 PDC # 806198  
                     Date Received 06-24-88 Permit #                       
Attn: Don Jenkins Date of Report 08-04-88 P.O. # 54453  
Waste Stream Neutralized Paint Sludge

Odor Slight Physical State Solid  
Color Gray Number of Phases 1  
Bulk Density 1,350 lb/yd<sup>3</sup> Water Reactivity None  
pH            (neat); 9.9 (10% solution) Paint Filter Pass  
Flashpoint >200 °F Load Bearing Capacity (ton/sq.ft.)                       
% Solids 69 Leachable Cyanide                      mg/l

	Totals (mg/kg)	EP Toxicity (mg/l)		(mg/kg)
Aluminum			Acidity	
Antimony			Alkalinity	
Arsenic	<2.5	<0.5	Cyanide (Total)	<0.31
Barium	260	<10	Cyanide (Reactive)	
Cadmium	4.3	0.2	EOX	<20
Chromium (Total)	25	0.5	Oil & Grease	
Chromium (Hex.)		<0.05	Phenol (Total)	4.6
Copper			Sulfide (Total)	<0.53
Iron			Sulfide (Reactive)	
Lead	53	<0.5	TOC	
Manganese				
Mercury	0.023			
Nickel				
Selenium	6.7	<0.10		
Silver	<2.5	<0.5		
Zinc				

(1) Run according to Illinois Pollution Control (6/84) Section 729.320/321.

John R. Lavigne  
Laboratory Manager  
PDC Laboratories, Inc.

John R. Davis  
Quality Assurance Officer  
PDC Laboratories, Inc.


Analyses conducted utilizing USEPA, IEPA or other recognized methods.  
Subsidiary of PDC Technical Services, Inc.




PDC Laboratories, Inc.

CLIENT The Eureka Co.  
DATE RECEIVED 09-17-90  
DATE OF REPORT 09-21-90  
SAMPLE DESCRIPTION Neutral Paint Sludge  
P.O. NUMBER 44148  
LAB NUMBER 90090539

LAB NUMBER	ANALYSIS	RESULTS
90090539	TCLP Arsenic	<0.05 mg/l
	Barium	0.5 mg/l *
	Cadmium	0.03 mg/l *
	Chromium	0.03 mg/l *
	Lead	<0.25 mg/l *
	Mercury	<0.001 mg/l
	Selenium	<0.4 mg/l *
	Silver	0.07 mg/l *
	Arsenic Spike Recovery	76 %
	Barium Spike Recovery	59 %
	Cadmium Spike Recovery	66 %
	Chromium Spike Recovery	66 %
	Lead Spike Recovery	61 %
	Mercury Spike Recovery	119 %
	Selenium Spike Recovery	88 %
	Silver Spike Recovery	71 %
	* Performed by Method of Standard Additions.	

  
Laboratory Manager  
by JRD

TCLP-Metals:edd

  
Quality Assurance Officer




PDC Laboratories, Inc.

TOXICITY CHARACTERISTIC  
CONSTITUENTS (TCLP)


CLIENT The Eureka Company  
DATE RECEIVED 06-25-90  
DATE OF REPORT 07-24-90  
SAMPLE DESCRIPTION Neutral Paint  
Sludge  
P.O. NUMBER 44148  
LAB NUMBER 90060811

COMPOUND	SAMPLE CONCENTRATION mg/l	REGULATORY THRESHOLD mg/l
<u>VOLATILES</u>		
Vinyl Chloride	<0.2	0.2
1,1-Dichloroethene	<0.1	0.7
Chloroform	<0.1	6.0
1,2-Dichloroethane	<0.1	0.5
Carbon Tetrachloride	<0.1	0.5
Trichloroethene	<0.1	0.5
Benzene	<0.1	0.5
Tetrachloroethene	<0.1	0.7
Chlorobenzene	<0.1	100.0
1,4-Dichlorobenzene	<0.1	7.5
2-Butanone (MEK)	<0.2	200.0
<u>BASE/NEUTRALS</u>		
Hexachloroethane	<0.02	3.0
Hexachlorobutadiene	<0.02	0.5
2,4-Dinitrotoluene	<0.02	0.13 *
Hexachlorobenzene	<0.02	0.13 *
Pyridine	<0.02	5.0 *
Nitrobenzene	<0.02	2.0
<u>ACIDS</u>		
2,4,6-Trichlorophenol	<0.02	2.0
2,4,5-Trichlorophenol	<0.1	400.0
Pentachlorophenol	<0.1	100.0
o-Cresol	<0.02	200.0
m,p-Cresol	<0.02	200.0

\* If the quantitation limit is greater than calculated regulatory level,  
the quantitation limit then becomes the regulatory level.

  
Laboratory Manager

TCLP-1:edd

  
Quality Assurance Officer







Environmental  
Science &  
Engineering, Inc.

8901 North Industrial Road  
Peoria, IL 61615-1589  
Phone (309) 692-4422  
Fax (309) 692-9364

An IEPA Contract Laboratory

TO: The Eureka Company  
1201 E. Bell Street  
Bloomington, IL 61701  
ATTN: Mr. Dean Shoemaker

REPORT DATE: 11-1-91  
DATE RECEIVED: 10-11-91  
PROJECT NO.: 591-5249  
P.O. NO.: 54177

ISE SAMPLE --- 5047-1 5047-2  
SAMPLE DATE --- 10-10-91 10-10-91

DESCRIPTION	Quant. Limit	SCOilMAIN Oil	SCOilCOOL Oil	METHOD NO.	DATE ANALYZED	ANALYST
TCIP Metals, mg/l						
Arsenic	0.50	< 0.50	< 0.50	6010	10-22-91	GRS
Barium	0.10	0.283	1.01	6010	10-22-91	GRS
Cadmium	0.050	< 0.050	< 0.050	6010	10-22-91	GRS
Chromium	0.10	< 0.10	< 0.10	6010	10-22-91	GRS
Lead	0.50	< 0.50	< 0.50	6010	10-22-91	GRS
Mercury	0.0005	< 0.0005	< 0.0005	7471	10-22-91	FWM
Selenium	0.075	< 0.075	< 0.075	6010	10-22-91	GRS
Silver	0.10	< 0.10	< 0.10	6010	10-22-91	GRS

PCBs, mg/kg  
Aroclor-1016  
Aroclor-1221  
Aroclor-1232  
Aroclor-1242  
Aroclor-1248  
Aroclor-1254  
Aroclor-1260

1.0	< 1.0	< 1.0	8080	10-15-91	RDU
1.0	< 1.0	< 1.0	8080	10-15-91	RDU
1.0	< 1.0	< 1.0	8080	10-15-91	RDU
1.0	< 1.0	< 1.0	8080	10-15-91	RDU
1.0	< 1.0	< 1.0	8080	10-15-91	RDU
1.0	< 1.0	< 1.0	8080	10-15-91	RDU
1.0	< 1.0	< 1.0	8080	10-15-91	RDU

Report Approved by: Vickie M. Wynkoop  
Vickie M. Wynkoop  
Project Manager



Environmental  
Science &  
Engineering, Inc.

8901 North Industrial Road  
Phone (309) 692-4422

Peoria, IL 61615-1589  
Fax (309) 692-9364

An IEPA Contract Laboratory

TO: The Eureka Company  
1201 E. Bell Street  
Bloomington, IL 61701  
ATTN: Mr. Dean Shoemaker

REPORT DATE: 11-1-91  
DATE RECEIVED: 10-11-91  
PROJECT NO.: 591-5249  
P.O. NO.: 54177

ESE SAMPLE  
SAMPLE DATE

5047-1 5047-2  
10-10-91 10-10-91

DESCRIPTION

Quant.  
Limit

SCOILMAIN SCCIMCOOL  
OIL OIL

METHOD  
NO. DATE  
ANALYZED ANALYST

Other Parameters

pH, units -  
Cyanide, Total, mg/l 0.10  
Cyanide, Reactive, mg/l 0.10  
Sulfide, Total, mg/l 4  
Sulfide, Reactive, mg/l 4  
Total Solids, mg/l 1.0  
Flash Point, Deg-C 25  
Phenols, mg/l 0.050

6.62 6.46  
< 0.10 < 0.10  
< 0.10 < 0.10  
16 68  
6 43  
95.2 15.4  
> 100 > 100  
2.51 1.10

150.1 10-12-91 RAU  
9010 10-15-91 KMC  
9010 10-15-91 KMC  
9030 10-15-91 KMC  
9030 10-15-91 KMC  
160.3 10-12-91 RAU  
1010 10-15-91 KMC  
9065 10-21-91 NEB

Report Approved by: Vickie M. Wynkoop  
Vickie M. Wynkoop  
Project Manager

SDF/L/11.2



Environmental  
Science &  
Engineering, Inc.

8901 N. Industrial Road  
Peoria, Illinois 61615-1589

(309) 692-4422  
Fax (309) 692-9364

An IEPA Contract Laboratory

TO: The Eureka Company  
1201 E. Bell Street  
Bloomington, IL 61701  
ATTN: Mr. Dean Shoemaker

REVISED DATE: 12-23-91  
DATE: 11-1-91  
DATE RECEIVED: 10-11-91  
PROJECT NO.: 591-5249  
P. O. NO.: 54177

ESE SAMPLE: 5047-1  
SAMPLE DATE: 10-10-91  
DESCRIPTION: SCOILMAIN OIL

Parameter	TCLP Concentration (mg/l)	Maximum Allowable Concentration (mg/l)
-----------	------------------------------	---

TCLP VOLATILE ORGANIC COMPOUNDS

METHOD NO.:	8240	
DATE ANALYZED:	10-15-91	
ANALYST:	EPL	
Benzene	< 0.05	0.5
Carbon Tetrachloride	< 0.05	0.5
Chlorobenzene	< 0.10	100.0
Chloroform	< 0.05	6.0
1,2-Dichloroethane	< 0.05	0.5
1,1-Dichloroethylene	< 0.05	0.7
Methyl ethyl ketone	< 0.10	200.0
Tetrachloroethylene	< 0.05	0.7
Trichloroethylene	< 0.05	0.5
Vinyl chloride	< 0.10	0.2

TCLP SEMIVOLATILE ORGANIC COMPOUNDS

METHOD NO.:	8270	
DATE ANALYZED:	10/29-30/91	
ANALYST:	PEM	
Total Cresols (o + m + p)	< 0.30	200.0
1,4-Dichlorobenzene	< 0.40	7.5
2,4-Dinitrotoluene	< 0.56*	0.13
Hexachlorobenzene	< 0.29*	0.13
Hexachlorobutadiene	< 0.31	0.5
Hexachloroethane	< 0.57	3.0
Nitrobenzene	< 0.42	2.0
Pentachlorophenol	< 0.50	100.0
Pyridine	< 1.4*	5.0
2,4,5-Trichlorophenol	< 0.50	400.0
2,4,6-Trichlorophenol	< 0.50	2.0

TCLP results are corrected for spike recoveries.

\*Matrix interference encountered in the organic extraction procedure  
resulted in higher than normal detection limits.

Report Approved by:

*Vickie M. Wynkoop*  
Vickie M. Wynkoop  
Project Manager

SDF/L:12.1



Environmental  
Science &  
Engineering, Inc.

8901 N. Industrial Road  
Peoria, Illinois 61615-1589

(309) 692-4422  
Fax (309) 692-9364

An IEPA Contract Laboratory

TO: The Eureka Company  
1201 E. Bell Street  
Bloomington, IL 61701  
ATTN: Mr. Dean Shoemaker

REVISED DATE: 12-23-91  
DATE: 11-1-91  
DATE RECEIVED: 10-11-91  
PROJECT NO.: 591-5249  
P. O. NO.: 54177

ESE SAMPLE: 5047-2  
SAMPLE DATE: 10-10-91  
DESCRIPTION: SCCIMCOOL OIL

Parameter	TCLP Concentration (mg/l)	Maximum Allowable Concentration (mg/l)
-----------	------------------------------	---

TCLP VOLATILE ORGANIC COMPOUNDS

METHOD NO.:	8240	
DATE ANALYZED:	10-15-91	
ANALYST:	EPL	
Benzene	< 0.05	0.5
Carbon Tetrachloride	< 0.05	0.5
Chlorobenzene	< 0.10	100.0
Chloroform	< 0.05	6.0
1,2-Dichloroethane	< 0.05	0.5
1,1-Dichloroethylene	< 0.05	0.7
Methyl ethyl ketone	0.38	200.0
Tetrachloroethylene	< 0.05	0.7
Trichloroethylene	< 0.05	0.5
Vinyl chloride	< 0.10	0.2

TCLP SEMIVOLATILE ORGANIC COMPOUNDS

METHOD NO.:	8270	
DATE ANALYZED:	10/29-30/91	
ANALYST:	PEM	
Total Cresols (o + m + p)	0.669	200.0
1,4-Dichlorobenzene	< 0.29	7.5
2,4-Dinitrotoluene	< 0.35*	0.13
Hexachlorobenzene	< 0.42*	0.13
Hexachlorobutadiene	< 0.28	0.5
Hexachloroethane	< 0.40	3.0
Nitrobenzene	< 0.25	2.0
Pentachlorophenol	< 0.50	100.0
Pyridine	< 0.42	5.0
2,4,5-Trichlorophenol	< 0.50	400.0
2,4,6-Trichlorophenol	< 0.50	2.0

TCLP results are corrected for spike recoveries.

\*Matrix interference encountered in the organic extraction procedure resulted in higher than normal detection limits.

Report Approved by: Vickie M. Wynkoop  
Vickie M. Wynkoop  
Project Manager

SDF/L:12.2



Environmental  
Science &  
Engineering, Inc.

December 20, 1991

Mr. Dean Shoemaker  
The Eureka Company  
1201 E. Bell Street  
Bloomington, IL 61701

Dear Mr. Shoemaker:

Our laboratory recently analyzed two samples for The Eureka Company for the Toxicity Characteristic Leaching Process (TCLP) targets. The samples were collected 10 October, and received by our laboratory 11 October. The samples were identified on the chain of custody as SCOILMAIN OIL and SCCIMCOOL OIL (E.S.E. identification numbers 5047-1 and 5047-2, respectively). The report indicates that the semivolatile organic compounds 2,4-dinitrotoluene and hexachlorobenzene are above the regulatory limits of 0.13 mg/L for each of the two samples.

TCLP leachates are extracted for semivolatile organic analyses and analyzed by U.S. EPA SW846 Method 8270. No TCLP targets were detected. However, the reporting limits (concentrations on the report form) are determined by the instrument sensitivity, the amount of initial starting material, the final volume of the extract, and matrix spike recovery data. For these two samples, the final volume of the extracts were twenty-five times the usual volume due to high concentrations of hydrocarbon compounds. As a result, even though no TCLP targets were detected, the concentrations reported must reflect the matrix interference.

In reviewing the data and results for these two samples, I noticed two errors:


The reported pyridine result for sample SCOILMAIN OIL is above the regulatory limit of 5.0 mg/L. This was an error on our part. A corrected report will be sent to you indicating that the pyridine value is less than 1.4 mg/L. This value is above the usual reporting limits for pyridine, but well below the regulatory limit.


The vinyl chloride value of sample SCCIMCOOL OIL was reported as 0.10 mg/L. It should have been reported as less than (<). This has been corrected on the report.

If you have any questions or need more information, please call us.

Sincerely,

ENVIRONMENTAL SCIENCE & ENGINEERING, INC.

  
Tom Johnson  
GC/MS Supervisor

  
Vickie M. Wynkoop  
Project Manager

BTJ.171



Environmental  
Science &  
Engineering, Inc.

8901 N. Industrial Road  
Peoria, Illinois 61615-1589

(309) 692-4422  
Fax (309) 692-9364

An IEPA Contract Laboratory

January 6, 1992

Mr. Rich Johnson  
Division of Land Pollution Control  
Illinois EPA  
4500 S. Sixth Street Road  
Springfield, IL 62706

Dear Mr. Johnson:

You recently requested further clarification of the results of two analyses our laboratory recently performed for The Eureka Company.

The two samples were identified as SCOILMAIN OIL and SCCIMCOOL OIL (E.S.E. identification numbers 5047-1 and 5047-2, respectively). The samples were extracted for the Toxicity Characteristic Leaching Process (TCLP). Two hundred milliliters of the TCLP extract of each sample was then extracted for the semivolatile organic compounds of the TCLP target list. This provided a dilution factor of 5; i.e., 200 mL of extract diluted to one liter for continuous liquid/liquid extraction.

A separate extraction for a matrix spike of the semivolatile organics of the TCLP target list was also extracted for each sample to determine the target compound recoveries from each sample. The final volume of each of the semivolatile extracts was 5 milliliters, rather than the usual 1 milliliter. This provided another dilution factor of 5 for the TCLP targets. The final effective dilution factor for each sample and its matrix spike was thus 25. This resulted from the high concentration of hydrocarbon pattern evidenced in the chromatograms of the analyses by GC/MS (U.S. EPA SW846 Method 8270 for semivolatile organics).

The analyst performed a manual search for each of the characteristic ions of the TCLP target compounds in the chromatograms of the sample analyses and the matrix spike analyses. This was necessary because of the matrix interference of each sample. No mass spectral patterns were detected within appropriate retention time windows for 2,4-dinitrotoluene and hexachlorobenzene in either sample. The detection limit used for the searches was 1 ng, which represents from 0.029 to 0.056 mg/L after corrections for dilution factors and matrix spike recoveries. This amount is one tenth of the normal instrument reporting limits, and below the regulatory limit of 0.13 mg/L for each of the target compounds of concern.

Such low values are not normally reported because they represent an undocumented extrapolation of the initial calibration of the instrument and methods used. Nevertheless, our data reduction procedures indicate that the semivolatile organic (BNA) TCLP extracts contain less than the regulatory limits of the two target compounds in question. This conclusion is consistent with information from our client, Mr. Dean Shoemaker of The Eureka Company, indicating that 2,4-dinitrotoluene and hexachlorobenzene are not utilized in the processes that produced the samples.


If you have any questions or need more information, please call us.

Sincerely,

ENVIRONMENTAL SCIENCE & ENGINEERING, INC.



Tom Johnson  
GC/MS Supervisor



Vickie M. Wynkoop  
Project Manager

cc: Dean Shoemaker

BTJ.171(3,4)







# Daily Analytical Laboratories

1621 W. Candletree Drive Peoria, Illinois 61614  
Tel. (309) 692-5252

Eugene J. Daily, Chairman  
John P. Higgins, President  
Otis E. Michels, Vice President  
James F. Dallmeyer  
Laboratory Director

TO: The Eureka Company DATE RECEIVED 8-13-86  
1201 E. Bell Street CLIENT P.O. #  
Bloomington, IL 61701 D/A PROJECT # 5060.10  
ATTENTION: Mr. Don Jenkins DATE OF REPORT 9-3-86

D/A SAMPLE NO.		6225-12			
SAMPLE DESCRIPTION		Water Reduced paint 9:30			
SAMPLE DATE		8-7-86			
Cyanide, Total	mg/kg	< 0.12			
Sulfide	mg/kg	< 1			
Phenols	mg/kg	< 1.0			
pH	Units	* 8.3			
% Solid	%w/w	47%			
Flashpoint	°F	> 200°			
Chromium, Hexavalent	mg/kg	0.24			
Reactive Cyanide	mg/kg	< 0.12			
Reactive Sulfide	mg/kg	< 1			
EP TOXICITY					
Arsenic	ug/l	< 40			
Barium	ug/l	200			
Cadmium	ug/l	< 20			
Chromium,	ug/l	90			
Lead	ug/l	< 40			
Mercury	ug/l	< 0.2			
Selenium	ug/l	< 40			
Silver	ug/l	< 20			

abbreviated report sheet

\* pH is a 10% mixture in lab pure water

Analysis Certified By:

John R. LaPayne, Chief Chemist

Analysis and Testing shall be performed in accord with U.S. EPA's current manual of practice  
or with other procedures acceptable to U.S. EPA and IEPA.

100% Recycled Paper








PDC Laboratories, Inc.


TOXICITY CHARACTERISTIC  
CONSTITUENTS (TCLP)

CLIENT The Eureka Company  
DATE RECEIVED 08-09-90  
DATE OF REPORT 09-11-90  
SAMPLE DESCRIPTION Paint Booth  
Filters  
P.O. NUMBER 44148  
LAB NUMBER 90080437

COMPOUND	SAMPLE CONCENTRATION mg/l	REGULATORY THRESHOLD mg/l
<u>VOLATILES</u>		
Vinyl Chloride	<0.2	0.2
1,1-Dichloroethene	<0.1	0.7
Chloroform	<0.1	6.0
1,2-Dichloroethane	<0.1	0.5
Carbon Tetrachloride	<0.1	0.5
Trichloroethene	<0.1	0.5
Benzene	<0.1	0.5
Tetrachloroethene	<0.1	0.7
Chlorobenzene	<0.1	100.0
1,4-Dichlorobenzene	<0.1	7.5
2-Butanone (MEK)	<0.2	200.0
<u>BASE/NEUTRALS</u>		
Hexachloroethane	<0.5	3.0
Hexachlorobutadiene	<0.3	0.5
2,4-Dinitrotoluene	<0.13	0.13 *
Hexachlorobenzene	<0.13	0.13 *
Pyridine	<0.2	5.0 *
Nitrobenzene	<0.2	2.0
<u>ACIDS</u>		
2,4,6-Trichlorophenol	<0.2	2.0
2,4,5-Trichlorophenol	<1.0	400.0
Pentachlorophenol	<1.0	100.0
o-Cresol	<0.2	200.0
m,p-Cresol	<0.2	200.0

\* If the quantitation limit is greater than calculated regulatory level, the quantitation limit then becomes the regulatory level.

  
Laboratory Manager

  
Quality Assurance Officer

TCLP-1:edd

# DA Daily Analytical Laboratories

1621 W. Candletree Drive Peoria, Illinois 61614  
Tel. (309) 692-5252

The Eureka Company  
1201 East Bell Street  
Bloomington, IL. 61701

Attn: Mr. Don Jenkins

Date Received: 10/12/88  
Date of Report: 11/01/88  
Work Order: 88-10-231  
Job Number:  
# of Samples: 1

Work ID: Strip Waste Paint Booth Filt.  
P O # : 54426

Test	Units	Waste Paint Filter
Silver, Total	mg/kg	<0.50
Arsenic, Total	mg/kg	<1.4
Barium, Total	mg/kg	730
Cadmium, Total	mg/kg	<0.25
Chromium, Total	mg/kg	5.7
Mercury, Total	mg/kg	<0.01
Lead, Total	mg/kg	75
Selenium, Total	mg/kg	<0.55
Metals Digest Nonaqueous	date of prep.	10/13/88
Barium, EP Toxicity	mg/l	0.04
Chromium, EP Toxicity	mg/l	<0.01
Lead, EP Toxicity	mg/l	0.05
EP TOX Extraction	date of prep.	10/19/88
Cyanide, Reactive	mg/kg	<1.0
Cyanide, Total	mg/kg	<1.0
Paint Filter	none	pass
Flashpoint	degrees F	>200
Phenol	mg/kg	<2.4
pH Nonaqueous	units	3.9
Reactive Sulfide	mg/kg	<7.5
Total Sulfide	mg/kg	<7.5

---

# DA Daily Analytical Laboratories

1621 W. Candletree Drive Peoria, Illinois 61614  
Tel. (309) 692-5252

Page 2  
Received: 10/12/88


DAILY LABS  
11/01/88 13:52:09

REPORT

Work Order # 88-10-231  
Continued From Above

Test	Units	Waste Paint Filter
Total Organic Carbon		
	mg/kg	>170,000
Extract. Organic Halogen		
	mg/kg	<40
Total Solids		
	zw/w	93

Certified By:

  
David J. Cirilli, Chemist



**ATTACHMENT F**  
**TANK REMOVAL CERTIFICATION**



The Eureka Company  
A Division of National  
Union Electric Corporation  
Bloomington, IL 61701-6902

November 30, 1988

Underground Storage Tank Program  
Office of Illinois State Fire Marshall  
3150 Executive Park Drive  
Springfield, IL 62703-4599


Gentlemen:

In reference to our underground storage tanks located at 1201 East Bell Street, Bloomington, IL, Facility No. 4019095; The Eureka Company had previously notified your office of four underground tanks in use, these tanks were numbered 1 through 4. Tanks #2 and #3 were removed and scrapped on June 15, 1988.


The Pemco Service Company of Bloomington, IL was contracted to perform this work. Mr. Mark Segobiano, Inspector for the Bloomington Fire Department, was contacted and kept informed of the activity. It was determined that the exposed and excavated soil presented no evidence of contamination. This area has since been backfilled and concrete paved.

In regard to the above information, we request that tanks #2 and #3 be deleted from your records. Thank you for your help in this matter.


Sincerely,



Don Jenkins  
Environmental Engineer



Authorized Signature



Title

DJ:tat

# Notification for Underground Storage Tanks

FORM APPROVED  
OMB NO. 2050-0048  
APPROVAL EXPIRES 6-30-89

FOR  
TANKS  
IN  
IL

RETURN  
COMPLETED  
FORM  
TO

UST Coordinator  
Division of Fire Prevention  
P.O. Box 3803  
Springfield, IL 62708-3803

I.D. Number

STATE USE ONLY

Date Received

## GENERAL INFORMATION

Notification is required by Federal law for all underground tanks that have been used to store regulated substances since January 1, 1974, that are in the ground as of May 8, 1986, or that are brought into use after May 8, 1986. The information requested is required by Section 9002 of the Resource Conservation and Recovery Act, (RCRA), as amended.

The primary purpose of this notification program is to locate and evaluate underground tanks that store or have stored petroleum or hazardous substances. It is expected that the information you provide will be based on reasonably available records, or, in the absence of such records, your knowledge, belief, or recollection.

**Who Must Notify?** Section 9002 of RCRA, as amended, requires that, unless exempted, owners of underground tanks that store regulated substances must notify designated State or local agencies of the existence of their tanks. Owner means—  
(a) in the case of an underground storage tank in use on November 8, 1984, or brought into use after that date, any person who owns an underground storage tank used for the storage, use, or dispensing of regulated substances, and  
(b) in the case of any underground storage tank in use before November 8, 1984, but no longer in use on that date, any person who owned such tank immediately before the discontinuation of its use.

**What Tanks Are Included?** Underground storage tank is defined as any one or combination of tanks that (1) is used to contain an accumulation of "regulated substances," and (2) whose volume (including connected underground piping) is 10% or more beneath the ground. Some examples are underground tanks storing: 1. gasoline, used oil, or diesel fuel, and 2. industrial solvents, pesticides, herbicides or fumigants.

**What Tanks Are Excluded?** Tanks removed from the ground are not subject to notification. Other tanks excluded from notification are:

1. farm or residential tanks of 1,100 gallons or less capacity used for storing motor fuel for noncommercial purposes;
2. tanks used for storing heating oil for consumptive use on the premises where stored;
3. septic tanks;

4. pipeline facilities (including gathering lines) regulated under the Natural Gas Pipeline Safety Act of 1968, or the Hazardous Liquid Pipeline Safety Act of 1979, or which is an intrastate pipeline facility regulated under State laws;
5. surface impoundments, pits, ponds, or lagoons;
6. storm water or waste water collection systems;
7. flow-through process tanks;
8. liquid traps or associated gathering lines directly related to oil or gas production and gathering operations;
9. storage tanks situated in an underground area (such as a basement, cellar, mineworking, drift, shaft, or tunnel) if the storage tank is situated upon or above the surface of the floor.

**What Substances Are Covered?** The notification requirements apply to underground storage tanks that contain regulated substances. This includes any substance defined as hazardous in section 101 (14) of the Comprehensive Environmental Response, Compensation and Liability Act of 1980 (CERCLA), with the exception of those substances regulated as hazardous waste under Subtitle C of RCRA. It also includes petroleum, e.g., crude oil or any fraction thereof which is liquid at standard conditions of temperature and pressure (60 degrees Fahrenheit and 14.7 pounds per square inch absolute).

**Where To Notify?** Completed notification forms should be sent to the address given at the top of this page.

**When To Notify?** 1. Owners of underground storage tanks in use or that have been taken out of operation after January 1, 1974, but still in the ground, must notify by May 8, 1986. 2. Owners who bring underground storage tanks into use after May 8, 1986, must notify within 30 days of bringing the tanks into use.

**Penalties:** Any owner who knowingly fails to notify or submits false information shall be subject to a civil penalty not to exceed \$10,000 for each tank for which notification is not given or for which false information is submitted.

## INSTRUCTIONS

Please type or print in ink all items except "signature" in Section V. This form must be completed for each location containing underground storage tanks. If more than 5 tanks are owned at this location, photocopy the reverse side, and staple continuation sheets to this form.

Indicate number of continuation sheets attached

0

### I. OWNERSHIP OF TANK(S)

Owner Name (Corporation, Individual, Public Agency, or Other Entity)

NATIONAL UNION ELECTRIC CORP.

Street Address

1201 E. BELL STREET

County

MCLEAN

City

BLOOMINGTON ILLINOIS 61701

Area Code

309

Phone Number

828 2367

Type of Owner (Mark all that apply)

☒ Current

☐ State or Local Gov't

☒ Private or Corporate

☐ Former

☐ Federal Gov't (GSA facility I.D. no.)

☐ Ownership uncertain

### II. LOCATION OF TANK(S)

(If same as Section I, mark box here ☐)

Facility Name or Company Site Identifier, as applicable

THE EUREKA COMPANY

Street Address or State Road, as applicable

1201 E. BELL STREET

County

MCLEAN

City (nearest)

BLOOMINGTON ILLINOIS 61701

Indicate number of tanks at this location

4

Mark box here if tank(s) are located on land within an Indian reservation or on other Indian trust lands ☐

### III. CONTACT PERSON AT TANK LOCATION

Name (If same as Section I, mark box here ☐)

DON JENKINS

Job Title

ENVIRONMENTAL ENGINEER

Area Code

309

Phone Number

828 2367

### IV. TYPE OF NOTIFICATION

☐ Mark box here only if this is an amended or subsequent notification for this location.

### V. CERTIFICATION (Read and sign after completing Section VI.)

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this and all attached documents, and that based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the submitted information is true, accurate, and complete.

Name and official title of owner or owner's authorized representative

J.P. OF MANUFACTURING

Signature

Frederick Waldman

Date Signed

4/1/86

CONTINUE ON REVERSE SIDE

VI. DESCRIPTION OF UNDERGROUND STORAGE TANKS (Complete for each tank at this location.)

Tank Identification No. (e.g., ABC-123), or Arbitrarily Assigned Sequential Number (e.g., 1,2,3...)	Tank No. 1	Tank No. 2	Tank No. 3	Tank No. 4	Tank No.
1. Status of Tank (Mark all that apply <input checked="" type="checkbox"/> ) Currently in Use Temporarily Out of Use Permanently Out of Use Brought into Use after 5/8/86	<input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>	<input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>	<input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>	<input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>	<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>
2. Estimated Age (Years)	6	14	14	8	
3. Estimated Total Capacity (Gallons)	560	500	500	1000	
4. Material of Construction (Mark one <input checked="" type="checkbox"/> ) Steel Concrete Fiberglass Reinforced Plastic Unknown Other, Please Specify	<input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> _____	<input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> _____	<input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> _____	<input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> _____	<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> _____
5. Internal Protection (Mark all that apply <input checked="" type="checkbox"/> ) Cathodic Protection Interior Lining (e.g., epoxy resins) None Unknown Other, Please Specify	<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> <input type="checkbox"/> _____	<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> <input type="checkbox"/> _____	<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> <input type="checkbox"/> _____	<input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> <input type="checkbox"/> _____	<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> _____
6. External Protection (Mark all that apply <input checked="" type="checkbox"/> ) Cathodic Protection Painted (e.g., asphaltic) Fiberglass Reinforced Plastic Coated None Unknown Other, Please Specify	<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> <input type="checkbox"/> _____	<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> <input type="checkbox"/> _____	<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> <input type="checkbox"/> _____	<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> <input type="checkbox"/> _____	<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> _____
7. Piping (Mark all that apply <input checked="" type="checkbox"/> ) Bare Steel Galvanized Steel Fiberglass Reinforced Plastic Cathodically Protected Unknown Other, Please Specify	<input type="checkbox"/> <input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> _____	<input type="checkbox"/> <input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> _____	<input type="checkbox"/> <input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> _____	<input type="checkbox"/> <input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> _____	<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> _____
8. Substance Currently or Last Stored in Greatest Quantity by Volume (Mark all that apply <input checked="" type="checkbox"/> ) a. Empty b. Petroleum Diesel Kerosene Gasoline (including alcohol blends) Used Oil Other, Please Specify c. Hazardous Substance Please Indicate Name of Principal CERCLA Substance OR Chemical Abstract Service (CAS) No. Mark box <input checked="" type="checkbox"/> if tank stores a mixture of substances d. Unknown	<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input checked="" type="checkbox"/> <input type="checkbox"/> _____ <input type="checkbox"/> _____ <input type="checkbox"/> <input type="checkbox"/>	<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> _____ <input checked="" type="checkbox"/> <u>TELURENE</u> <u>105883</u> <input type="checkbox"/> <input type="checkbox"/>	<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> _____ <input checked="" type="checkbox"/> <u>VM&amp;P Naphtha</u> <u>8030306</u> <input checked="" type="checkbox"/> <input type="checkbox"/>	<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> _____ <input checked="" type="checkbox"/> <u>VM&amp;P Naphtha</u> <u>8030306</u> <input checked="" type="checkbox"/> <input type="checkbox"/>	<input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/> _____ <input type="checkbox"/> _____ <input type="checkbox"/> <input type="checkbox"/>
9. Additional Information (for tanks permanently taken out of service) a. Estimated date last used (mo/yr) b. Estimated quantity of substance remaining (gal.) c. Mark box <input checked="" type="checkbox"/> if tank was filled with inert material (e.g., sand, concrete)	   <input type="checkbox"/>	   <input type="checkbox"/>	   <input type="checkbox"/>	   <input type="checkbox"/>	   <input type="checkbox"/>

Division of Petroleum & Chemical Safety  
3150 Executive Park Drive  
Springfield, Illinois 62703

Facility # 4-019095  
Permit # 315  
Request Rec'd 04-18-89  
Date 04-19-89

PERMIT FOR REMOVAL OF  
UNDERGROUND STORAGE TANKS FOR PETROLEUM AND HAZARDOUS MATERIALS

Permission to remove underground storage tank or tanks is hereby granted. Such removal shall not commence until April 28, 1989. A seventy-two (72) hour notice is required to confirm final date of the removal for confirmation of our Inspector to be on site. This Office Phone Number is 217-785-5878 or 217-785-1020. You must notify ESDA 1-800-782-7860 or IEPA 217-785-3497 within 24 hours of leaks or contaminated soil. Removal must be in accordance with acceptable closure requirements and procedures, such as API Bulletin 1604. A site assessment must be conducted to determine if a release has occurred.

- 1) Owner. - Corporation, Partnership or Other Business Entity:

The Eureka Company  
Name  
1201 E. Bell Street  
Street Address  
Bloomington Illinois 61701-6902  
City State Zip  
Loren Bean (309)828-2367  
Contact Person Phone

- 2) Name and Location of Facility Where Removal is to Occur:

The Eureka Company  
Name  
1201 E. Bell Street  
Street Address  
Bloomington McLean 61701-2367  
City County Zip  
Loren Bean (309)828-2367  
Contact Person Phone

- 3) ☒ Tank Removal ☐ Abandonment in Place

a) 1-560 Gallon  
1-1000 Gallon  
Number and size of tanks being removed or abandoned  
b) No longer required for our operations  
Reason for removal of tanks  
c) Waiver approval letter date if abandoned in place

- 4) Person, Firm or Company Performing Work:

Pemco Service Co.  
Name  
1321 N. Mason Street  
Street Address  
Bloomington Illinois 61701-6902  
City State Zip  
(309)828-6134 370-90-6989  
Phone Registration No.

- 5) You must notify this Office when completion of tank removal has taken place, on EPA Notification Form 7530, so that appropriate records can be corrected.

Sincerely, W. Dale Tanke  
W. Dale Tanke, Storage Tank Safety Engineer

cc: Local Region  
Local Fire Department

# Notification for Underground Storage Tanks

FORM APPROVED  
OMB NO. 2050-0049  
APPROVAL EXPIRES 6-30-88

FOR  
TANKS  
IN  
IL

RETURN  
COMPLETED  
FORM  
TO

UST Coordinator, Division of Fire Prevention  
Office of State Fire Marshal  
3150 Executive Park Drive  
Springfield, IL 62703-4599

STATE USE ONLY  
I.D. Number 4-019095  
Date Received

## GENERAL INFORMATION

Notification is required by Federal law for all underground tanks that have been used to store regulated substances since January 1, 1974, that are in the ground as of May 8, 1986, or that are brought into use after May 8, 1986. The information requested is required by Section 9002 of the Resource Conservation and Recovery Act, (RCRA), as amended.

The primary purpose of this notification program is to locate and evaluate underground tanks that store or have stored petroleum or hazardous substances. It is expected that the information you provide will be based on reasonably available records, or, in the absence of such records, your knowledge, belief, or recollection.

**Who Must Notify?** Section 9002 of RCRA, as amended, requires that, unless exempted, owners of underground tanks that store regulated substances must notify designated State or local agencies of the existence of their tanks. Owner means —  
(a) in the case of an underground storage tank in use on November 8, 1984, or brought into use after that date, any person who owns an underground storage tank used for the storage, use, or dispensing of regulated substances, and  
(b) in the case of any underground storage tank in use before November 8, 1984, but no longer in use on that date, any person who owned such tank immediately before the discontinuation of its use.

**What Tanks Are Included?** Underground storage tank is defined as any one or combination of tanks that (1) is used to contain an accumulation of "regulated substances," and (2) whose volume (including connected underground piping) is 10% or more beneath the ground. Some examples are underground tanks storing: 1. gasoline, used oil, or diesel fuel, and 2. industrial solvents, pesticides, herbicides or fumigants.

**What Tanks Are Excluded?** Tanks removed from the ground are not subject to notification. Other tanks excluded from notification are:

1. farm or residential tanks of 1,100 gallons or less capacity used for storing motor fuel for noncommercial purposes;
2. tanks used for storing heating oil for consumptive use on the premises where stored;
3. septic tanks;

4. pipeline facilities (including gathering lines) regulated under the Natural Gas Pipeline Safety Act of 1968, or the Hazardous Liquid Pipeline Safety Act of 1979, or which is an intrastate pipeline facility regulated under State laws;

5. surface impoundments, pits, ponds, or lagoons;

6. storm water or waste water collection systems;

7. flow-through process tanks;

8. liquid traps or associated gathering lines directly related to oil or gas production and gathering operations;

9. storage tanks situated in an underground area (such as a basement, cellar, mineworking, drift, shaft, or tunnel) if the storage tank is situated upon or above the surface of the floor.

**What Substances Are Covered?** The notification requirements apply to underground storage tanks that contain regulated substances. This includes any substance defined as hazardous in section 101 (14) of the Comprehensive Environmental Response, Compensation and Liability Act of 1980 (CERCLA), with the exception of those substances regulated as hazardous waste under Subtitle C of RCRA. It also includes petroleum, e.g., crude oil or any fraction thereof which is liquid at standard conditions of temperature and pressure (60 degrees Fahrenheit and 14.7 pounds per square inch absolute).

**Where To Notify?** Completed notification forms should be sent to the address given at the top of this page.

**When To Notify?** 1. Owners of underground storage tanks in use or that have been taken out of operation after January 1, 1974, but still in the ground, must notify by May 8, 1986. 2. Owners who bring underground storage tanks into use after May 8, 1986, must notify within 30 days of bringing the tanks into use.

**Penalties:** Any owner who knowingly fails to notify or submits false information shall be subject to a civil penalty not to exceed \$10,000 for each tank for which notification is not given or for which false information is submitted.

## INSTRUCTIONS

Please type or print in ink all items except "signature" in Section V. This form must be completed for each location containing underground storage tanks. If more than 5 tanks are owned at this location, photocopy the reverse side, and staple continuation sheets to this form.

Indicate number of continuation sheets attached

0

### I. OWNERSHIP OF TANK(S)

Owner Name (Corporation, Individual, Public Agency, or Other Entity)

National Union Electric Corp.

Street Address

1201 E. Bell St.

County

McLean

City

Bloomington

State

Ill

ZIP Code

61701

Area Code

309

Phone Number

828-2367

Type of Owner (Mark all that apply ☒)

☒ Current

☐ State or Local Gov't

☒ Private or Corporate

☐ Former

☐ Federal Gov't (GSA facility I.D. no.)

☐ Ownership uncertain

### II. LOCATION OF TANK(S)

(If same as Section I, mark box here ☐)

Facility Name or Company Site Identifier, as applicable

The Eureka Company

Street Address or State Road, as applicable

1201 E Bell St.

County

McLean

City (nearest)

Bloomington

State

Ill.

ZIP Code

61701

Indicate number of tanks at this location

2

Mark box here if tank(s) are located on land within an Indian reservation or on other Indian trust lands ☐

### III. CONTACT PERSON AT TANK LOCATION

Name (If same as Section I, mark box here ☐)

Loren Benn

Job Title

Plant Engineer

Area Code

309

Phone Number

828-2367

### IV. TYPE OF NOTIFICATION

☒ Mark box here only if this is an amended or subsequent notification for this location.

### V. CERTIFICATION (Read and sign after completing Section VI.)

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this and all attached documents, and that based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the submitted information is true, accurate, and complete.

Name and official title of owner or owner's authorized representative

D. K. Small, Manager of Manufacturing

Signature

DK Small

Date Signed

4/24/89

CONTINUE ON REVERSE SIDE

#### VI. DESCRIPTION OF UNDERGROUND STORAGE TANKS (Complete for each tank at this location.)

Tank Identification No. (e.g., ABC-123), or Arbitrarily Assigned Sequential Number (e.g., 1,2,3...)	Tank No. 1	Tank No. 4	Tank No.	Tank No.	Tank No.
<b>1. Status of Tank</b> (Mark all that apply) <div style="float:right;">Currently in Use</div> <div style="clear:both;"></div> <div style="float:right;">Temporarily Out of Use</div> <div style="clear:both;"></div> <div style="float:right;">Permanently Out of Use</div> <div style="clear:both;"></div> <div style="float:right;">Brought into Use after 5/8/86</div> <div style="clear:both;"></div>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<b>2. Estimated Age (Years)</b>	9	11			
<b>3. Estimated Total Capacity (Gallons)</b>	560	1000			
<b>4. Material of Construction</b> (Mark one) <div style="float:right;">Steel</div> <div style="clear:both;"></div> <div style="float:right;">Concrete</div> <div style="clear:both;"></div> <div style="float:right;">Fiberglass Reinforced Plastic</div> <div style="clear:both;"></div> <div style="float:right;">Unknown</div> <div style="clear:both;"></div> <div style="float:right;">Other, Please Specify _____</div> <div style="clear:both;"></div>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<b>5. Internal Protection</b> (Mark all that apply) <div style="float:right;">Cathodic Protection</div> <div style="clear:both;"></div> <div style="float:right;">Interior Lining (e.g., epoxy resins)</div> <div style="clear:both;"></div> <div style="float:right;">None</div> <div style="clear:both;"></div> <div style="float:right;">Unknown</div> <div style="clear:both;"></div> <div style="float:right;">Other, Please Specify _____</div> <div style="clear:both;"></div>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<b>6. External Protection</b> (Mark all that apply) <div style="float:right;">Cathodic Protection</div> <div style="clear:both;"></div> <div style="float:right;">Painted (e.g., asphaltic)</div> <div style="clear:both;"></div> <div style="float:right;">Fiberglass Reinforced Plastic Coated</div> <div style="clear:both;"></div> <div style="float:right;">None</div> <div style="clear:both;"></div> <div style="float:right;">Unknown</div> <div style="clear:both;"></div> <div style="float:right;">Other, Please Specify _____</div> <div style="clear:both;"></div>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<b>7. Piping</b> (Mark all that apply) <div style="float:right;">Bare Steel</div> <div style="clear:both;"></div> <div style="float:right;">Galvanized Steel</div> <div style="clear:both;"></div> <div style="float:right;">Fiberglass Reinforced Plastic</div> <div style="clear:both;"></div> <div style="float:right;">Cathodically Protected</div> <div style="clear:both;"></div> <div style="float:right;">Unknown</div> <div style="clear:both;"></div> <div style="float:right;">Other, Please Specify _____</div> <div style="clear:both;"></div>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<b>8. Substance Currently or Last Stored in Greatest Quantity by Volume</b> (Mark all that apply) <div style="float:right;"><b>a. Empty</b></div> <div style="clear:both;"></div> <div style="float:right;"><b>b. Petroleum</b></div> <div style="clear:both;"></div> <div style="float:right;">Diesel</div> <div style="clear:both;"></div> <div style="float:right;">Kerosene</div> <div style="clear:both;"></div> <div style="float:right;">Gasoline (including alcohol blends)</div> <div style="clear:both;"></div> <div style="float:right;">Used Oil</div> <div style="clear:both;"></div> <div style="float:right;">Other, Please Specify _____</div> <div style="clear:both;"></div> <div style="float:right;"><b>c. Hazardous Substance</b></div> <div style="clear:both;"></div> <div style="float:right;">Please Indicate Name of Principal CERCLA Substance OR Chemical Abstract Service (CAS) No.</div> <div style="clear:both;"></div> <div style="float:right;">Mark box <input checked="" type="checkbox"/> if tank stores a mixture of substances</div> <div style="clear:both;"></div> <div style="float:right;"><b>d. Unknown</b></div> <div style="clear:both;"></div>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	<input type="checkbox"/>	Vm-P Naphtha 8030306	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<b>9. Additional Information (for tanks permanently taken out of service)</b> <div style="float:right;">a. Estimated date last used (mo/yr)</div> <div style="clear:both;"></div> <div style="float:right;">b. Estimated quantity of substance remaining (gal.)</div> <div style="clear:both;"></div> <div style="float:right;">c. Mark box <input checked="" type="checkbox"/> if tank was filled with inert material (e.g., sand, concrete)</div> <div style="clear:both;"></div>	4 / 89	4 / 89	/	/	/
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>